

**A LIMITED ENERGY STUDY OF
HIGH TEMPERATURE AND CHILLED WATER DISTRIBUTION SYSTEMS
AT FORT STEWART AND HUNTER ARMY AIRFIELD, GEORGIA**

**VOLUME II
APPENDICES**

FINAL SUBMITTAL


Prepared For
Savannah District, Corps of Engineers

Contract Number DACA01-94-D-0038
Delivery Order Number 0002

Prepared by
Reynolds, Smith and Hills, Inc.
4651 Salisbury Road
Jacksonville, Florida 32256
(904) 296-2000



Carlos S. Warren, PhD, PE
Project Manager



William T. Todd, PE
Field Survey Manager

September 6, 1996


6941331002

DISTRIBUTION STATEMENT A


Approved for public release
Distribution Unlimited



Forces Command



3rd Infantry Division
Fort Stewart



Savannah District
Corps of Engineers

RS&H

Reynolds, Smith and
Hills, Inc.




DEPARTMENT OF THE ARMY
CONSTRUCTION ENGINEERING RESEARCH LABORATORIES, CORPS OF ENGINEERS
P.O. BOX 9005
CHAMPAIGN, ILLINOIS 61826-9005

REPLY TO

ATTENTION OF: TR-I Library

17 Sep 1997

Based on SOW, these Energy Studies are unclassified/unlimited.
Distribution A. Approved for public release.


Marie Wakefield,
Librarian Engineering

DTIC COULD NOT GET MISSING
PAGE FROM CONTRIBUTOR

A 6-6

TABLE OF CONTENTS

Volume	Section	Title	Page
ES		EXECUTIVE SUMMARY	
	1.0	INTRODUCTION	ES.1-1
	2.0	FACILITY DESCRIPTION	ES.2-1
	3.0	METHODOLOGY	ES.3-1
	4.0	ANALYSIS	ES.4-1
	5.0	RESULTS AND RECOMMENDATIONS	ES.5-1
I		NARRATIVE REPORT	
	1.0	INTRODUCTION	
		1.1 Authorization	1-1
		1.2 Objectives	1-1
		1.3 Work Accomplished	1-1
	2.0	FACILITY DESCRIPTION	
		2.1 General Description	2-1
		2.2 Central Energy Plant	2-1
		2.3 Satellite Energy Plant	2-1
		2.4 HTW Distribution Systems	2-1
	3.0	METHODOLOGY	
		3.1 General	3-1
		3.2 Quantify HTW Losses	3-1
		3.3 Locate Leaks in Underground HTW Piping	3-5
		3.4 Field Investigation Schedule	3-6
		3.5 Utility Rates	3-8
	4.0	ANALYSIS	
		4.1 Historical Make-Up Water Use	4-1
		4.2 Estimate of HTW Losses	4-9
		4.3 Water Quality and Treatment	4-16
		4.4 Evaluation of Energy Conservation Projects	4-19
	5.0	RESULTS AND RECOMMENDATIONS	
		5.1 Summary of ECO Evaluations	5-1
		5.2 O&M Recommendations	5-4

BIC QUALITY INSPECTED &

9/96

19971022 142

TABLE OF CONTENTS (continued)

Volume	Section	Title	Page
I	6.0	FEMP PROJECT PROGRAMMING DOCUMENTS	
		6.1 Repair CEP and SEP HTW and Steam Leaks (ECO-4)	6.1-1
		6.2 Repair HTW Leaks in Mechanical Rooms (ECO-5)	6.2-1
		6.3 Repair HHW Leaks in Mechanical Rooms (ECO-6)	6.3-1
		6.4 Repair HTW Leaks in Valve Pits (ECO-7)	6.4-1
		6.5 Distribute HTW from the CEP to the SEP (ECO-10A)	6.5-1
		6.6 Use Leak Locator Equipment (ECO-11)	6.6-1
		6.7 Reduce Operating Pressure to 60 psig (ECO-12B)	6.7-1
	7.0	LOW COST/NO COST PROJECT DOCUMENTATION	
		7.1 Reduce Blowdown (ECO-2)	7.1-1
		7.2 Reduce Soot Blowing (ECO-3)	7.2-1
		7.3 Improve SEP Start-Up Procedure (ECO-9A)	7.3-1
		7.4 Reduce Operating Pressure to 100 psig (ECO-12A)	7.4-1
II	A	APPENDICES	
		A.1 Scope of Work	A.1-1
		A.2 HTW Distribution System Map	A.2-1
		A.3 ECO Energy and Cost Calculations	A.3-1
		A.4 HTW Loss Calculations	A.4-1
		A.5 Energy Data, Boiler Logs and Make-Up Water Data	A.5-1
		A.6 Results of Analysis of HTW and DHW Samples	A.6-1
		A.7 Submittal Review Comments and Review Actions	A.7-1
		A.8 List of Abbreviations and Acronyms	A.8-1
		A.9 Correspondence and Meeting Notes	A.9-1
		A.10 Records Analysis and Site Survey Plan	A.10-1
III	B	FIELD INVESTIGATION FORMS	
		B.1 Valve Pit Valves and Fittings Survey Forms	
		B.2 Mechanical Equipment Room Survey Forms	
		B.3 CEP and SEP Survey Forms	
		B.4 HTW Distribution System Survey Forms	

A.1 SCOPE OF WORK

APPENDIX A
for Delivery Order No. 2,

A LIMITED ENERGY STUDY OF HIGH TEMPERATURE AND CHILLED WATER
DISTRIBUTION SYSTEMS AT FORT STEWART AND HUNTER ARMY AIRFIELD, GA

1. BRIEF DESCRIPTION OF WORK:

The Architect-Engineer (A-E) shall perform the following:

1.1 Field Investigation.

1.1.1 High Temperature Water (HTW) Distribution Systems. Develop a plan for and conduct a field survey to identify points or areas in the HTW distribution system at Fort Stewart where energy leaks occur, describe and estimate the cost of the Energy Conservation Opportunities (ECO's) to close these leaks in the most technically sound and cost-effective manner for the long-term, and perform a Life Cycle Cost Analysis (LCCA) to determine whether any or all of the recommended ECO's qualify for funding under the criteria for the Federal Energy Management Program (FEMP) or the Energy Conservation Investment Program (ECIP). At Hunter Army Airfield (HAAF) the A-E will review all available data and records for both the Central Energy Plant (CEP) and the pinwheel barracks energy plant and interview all personnel that the Fort Stewart Energy Officer (FSEO) can direct him to. Based on an analysis of the gathered information, the A-E will recommend whether or not further study of the HAAF HTW distribution systems should be programmed for the future.

1.1.2 Chilled Water (CHW) Distribution Systems. Review all data and records related to the Fort Stewart CHW distribution system and interview all personnel that the FSEO can direct him to. Based on this review, the A-E will make a recommendation as to whether or not a field investigation of the CHW system is needed. For HAAF the A-E will review all available records and data for both the CEP and the pinwheel barracks energy plant and interview all personnel that the FSEO can direct him to. Based on an analysis of the gathered information, the A-E will recommend whether or not further study of the HAAF CHW distribution systems should be programmed for the future.

1.2 Project Identification and Documentation. The A-E is instructed to fully analyze and document one particular alternative for the Fort Stewart HTW distribution system: complete replacement of the existing distribution lines with a shallow trench distribution system. Other alternatives or projects will be identified by the A-E or government reviewers as a result of the study, and the A-E will provide complete programming or implementation documentation for all recommended projects, which may be individual ECO's or more than one ECO combined. Guidance from the participants in this project from Fort Stewart and Forces

Command (FORSCOM) will be given to the A-E at the interim submittal review stage as to how best to package ECO's for funding purposes.

1.3 Study Report. Provide a comprehensive report to document all work performed, the results and conclusions, and all recommendations.

2. SPECIFIC INSTRUCTIONS:

2.1 Field Investigation.

2.1.1 Plan for the field investigation. Prior to beginning any detailed system investigations at Fort Stewart, the A-E will be required to develop and submit for the other project team members' information a plan of action for the actual field work. As a minimum, it will include a weekly schedule of anticipated events, the techniques that will be used for surveying underground distribution lines, and a map annotated to depict the plan of attack for surveying the full length of all distribution lines and other distribution system components from the points of departure out of the Central Energy Plant (CEP) to the points of connection to each facility that is an end user of the energy supplied by the plant. In order to accomplish this, the A-E will be required to visit the installation and:

2.1.1.1 Obtain a complete set of distribution system maps for Fort Stewart and HAAF. These will be annotated in the field during the detailed survey of the distribution systems. All inaccuracies or changes that are noted will be posted to the field maps. These annotated maps will be part of the interim submittal.

2.1.1.2 Review records of work orders and service orders, obtainable from the Resource Management Divisions and/or the Facilities Engineering Divisions at the respective installations, for the most recent twelve month period. This will assist the A-E in defining the areas most suspected of having energy leaks, where he may need to concentrate more of his field effort.

2.1.1.3 Interview personnel assigned to both Fort Stewart and HAAF most knowledgeable about the distribution systems, starting with the responsible division chiefs and proceeding through the organizational chain of command to the line workers responsible for operation, maintenance, and repair of the systems.

2.1.1.4 Review logs of make-up water volumes at the CEP. This study is directed to the correction of energy losses in the distribution system. Some investigation of equipment in the central plant and in the buildings served by the system may be necessary to apportion makeup water usage among the distribution system, the CEP, and the building mechanical rooms. Sufficient field time should be devoted to these areas to gather the needed information.

2.1.2 Field survey.

2.1.2.1 The A-E will send sufficient personnel to the installations to complete the detailed field survey in the least amount of time possible. Contractor-developed forms designed to speed the process of conducting the field survey and contractor-controlled equipment and vehicles shall be available in adequate numbers to insure that the field crew(s) are never deadlined.

2.1.2.2 There will be a field survey manager appointed who will serve as the on site point of contact, who will be fully knowledgeable of the previous planning effort for the field survey, and who will serve in this capacity from beginning to end of the field survey. This individual will be required to report to the FSEO, or his project manager at the Savannah District, on a weekly basis. The field manager will have the authority to make those decisions necessary to finish the work in a thorough, high quality, and timely manner.

2.1.2.3 There are several non-destructive inspection techniques that can be employed to gather the information to pinpoint the sections in the systems where insulation has deteriorated to the degree that hot or cold spots are apparent, where water under pressure is leaking from lines or other parts of the system to include equipment in above ground components such as valve pits, or where energy losses in the system are occurring for other reasons. These include visual inspection, flow metering, infrared thermography, ground penetrating radar, SF6 leak detection, and video inspection. Other techniques with which the Contractor may have more familiarity or the technology for which has more recently been developed will be acceptable if they will produce the desired results and if they are identified in the plan for the field survey. The A-E will be responsible for the timing and coordination of the inspections and any peculiar requirements of a particular type and will be required to have his own equipment with which to perform the inspections by whatever technique(s) he chooses. The A-E will also be responsible for insuring that all safety standards are followed.

2.2 Project Identification and Documentation. All assumptions, formulas, input and output values, and the actual calculations used in generating project cost estimates and savings will be included with each ECO. All energy conservation opportunities or projects which the A-E has considered shall be included in one of the following categories and presented in the report as such:

2.2.1 Federal Energy Management Program (FEMP) Projects: Every attempt will be made to keep all projects within the Installation Commander's funding approval authorities applicable to the Operations and Maintenance, Army (OMA) account. These limitations are generally \$300,000 for a project classified as construction and \$1,000,000 for projects classified as maintenance

or repair, as defined in reference 9.2 and modified by reference 9.10. There is a special source of OMA funding called the FEMP that can generally provide funding for energy savings type projects, the cost of which are estimated to fall below these limitations, on a one year cycle or less, if a project is properly justified. To be classified as an OMA Energy maintenance or repair project, the project must result in needed maintenance or repair to an existing facility or replace a failed or failing system or component and result in energy savings. If the project would replace a system or component that is considered failed or failing due solely to obsolete technology or inefficiency, the system or component to be replaced must have been in use for at least three years and the simple payback period must be ten years or less. So long as the work can be logically separated and identified, projects can be combined in one undertaking. Any recommended project must have, as a minimum, a Savings to Investment Ratio (SIR) of 1.25 and a simple payback period of 10 years or less. The documentation required for each project is the life cycle cost analysis (LCCA) summary sheet completely filled out, a description of the work to be accomplished, backup data for the LCCA (i.e., energy and non-energy savings calculations and cost estimate), the SIR, and the simple payback period. The documentation of these projects will be a part of the study report described below.

2.2.2 Energy Conservation Investment Program (ECIP) Projects.

If a project cost estimate is greater than the limitations mentioned above, then the project becomes an ECIP project by definition. An ECIP project is one that proposes new construction or a retrofit of an existing facility for the purpose of conserving energy. In an ECIP project, savings may come from energy, demand, operations and maintenance, other factors, or a combination of the above. In addition to the cost threshold, a project must also have an SIR greater than 1.25 and a simple payback period of less than ten years to meet the minimum criteria for ECIP projects. Where ECO's have been combined into one ECIP project, each discrete part must meet the SIR and simple payback criteria. Programming documentation shall consist of a DD Form 1391 and an LCCA summary sheet with necessary backup data to verify the numbers presented. An LCCA summary sheet shall be developed for each ECO and for the overall project when more than one ECO have been combined.

2.2.3 Low Cost/No Cost Projects.

These are projects which the DPW can complete using his in-house work force. Minimum documentation will consist of a description of the project, a sketch of the location and the work required, a rationale for why the project is recommended, and a cost estimate. Other project documentation requirements may be added by the FSEO.

2.2.4 Nonfeasible ECO's.

All ECO's which the A-E has considered but which are not feasible shall be documented in the report with reasons and justifications showing why they were rejected.

2.3 Study Report. The work accomplished shall be fully documented by a comprehensive report. While the cost of report production is certainly a consideration, the report submittals must be well organized and lend themselves to quick and easy review because the installation staff will have only limited time available for this. The A-E is expected to compile the information for the submittals in a logical sequence and must take great care to consider the reader's point of view. Spelling, grammar, and punctuation will be checked prior to making a submittal; and, for clarity, highly technical terms will be explained. Before making copies for each submittal, the report will be proofread and critiqued by an employee of the firm not familiar with the project to insure good readability. Just as important as any other part of the effort, the A-E must be concise in conveying the key information to the customer. Following these rules will help to insure that the A-E's credibility will not suffer and that his technical capabilities will not be questioned.

The interim submittal may be copied and bound in the most convenient and least expensive manner, so long as it meets the criteria above. The pre-final report will be organized, tabbed, copied, and bound in the exact manner which the A-E proposes to produce the final report. Review of both submittals will include comments on the report's organization and flow of thought. The final report will incorporate all earlier comments and, if the pre-final report is produced properly, will be produced by page for page replacement in or page addition to the pre-final report. A high quality 3-ring binder will be used to package the pre-final report.

For easy reading line length on the printed page is a consideration. It may be advisable to use a two column format to accomplish this. The pages of the original copy will be laser printed. Xeroxed copies on high quality paper are acceptable so long as there is essentially no discernible difference between them and the original. A title page will be inserted in a sleeve on the front cover and will contain a photograph descriptive of the report contents. The inside title page will also incorporate logos and credits to the A-E and the offices which have played a role in development of the study and report, particularly the installation. This will be followed by a table of contents. Each section, subsection, and appendix shall be separated by a thick paper divider tabbed with the section name and number. Each page will be numbered with a section number followed by a dash and a page number.

A separately bound Executive Summary of the study, giving a brief overview of the conclusions and recommendations using graphs, tables, and charts as much as possible, will be prepared as part of the final submittal. For clarity, color will be used in these graphic elements or any others that appear in the report. The body of the report itself--i.e., that portion where the technical analysis, conclusions, and recommendations are developed--shall be organized in a logical manner and written simply enough for a person not an expert in the field to follow the line of reasoning for each project. All project documentation will be presented in this portion of the report. Appendices will include as a minimum

the Scope of Work for this D.O., minutes of meetings, and survey forms. Any other appendices that the A-E thinks will assist in making the report better and more organized are also encouraged. If acronyms are used, there will be a list of each one used with a definition.

3. SERVICES AND MATERIALS: All services, materials (except those specifically enumerated to be furnished by the Government), plant, labor (including that required to research installation records or databases to obtain all information needed to perform a thorough study), equipment, supervision, and travel necessary to complete the work and render the data required under this D.O. are to be included in the lump sum price.

4. GENERAL:

4.1 The information and analysis outlined herein are considered to be minimum requirements for adequate performance of this study. The A-E is encouraged to use his specialized knowledge in this field to provide additional information which will help the installation justify energy improvement projects.

4.2 For the distribution systems described above all methods of energy conservation which are reasonable and practical shall be considered, including improvements of operational methods and procedures as well as the physical facilities. All systems improvements that are considered during the study will be documented in the report, including those that are rejected because they are considered infeasible with reasons given for elimination. If, under another set of assumptions, an infeasible project will become feasible, then so state. For example, if using in-house labor to perform work would be less costly than using contract labor, and this change would result in meeting the SIR and payback criteria, then document this.

4.3 The "Energy Conservation Investment Program (ECIP) Guidance," described in a letter from DAIM-FDF-U, dated 10 Jan 1994, and any subsequent revisions establish criteria for ECIP projects and shall be used for performing the economic analyses associated with these projects. The software program, Life Cycle Cost in Design (LCCID), has been developed for performing life cycle cost calculations in accordance with ECIP guidelines and is referenced in the ECIP guidance. If any program other than LCCID is proposed for life cycle cost analysis, it must use the mode of calculation specified in the ECIP guidance. The output must be in the format of the ECIP LCCA summary sheet, and it must be submitted for approval to the Contracting Officer. The LCCID program is available from the BLAST Support Office at 144 Mechanical Engineering Building, 1206 West Green Street, Urbana, Illinois 61901 for a nominal fee. The telephone number is (217) 333-3977 or (800) 842-5278.

4.4 The A-E shall take great care to insure that the FSEO is kept apprised of the ongoing work, either directly or through periodic contact with his Savannah District project manager. The final recommended projects will be both technically and economically feasible and will be acceptable to the FSEO.

4.5 Public Disclosures. The A-E shall make no public announcements or disclosures relative to information contained or developed in this contract, except as authorized by the Contracting Officer.

4.6 Meetings. Meetings will be scheduled whenever requested by the A-E or the government's representative acting for the installation project manager for the resolution of questions or problems encountered in the performance of the work. These meetings, if necessary, will be in addition to the scheduled review meetings and presentations.

4.7 Site Visits, Inspections, and Investigations. The Contractor shall visit and inspect/investigate the site of the projects as necessary and required during the preparation and accomplishment of the work. Visits will be coordinated with the FSEO at least a week in advance. The A-E will determine whether any special security clearances are required with the assistance of the FSEO.

4.8 All invoices or payment estimates (ENG Form 93) will be sent to the Savannah District project manager, who is identified below in paragraph 5.4, for review and approval.

4.9 Records.

4.9.1 The A-E shall provide a record of all significant conferences, meetings, discussions, verbal directions, telephone conversations, etc., with government personnel relative to this project in which the A-E has participated. These records shall be dated and shall identify the contract and D.O. number, participating personnel, subject discussed, and conclusions reached. The A-E shall forward by letter to the list of P.O.C.'s in paragraph 5 within ten calendar days of the event a reproducible copy of the records. These will also be included in the study report as an appendix.

4.9.2 The A-E should expect to provide the manpower needed for, and should base his fee proposal on, gathering all information himself required to complete the study. But, if the A-E faces a situation where he must request the installation's assistance, then he shall provide a record of requests for and/or receipt of Government-furnished material, data, documents, information, etc., which if not furnished in a timely manner, would significantly impair the normal progression of the work under this D.O. The records shall be dated and shall identify the contract and D.O. number. The A-E shall forward to the Savannah District project manager within ten calendar days a reproducible copy of the record

of request or receipt of material.

4.10 Briefings. The A-E and the Savannah District project manager shall conduct entry and exit interviews with the DPW, or his designated representative as instructed by the FSEO, before starting work at the installation and after completion of the study.

4.10.1 Entry. The entry interview shall describe the purpose of the study, the intended procedures for the survey, the schedule, names of personnel performing the field investigation and the A-E's project manager, support required by the A-E of the DPW staff, a description of the final products, and any other information the A-E wishes to communicate and shall be conducted prior to commencing work at the installation.

4.10.2 Exit. The exit interview shall describe the items surveyed, an assessment of the condition of existing systems, and the results and conclusions of the analysis.

5. PROJECT MANAGEMENT:

5.1 The A-E shall designate a project manager, in addition to the field survey manager mentioned above, who will serve as the primary P.O.C. and liaison for work required under this D.O. If the A-E chooses, the same person can serve in both capacities but must be on site throughout the field survey. Upon award of this D.O., the individual shall be immediately designated in writing. The A-E's designated project manager shall be approved by the Contracting Officer prior to commencement of work. The project manager will be responsible for coordination of work required under this D.O. The A-E's project manager shall submit monthly progress reports, typically in conjunction with pay requests, and shall telephonically update the Savannah District project manager on project events about every two weeks between pay requests. Immediately upon award of this D.O., the A-E's project manager will submit a project schedule substituting dates for calendar days, with an assumed 28 calendar day government review period after each submittal.

5.2 The Fort Stewart Energy Officer and installation project manager for this effort is Doug Swanson, telephone number (912) 767-7925, FAX number (912) 767-9779. He will assist the A-E in obtaining information and establishing contacts necessary to accomplish the work required under this D.O.

5.3 The U.S. Forces Command program manager is Naresh Kapur, telephone number (404) 669-5327, FAX number (404) 669-7751.

5.4 The U.S. Army Corps of Engineers, Savannah District, project manager is Rob Callahan, telephone number (912) 652-5246, FAX number (912) 652-5442.

5.5 The U.S. Army Corps of Engineers, Savannah District, Contracting Officers Representative is Tom Clarke, telephone number (912) 652-5364, FAX number (912) 652-5090.

5.6 The U.S. Army Corps of Engineers, Mobile District, is the Army's designated Technical Center of Expertise for the Energy Engineering Analysis Program. Mobile District's program manager is Tony Battaglia, telephone number (205) 690-2618, FAX number (205) 690-2424.

6. SUBMITTALS, PRESENTATIONS, AND REVIEWS:

6.1 Interim Report Submittal. An interim report, which will include all field notes, shall be submitted for review after the field survey has been completed and an analysis has been performed on all of the ECO's. The report shall indicate the work which has been accomplished to date, illustrate the methods and justifications of the approaches taken and contain a plan for the work remaining to complete the study. One copy of the interim report shall be submitted for review to the FORSCOM and Mobile District P.O.C.'s. Two copies of the report shall be submitted to the Fort Stewart and Savannah District P.O.C.'s. Calculations showing energy and dollar savings, SIR, and simple payback period of all the ECO's shall be included. The results of the ECO analyses shall be summarized by lists as follows:

6.1.1 All ECO's eliminated from consideration shall be grouped into one listing with reasons for their elimination as discussed in paragraph 2.2.4.

6.1.2 All ECO's which were analyzed shall be grouped into two listings, recommended and non-recommended, each arranged in order of descending SIR. These lists may be subdivided by location or area as appropriate for the study.

6.1.3 The A-E shall make a presentation of the report at a review conference. Visual aids or other methods of presentation will be at the A-E's discretion to make understanding by those present easier.

6.2 Pre-final Report Submittal. The A-E shall prepare and submit the pre-final report when he believes all work under this D.O. is essentially complete. The report will be formatted and bound exactly as the A-E proposes to format the final report. All project documentation shall be completed and included in the report. All comments resulting from review of the interim submittal or from the presentation shall have been addressed in compiling this report, and review action comments related to the interim report shall be included in a separate appendix keyed to sections of the pre-final report where the appropriate changes have been made. The same number of copies shall be sent to the same offices as specified above for the interim report.

6.3 Final Report. Any revisions or corrections resulting from comments made during the review of the pre-final report will be able to be incorporated by page for page replacement in or page addition to the pre-final report, if it has been produced in accordance with these instructions. All instructions on organization and formatting shall be strictly followed. A separately bound Executive Summary will be prepared, as described above in paragraph 2.3. One copy each of the final submittal shall be sent to the FORSCOM and Mobile District P.O.C.'s; two copies each shall be sent to the Savannah District P.O.C.; and three copies, along with the original, shall be sent to the Fort Stewart P.O.C. In addition one copy each of only the Executive Summary shall be sent to the Corps of Engineers, South Atlantic Division, P.O.C., the U.S. Army Logistics Evaluation Agency P.O.C., and to the HQUSACE P.O.C. listed below in paragraph 8.

7. PROJECT SCHEDULE:

<u>Milestone</u>	<u>Date</u>
Entry interview and begin gathering information	NLT 14 days after award of this D.O.
A-E submits recommendations on further studies and field survey plan	NLT 42 days after award of this D.O.
A-E begins field survey	As described in field survey plan
A-E completes field survey	As described in field survey plan
A-E submits interim report	NLT 154 days after completion of field survey
Interim submittal review meeting and presentation	NLT 7 days after completion of government review
A-E submits pre-final report	NLT 56 days after interim submittal review meeting
A-E submits final report	NLT 28 days after receipt of government review comments on pre-final
Exit briefing	NLT 14 days after submitting final report

8. POINTS OF CONTACT:

Commander
24th Infantry Division and Fort Stewart
ATTN: AFZP-DEV (~~Mr. Doug Swanson~~) (Mr. Tim Harper.)
Fort Stewart, GA 31314

Commander
U.S. Army Forces Command
ATTN: AFPI-ENO (Mr. Naresh Kapur)
Fort McPherson, GA 30330

Savannah District, Corps of Engineers
ATTN: CESAS-PM-MR (Mr. Rob Callahan)
100 W. Oglethorpe Avenue
P.O. Box 889
Savannah, GA 31402-0889

Mobile District, Corps of Engineers
ATTN: CESAM-EN-DM (Mr. Tony Battaglia)
P.O. Box 2288
Mobile, AL 36628-0001

Commander
U.S. Army Engineer Division, South Atlantic
ATTN: CESAD-EN-TE (Mr. Baggette)
77 Forsyth Street, SW
Atlanta, GA 30335-6801

Commander
U.S. Army Corps of Engineers
ATTN: CEMP-ET (Mr. Gentil)
20 Massachusetts Avenue, NW
Washington, DC 20314-1000


Commander
U.S. Army Logistics Evaluation Agency
ATTN: LOEA-PL (Mr. Keath)
New Cumberland Army Depot
New Cumberland, PA 17070-5007


9. REFERENCES:

- 9.1 Architect and Engineer Instructions, 9 Dec 91
- 9.2 AR 420-10, Management of Installation Directorates of Engineering and Housing, 2 Jul 87
- 9.3 AR 415-15 (DRAFT), Army Military Construction Program Development and Execution
- 9.4 Energy Conservation Investment Program (ECIP) Guidance, 10 Jan 94
- 9.5 TM 5-785, Engineering Weather Data
- 9.6 TM 5-800-4, Programming Cost Estimates for Military Construction, Feb 94
- 9.7 General Energy Conservation Opportunities
- 9.8 Required DD Form 1391 Data
- 9.9 AR 11-27, Army Energy Program, 14 Jul 89
- 9.10 TWX dated 111600Z Jul 94 from DAIM-FDF-B, subject: Future Change to AR 420-10


A.2 HTW DISTRIBUTION SYSTEM MAP

A.2-1













LEG




- C-(
- I-II
- M-I
- A-A



LEGEND





SCALE IN FEET
CONTOUR INTERVAL = 2'




CREEK

E 664,000
E 664,000



BAYONET
CONFIDENCE



MILL

STORAGE
BLDG

TACTICAL
EQUIPMENT
SHOP

WASHRACK

SENTRY
STATION

VP-S-13


PKG


STORAGE BLDG



POL STORAGE
BLDG



TOWER


⑦























VP-2S-8
2-10" HTW
2-24" COW

VP-2S-9
VP-2S-10
VP-2S-11

BURGER KING

EDUCATION CENTER

AOP BLDG

POST HQ

HELIPAD

GAS PEAK SHAVING PLANT

CIDC FIELD OPERATIONS

VETERINARY CLINIC

INCINERATOR


BULTMAN

AVENUE

GA HWY. NO 36

ERALS CREEN WAY

16



VP-S-6

LITE
GY
IT
7

USAR
EQUIPMENT
POINT
LOADING
DOCK

TOWER

W 6TH STREET

F.S. 90

MILL


N.676,000 N-676,000


WEIGH SCA


CONC. STO
BINS

CONC. LOAD
DOCK

CONFORMING
STORAGE BLDG -







FORT STE

- SL
- PHASE I -
 - PHASE II -
 - PHASE III -

RS
 Reynolds, Smith and
 Architectural, Engine



FORT STEWART HTW SYSTEM

SURVEY PLAN

PHASE I - CEP, SEP & MECH. RMS ☐

PHASE II - VALVE & DRAIN PITS ☐

PHASE III - DISTRIBUTION SYSTEMS

ZONE 1 DIST. SYSTEM ☐

ZONE 2 DIST. SYSTEM ☐

ZONE 3 DIST. SYSTEM ☐

SEP DISTRIB. SYSTEM ☐

RS&H

Reynolds, Smith and Hills, Inc.
Architectural, Engineering, Planning and Environmental Services

A.3 ECO ENERGY AND COST CALCULATIONS

ECO NUMBER 1

**REPLACEMENT OF THE EXISTING HTW DISTRIBUTION LINES WITH A NEW
SHALLOW TRENCH DISTRIBUTION SYSTEM**

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-1

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-1 REPLACE THE HTW DISTRIBUTION SYSTEM

FISCAL YEAR 1995 DISCRETE PORTION NAME: SHALLOW TRENCH HTW PIPING

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST \$ 21975320.
 B. SIOH \$ 1318519.
 C. DESIGN COST \$ 1318519.
 D. TOTAL COST (1A+1B+1C) \$ 24612360.
 E. SALVAGE VALUE OF EXISTING EQUIPMENT \$ 0.
 F. PUBLIC UTILITY COMPANY REBATE \$ 0.
 G. TOTAL INVESTMENT (1D - 1E - 1F) \$ 24612360.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	7.	\$ 89.	15.08	\$ 1347.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	177890.	\$ 238373.	14.88	\$ 3546985.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		177897.	\$ 238462.		\$ 3548331.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)
 (1) DISCOUNT FACTOR (TABLE A) 14.88
 (2) DISCOUNTED SAVING/COST (3A X 3A1) \$ 131792.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
------	------------------------------	-----------------	------------------------	---

d. TOTAL \$ 0. 0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 131792.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 247319.

5. SIMPLE PAYBACK PERIOD (1G/4) 99.52 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 3680124.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .15
 (IF < 1 PROJECT DOES NOT QUALIFY)

ECO Number 1

Replacement of the existing HTW distribution lines with a new shallow trench distribution system.

Description

This project consists of replacing the existing underground HTW piping system with a new shallow trench distribution system. The existing HTW piping could be demolished and removed or it could be abandoned in place. The cost estimate and economic analysis assumes the existing HTW piping will be removed and sold for scrap. The new HTW piping design call for Schedule 80 steel pipe with welded joints. The new HTW pipe will be insulated with calcium silicate, installed inside a metal conduit and positioned in a shallow trench.

Analysis

This project is specifically called for by the scope of work, however, our surveys and analysis have indicated that the losses due to HTW leaks from the underground distribution system average only about 2.53 GPM which is 1,329,800 gallons per year. These losses are low considering the length and age of the piping system. However, there are substantial heating energy losses due to deteriorated and moist insulation.

Light steam flow and dripping was observed at many of the HTW conduit vent pipes during the valve pit survey. Since the estimated leaks in the HTW system were so low, it was assumed that the steam was being produced by ground water leaking into the HTW conduit. The conductivity of the insulation will increase dramatically with the introduction of moisture. A study of buried pipes for the district heating system at Fort McClellan estimated the heat transfer rates to be 55 Btu/Hr•LF for dry, insulated buried pipes and 275 Btu/Hr•LF for buried pipes with entrapped moisture and deteriorated insulation. The energy savings calculations assume that approximately one-half of the total length of HTW piping at Fort Stewart has deteriorated and moist insulation.

A small amount of energy and water savings are achieved by reducing the HTW losses from 2.53 GPM to approximately 0.10 GPM. The savings calculations and economic analysis assume an average of two leaks in the HTW piping each year and an average HTW loss of 20,000 gallons per leak.

The operation and maintenance savings associated with the need to repair about two HTW leaks per year is included in the economic analysis. The operation and maintenance cost includes trench excavation, HTW pipe repair and backfilling of the trench. Lengths and sizes of HTW piping used for energy savings calculations and cost estimates were taken from drawings titled Fort Stewart Central Heating and Cooling - Existing Conditions.



SUBJECT FORT STEWART
Replace HTW Piping
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF 4
DATE 2-7-96
DATE _____

ECO-1 REPLACE HTW PIPING

Heat Loss from Buried Pipe

Assumptions:

- 1) Total length of supply and return pipe = 122000 LF
- 2) About 1/2 of the piping has deteriorated insulation and entrapped moisture.
- 3) Average HTW pipe diameter is 6"
- 4) Average HTW supply temp. = 350 °F
- 5) Average HTW return temp. = 200 °F
- 6) HTW pipes have 4" of calcium silicate insulation
- 7) Heat loss from dry, insulated, buried pipes is about 55 Btu/HR·LF (see #9)
- 8) Heat loss from buried pipes with entrapped moisture and deteriorated insulation is 275 Btu/HR·LF (see #9)
- 9) Source is Ft. McClellan Study, see attached pages
- 10) Average ground temperature ≈ 70 °F
- 11) Average boiler efficiency 68 percent

Current Heat Loss:

$$122000 \text{ LF} \times 0.5 \times 55 \text{ Btu/HR·LF} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 3.355 \text{ MBtu/HR}$$

$$122000 \text{ LF} \times 0.5 \times 275 \text{ Btu/HR·LF} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 16.775 \text{ MBtu/HR}$$

$$\text{Annual Heat Loss} = \left(3.355 \frac{\text{MBtu}}{\text{HR}} + 16.775 \frac{\text{MBtu}}{\text{HR}} \right) \times 8760 \frac{\text{HR}}{\text{YR}}$$

$$\text{Current annual heat loss} = 20.13 \frac{\text{MBtu}}{\text{HR}} \times 8760 \frac{\text{HR}}{\text{YR}} = 176340 \frac{\text{MBtu}}{\text{YR}}$$

$$\text{Current fuel use} = 176340 \frac{\text{MBtu}}{\text{YR}} \div 0.68 = \underline{259320 \frac{\text{MBtu}}{\text{YR}}}$$



SUBJECT Fort Stewart
Replace HTW Piping
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF 4
DATE 2-7-96
DATE _____

ECO-1 REPLACE HTW PIPING

Heat loss w/ New Piping System

$$122\,000 \text{ LF} \times 55 \frac{\text{Btu}}{\text{HR} \cdot \text{LF}} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 6.71 \text{ MBtu/HR}$$

$$\text{Annual heat loss} = 6.71 \frac{\text{MBtu}}{\text{HR}} \times 8760 \frac{\text{HR}}{\text{YR}} = 58780 \frac{\text{MBtu}}{\text{YR}}$$

$$\text{Current Fuel use} = 58780 \frac{\text{MBtu}}{\text{YR}} \div 0.68 = \underline{86,440 \frac{\text{MBtu}}{\text{YR}}}$$



SUBJECT Fort Stewart
Replace HTW Piping
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 3 OF 4
DATE 2-7-96
DATE _____


ECO-1 Replace HTW Piping W/o Leak Correlator

Assume $\frac{1}{3}$ of the distance between valve pits must be dug up before the leak is found.

Average distance between valve pits:

$$\frac{9100 \text{ LF} + 4600 \text{ LF} + 6700 \text{ LF} + 17400 \text{ LF} + 8750 \text{ LF}}{95 \text{ Valve Pits}} = 490 \text{ LF/pit}$$

Area of excavation: Assume



$$6' \times 11' \times 490' \times \frac{1}{3} = 10780 \text{ CF} \div 27 \frac{\text{CF}}{\text{CY}} = 399 \Rightarrow 400 \text{ CY}$$

$$\text{Excavation: } \$4.41 / \text{CY} \times 400 \text{ CY} = \$1764 / \text{leak (96MM p 28)}$$

$$\text{Backfill: } \$ (1.53 + 2.13) / \text{CY} \times 400 \text{ CY} = \$1464 / \text{leak "}$$

$$\text{Repair: } 3 \text{ men} \times 6 \text{ hrs} \times \$46.35 / \text{hr} = 834 / \text{leak (96MM p 475)}$$

$$\text{Time Req'd: } 400 \text{ CY} \times 0.080 \frac{\text{hr}}{\text{CY}} \div 24 \frac{\text{hr}}{\text{day}} = 1.3 \frac{\text{days}}{\text{leak (96MM p 28)}}$$

$$\text{O\&M Costs} = \$ (1764 + 1464 + 834) / \text{leak} \times 2 \frac{\text{leaks}}{\text{yr}} = \boxed{\$8124 / \text{year}}$$

HTW Lost: (See graph of 1995 make-up water use)

$$\text{Average loss during leak} = 25000 \text{ GPD}$$

$$\text{Average 1995 Make-up use} = 10000 \text{ GPD}$$

$$(25000 \text{ GPD} - 10000 \text{ GPD}) \times 1.3 \text{ Day/leak} = 20,000 \text{ Gal/leak}$$

A.3.1-6



SUBJECT Fort Stewart
Replace HTW Piping
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 4 OF 4
DATE 2-7-96
DATE _____

ECO-1 REPLACE HTW PIPING

Minor HTW leaks average 2.5 GPM (see table for calc)

$$2.53 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{yr}} = 1,329,800 \text{ GAL/yr}$$

Current HTW Losses :

$$1,329,800 \text{ GAL/yr} + 20,000 \frac{\text{GAL}}{\text{LEAK}} \times 2 \frac{\text{LEAKS}}{\text{YR}} = \underline{1,369,800 \frac{\text{GAL}}{\text{YR}}}$$

Proposed HTW losses :

Assume losses in new HTW system will average about 0.10 GPM over the life of the system.

$$0.10 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{yr}} = \underline{52,560 \frac{\text{GAL}}{\text{YR}}}$$

ANNUAL SAVINGS

$$\text{Current} = 259320 \frac{\text{MBtu}}{\text{YR}} + 5210 \frac{\text{MBtu}}{\text{YR}} = 264,530 \frac{\text{MBtu}}{\text{YR}} \text{ (Heating)}$$

$$\text{New} = 86440 \frac{\text{MBtu}}{\text{YR}} + 200 \frac{\text{MBtu}}{\text{YR}} = 86640 \text{ MBtu/YR} \quad "$$

$$\text{HEATING FUELS} = 264530 - 86640 = \boxed{177,890 \text{ MBtu/YR}}$$

$$\text{ELECTRICITY} = 6.8 - 0.3 = \boxed{6.5 \text{ MBtu/YR}}$$

$$\text{WATER} = \$762 - \$29 = \boxed{\$733/\text{YR}}$$

$$\text{OIL} = \boxed{\$8124/\text{YR}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing HTW Piping
ECO Number: 1

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:	1. HTW temperature	380 °F
	2. Make-up water temperature	70 °F
	3. Boiler efficiency	68%
	4. Pump head (from record drawings)	300 Ft H2O
	5. Pump efficiency (from record drawings)	72%
	6. Motor efficiency	90%
	7. Average heating fuel cost	\$1.34 /MBtu
	8. Electricity cost	\$0.0469 /kWh
	9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$1369800 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 3543.6 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 3543.6 \text{ MBtu/yr} / 0.68 = \underline{5211.2 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 5211.2 \text{ MBtu/yr} \times \$1.34 / \text{MBtu} = \$6,983 / \text{Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{2.61 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.27 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.27 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.23 \text{ kW}$$

$$\text{Electricity Use} = 0.23 \text{ kW} \times 8760 \text{ Hr/Yr} = 1991 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 1991 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = \underline{6.8 \text{ MBtu/Yr}}$$

$$\text{Electricity Cost} = 1991 \text{ kWh/Yr} \times \$0.0469 / \text{kWh} = \$93 / \text{Year}$$

Water Cost:

$$1369800 \text{ Gal/Yr} \times \$0.5562 / \text{kGal} = \underline{\$762 / \text{Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$6,983 /Year
Pumping (Elec) Cost	\$93 /Year
Water Cost	\$762 /Year
Total Utility Cost	<u>\$7,838 /Year</u>

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Install New Shallow Trench HTW Piping
ECO Number: 1

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$52560 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 136.0 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 136.0 \text{ MBtu/yr} / 0.68 = \underline{200.0 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 200.0 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$268 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.10 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.01 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.01 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.01 \text{ kW}$$

$$\text{Electricity Use} = 0.01 \text{ kW} \times 8760 \text{ Hr/Yr} = 76 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 76 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = \underline{0.3 \text{ MBtu/Yr}}$$

$$\text{Electricity Cost} = 76 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$4 \text{ /Year}$$


Water Cost:

$$52560 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \underline{\$29 \text{ /Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$268 /Year
Pumping (Elec) Cost	\$4 /Year
Water Cost	\$29 /Year
Total Utility Cost	<u>\$301 /Year</u>

Figure #. #
 Fort Stewart CEP Make-up Water, 1995
 6475W



Fort Stewart - Central Energy Plant
 Filename: FS-VPDIS.WQ1
 12/15/95

Approximate Distance Between Valve Pits (1)

ZONE 1		ZONE 2N		ZONE 2S		ZONE 3		SEP ZONE		
PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	
CP-B1	200	CP-V1	150	V1-B1	700	CP-?	700	C1-V1	1500	(2)
B1-V4	1000	V1-V2	200	B1-V1	1500	?-1	800	V1-V2	100	(2)
V1-V2	600	V2-V3	350	V1-B2	300	?-2	400	V2-V3	1700	(2)
V2-V3	200	V3-V4	650	B2-B3	550	2-2A	400	V3-V4	450	(2)
V3-V4	350	V4-V5	600	B3-V1	250	2A-3	500	V4-V5	600	(2)
V4-V5	300	V5-V6	800	V1-V2	250	3-3A	400	V5-V6	500	(2)
V5-V6	550	V6-V7	800	V1-V3	350	3A-6	550	V6-SP	100	(2)
V6-V7	400	V2-V8	750	V3-V4	250	4-5	900	SP-V7	200	
V7-V8	600	V8-V9	300	V3-V6	300	5-6	650	V7-V8	150	
V8-V9	350			V4-V5	200	6-7	850	V8-V9	550	
V9-V10	350			V3-V7	650	7-8	950	V9-V10	650	
V10-V11	250			V7-V8	250	8-9	1000	V10-V11	800	
V11-V12	500			V8-V9	500	9-10	1000	V11-V12	650	
V12-V13	1000			V9-V10	200	10-11	900	V12-V13	800	
V13-V14	350			V9-V11	450	11-12	500			
V14-V15	400					12-13	950			
V15-V16	400					13-13A	750			
V16-V17	500					12-14	950			
V17-V18	800					14-15	200			
						15-16	250			
						16-16A	300			
						16A-17	200			
						17-18	200			
						18-19	100			
						19-20	150			
						20-22	200			
						21-22	100			
						22-23	350			
						15-24C	350			
						24C-24B	200			
						24B-24	200			
						24-24A	200			
						24A-25	150			
						24A-25A	300			
						25A-26	100			
						26-26A	200			
						26A-27	250			
						27-28	250			
TOTAL LN.FT.		9100	4600	6700		17400		8750		
MILES		1.7	0.9	1.3		3.3		1.7		8.8
MAX LNFT/VP		1000	800	1500		1000		1700		
AVG LNFT/VP		479	511	447		458		625		
MIN LNFT/VP		200	150	200		100		100		
NO. OF PITS (1)		19	9	15		38		14		95

- (1) There are other valve boxes and drain pits that are not shown on our HTW system map.
 (2) These pipes carry steam.

NOTICE

PORTIONS OF THIS REPORT ARE ILLEGIBLE. It has been reproduced from the best available copy to permit the broadest possible availability.

ANALYSIS OF A SMALL DISTRICT STEAM SYSTEM AT
FT. McCLELLAN, ALABAMA

Gerald D. Pine and Michael A. Karnitz

CONF-8406132

DE84 014051

Energy Division
Oak Ridge National Laboratory*
Oak Ridge, Tennessee 37831

615 576-5454

574-5150

For presentation at the
75th Annual Conference of the International
District Heating Association
Mount Washington, New Hampshire

June 17-20, 1984

MASTER

By acceptance of this article, the publisher or recipient acknowledges the U.S. Government's right to retain a nonexclusive, royalty-free license in and to any copyright covering the article.

* Research sponsored by the U. S. Army, Construction Engineering Research Laboratory, under Interagency Agreement Number 40-1361-83, Army Number CERL-83-080, operated by Martin Marietta Energy Systems, Inc., under Contract No. DE-AC05-84OR21400 with the U.S. Department of Energy.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

Of the total steam produced, we estimate that approximately 95% enters the steam distribution system. The remaining 5% is used within the boiler plants to power auxiliaries. This amounts to some 370 lb/hr on the average or 3.0 million lb/yr. Then approximately 96 million lb/yr enters the distribution system.

5. CAUSES FOR HEAT LOSS FROM BURIED PIPE

In order to minimize heat losses from steam and condensate pipe lines, the lines are usually insulated. Sometimes the pipes may run above ground but more commonly, the pipes are buried from two to six feet below the surface. If the insulation is intact and dry, the ground helps to insulate the pipe from cold temperatures in the winter and to reduce the heat losses. In this section, we present estimates of the heat losses for well insulated pipes as well as for pipes with deteriorated insulation and under various failure conditions.

Heat Loss From Dry, Insulated, Buried Pipes. Heat losses have been calculated for varied soil conditions and various types of insulation by King et al. [3]. For the example of a six-inch steam line at 325°F with four inches of calcium silicate insulation in clay of average moisture and a soil temperature of 50°F, the rate of heat loss would be approximately 55 Btu/hour per linear foot of pipe. For the Ft. McClellan system with a steam temperature of 338°F and a ground temperature of 80°F, the loss rate would be about 52 Btu/hr-ft. ←

Heat Loss From Bare Pipes in Air. The simplest case to consider is a bare pipe exposed to ambient air on a dry, still day. For this case, the two major heat loss mechanisms are natural convection and radiation. We consider the case of a six-inch pipe with 338°F steam and ambient air at 150°F (a typical temperature inside a dry vault, where much of the bare pipe is found). The estimated loss due to natural convection under these conditions is about 350 Btu/hour per foot of pipe. Kreith [4] in Table 5.1 gives a value of emissivity of 0.8 for oxidized steel pipe. For the same pipe, the estimated radiation loss is approximately 570 Btu/hr-ft. The total loss per foot of bare pipe under these circumstances is then 920 Btu/hr-ft.

Buried Pipes With Entrapped Moisture and Deteriorated Insulation. Observations of actual buried steam lines indicates that the heat losses are substantially higher than the theoretical losses. Consideration of the magnitudes of the observed losses suggests that the pipe is behaving as though there were no insulation, and that the pipe is in direct contact with the surrounding soil. The most likely physical explanation is that the conductivity has been greatly enhanced by the deterioration of the insulation from the combined effects of heat and moisture that gets into the system by steam leaks or the intrusion of ground water. Entrapped moisture could be boiling near the surface of the pipe and condensing on the jacket, or subcooled boiling and the formation of a thermal convection loop in water filling the space between the pipe and jacket could be occurring. Both these processes produce extremely high heat transfer rates compared to the rate through dry insulation. If it is assumed that the conductivity of the insulation is infinite, the model of King et al. yields a heat transfer factor of about 1.8 Btu/hr-°F per foot of six-inch diameter pipe. For the six-inch pipe at 330°F and a 80°F ground temperature, the rate of heat loss per foot of pipe would be 460 Btu/hr-ft. This compares with the observed value of about 275 Btu/hr-ft. ←

Heat Loss From Flooding of Vaults. A commonly observed failure of steam lines is the failure of sump pumps in valve pits and the subsequent covering of the steam pipe with water. The source of the water can be either condensate from steam traps, which collect in the vault and causes flooding when sump pumps fail, or intrusion of ground water into the pits through cracks in the pit wall or around pipes that penetrate the pit walls. Water in the vault is commonly heated to temperatures that are rather hot; we assume here that the water in the vault is heated to 150°F. The estimated rate of heat loss from a bare, six-inch steam pipe carrying 338°F steam and covered by 150°F water is 30,000 Btu/hr-ft. (This estimate could be higher, perhaps as high as 150,000 Btu/hr-ft depending on the assumed heat transfer mechanism.) Notice that the loss is nearly sixty times as large as the loss from dry, bare pipe. Perhaps even more interesting, the rate of heat loss would be 190 times greater than the

WATER LOSS ESTIMATE		
ITEM	GPD	GPM
1) Blowdown	1440	1.000
2) Sootblowing	468	0.325
3) CEP - Misc. Leaks	298	0.207
4) CEP - No. 4 Boiler	334	0.232
5) SEP Leaks	336	0.233
6) Valve Pit Leaks	1398	0.971
7) Mech. Equip. Room Leaks*	1260	0.875
Total Losses Identified	5534	3.843
Average 1995 Water Use	9179	6.374
- Total Losses Identified	5534	3.843
Estimated HTW Piping Leaks	3645	2.531
<p>* Some of the leaks found during the survey of mechanical equipment rooms may have been found and repaired and other leaks might have developed since the surveys were performed.</p>		

PIE CHART VALUES

Blowdown/Soot Blowing	1908	1.325	20.8%
CEP/SEP/VP/ME Rm Leaks	3626	2.518	39.5%
HTW Piping Leaks	3645	2.531	39.7%

BAR CHART VALUES

	1993	1994	1995
Blowdown/Soot Blowing	1908	1908	1908
CEP/SEP/VP/ME Rm Leaks	3626	3626	3626
HTW Piping Leaks	7312	8922	3645

022 | Earthwork

2 SITE WORK

022 200 Excav./Backfill/Compact.				CREW	DAILY OUTPUT	LABOR HOURS	UNIT	1996 BARE COSTS				TOTAL INCL O&P	
								MAT.	LABOR	EQUIP.	TOTAL		
204	0500	Air tamp, add	A123	B-9	190	.211	C.Y.		4.25	.80	5.05	7.70	204
	0600	Vibrating plate, add	-110	A-1	60	.133			2.64	1	3.64	5.30	
	0800	Compaction in 12" layers, hand tamp, add to above		1 Clab	34	.235			4.66		4.66	7.45	
	0900	Roller compaction operator walking, add		B-10A	150	.080			1.90	.57	2.47	3.58	
	1000	Air tamp, add		B-9	285	.140			2.84	.53	3.37	5.10	
	1100	Vibrating plate, add		A-1	90	.089			1.76	.67	2.43	3.55	
	1300	Dozer backfilling, bulk, up to 300' haul, no compaction		B-10B	1,200	.010			.24	.71	.95	1.15	
	1400	Air tamped		B-11B	240	.067			1.52	4.46	5.98	7.30	
	1600	Compacting backfill, 6" to 12" lifts, vibrating roller		B-10C	800	.015			.36	1.19	1.55	1.86	
	1700	Sheepsfoot roller		B-10D	750	.016			.38	1.29	1.67	2.01	
	1900	Dozer backfilling, trench, up to 300' haul, no compaction		B-10B	900	.013			.32	.95	1.27	1.53	
	2000	Air tamped		B-11B	235	.068			1.55	4.56	6.11	7.40	
	2200	Compacting backfill, 6" to 12" lifts, vibrating roller		B-10C	700	.017			.41	1.37	1.78	2.13	
	2300	Sheepsfoot roller		B-10D	650	.018			.44	1.49	1.93	2.32	
234	0010	DRILLING AND BLASTING Only, rock, open face, under 1500 C.Y.		B-47	225	.107	C.Y.	1.50	2.36	2.52	6.38	8.15	234
	0100	Over 1500 C.Y.		"	300	.080		1.50	1.77	1.89	5.16	6.50	
	2200	Trenches, up to 1500 C.Y.		B-47	22	1.091		4.50	24	25.50	54	71.50	
	2300	Over 1500 C.Y.		"	26	.923		4.29	20.50	22	46.79	60.50	
250	0010	EXCAVATING, STRUCTURAL Hand, pits to 6' deep, sandy soil		1 Clab	8	1	C.Y.		19.80		19.80	31.50	250
	0100	Heavy soil or clay			4	2			39.50		39.50	63	
	0300	Pits 6' to 12' deep, sandy soil			5	1.600			31.50		31.50	50.50	
	0500	Heavy soil or clay			3	2.667			53		53	84.50	
	0700	Pits 12' to 18' deep, sandy soil			4	2			39.50		39.50	63	
	0900	Heavy soil or clay			2	4			79		79	126	
	1500	For wet or muck hand excavation, add to above					%				50%	50%	
254	0010	EXCAVATING, TRENCH or continuous footing, common earth	A123										254
	0020	No sheeting or dewatering included	-110										
	0050	1' to 4' deep, 3/8 C.Y. tractor loader/backhoe		B-11C	150	.107	C.Y.	2.43	1.39		3.82	5.30	
	0060	1/2 C.Y. tractor loader/backhoe		B-11M	200	.080		1.82	1.43		3.25	4.41	
	0090	4' to 6' deep, 1/2 C.Y. tractor loader/backhoe		"	200	.080		1.82	1.43		3.25	4.41	
	0100	5/8 C.Y. hydraulic backhoe		B-12Q	250	.064		1.56	1.58		3.14	4.12	
	0110	3/4 C.Y. hydraulic backhoe		B-12F	300	.053		1.30	1.50		2.80	3.64	
	0300	1/2 C.Y. hydraulic excavator, truck mounted		B-12J	200	.080		1.95	3.15		5.10	6.45	
	0500	6' to 10' deep, 3/4 C.Y. hydraulic backhoe		B-12F	225	.071		1.73	2		3.73	4.86	
	0600	1 C.Y. hydraulic excavator, truck mounted		B-12K	400	.040		.97	2.17		3.14	3.88	
	0900	10' to 14' deep, 3/4 C.Y. hydraulic backhoe		B-12F	200	.080		1.95	2.25		4.20	5.45	
	1000	1-1/2 C.Y. hydraulic backhoe		B-12B	540	.030		.72	1.32		2.04	2.56	
	1300	14' to 20' deep, 1 C.Y. hydraulic backhoe		B-12A	320	.050		1.22	1.72		2.94	3.77	
	1400	By hand with pick and shovel to 6' deep, light soil		1 Clab	8	1		19.80			19.80	31.50	
	1500	Heavy soil		"	4	2		39.50			39.50	63	
	1700	For tamping backfilled trenches, air tamp, add		A-1	100	.080		1.58	.60		2.18	3.19	
	1900	Vibrating plate, add			90	.089		1.76	.67		2.43	3.55	
	2100	Trim sides and bottom for concrete pours, common earth			600	.013	S.F.	.26	.10		.36	.53	
	2300	Hardpan			180	.044	"	.88	.33		1.21	1.77	
258	0010	EXCAVATING, UTILITY TRENCH Common earth											258
	0050	Trenching with chain trencher, 12 H.P., operator walking											
	0100	4" wide trench, 12" deep		B-53	800	.010	LF.	.25	.11		.36	.50	
	0150	18" deep			750	.011		.26	.11		.37	.52	
	0200	24" deep			700	.011		.28	.12		.40	.56	
	0300	6" wide trench, 12" deep			650	.012		.30	.13		.43	.61	
	0350	18" deep			600	.013		.33	.14		.47	.66	
	0400	24" deep			550	.015		.36	.15		.51	.72	
	0450	36" deep			450	.018		.44	.19		.63	.88	
	0600	8" wide trench, 12" deep			475	.017		.42	.18		.60	.84	

A.3.1-15

CONSTRUCTION COST ESTIMATE

Project: Shallow Trench HTW Piping System
 Location: Fort Stewart, GA
 Basis: Schematic Design
 ECO No.: 1

RS&H No.: 694-1331-002
 Date: 14-Feb-96
 Estimator: W.T.Todd
 Filename: EST-1.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Excavating Trench	60900	CY	1.37	83433	1.73	105357	188,790	MMp23	MMp23
Piping Demolition, to 2"	40887	LF	NA	0	1.13	46202	46,202	MMp17	MMp17
Piping Demolition, to 4"	22880	LF	NA	0	1.51	34549	34,549	MMp17	MMp17
Piping Demolition, to 8"	34430	LF	NA	0	4.53	155968	155,968	MMp17	MMp17
Piping Demolition, to 16"	23540	LF	NA	0	7.55	177727	177,727	MMp17	MMp17
Scrap Salvage, Steel	1593	Ton	-60.00	-95570	NA	0	(95,570)	MMp17	MMp17
HTW Pipe, 2" Sch 80 Steel	40887	LF	5.17	211529	6.51	266031	477,560	MMp107	MMp107
Joint Weld, 2" Sch 80	4089	Ea	3.41	13942	27.00	110395	124,337	MMp109	MMp109
Insul., 2" Wall, 2" Pipe	40887	LF	3.37	137789	3.10	126750	264,539	MMp199	MMp199
HTW Pipe, 4" Sch 80 Steel	22880	LF	14.31	327413	11.61	265614	593,027	MMp107	MMp107
Joint Weld, 4" Sch 80	2288	Ea	4.65	10639	37.00	84656	95,295	MMp109	MMp109
Insul., 2" Wall, 4" Pipe	22880	LF	4.56	104333	3.37	77106	181,439	MMp199	MMp199
HTW Pipe, 6" Sch 80 Steel	24970	LF	30.95	772822	20.16	503395	1,276,217	MMp107	MMp107
Joint Weld, 6" Sch 80	2497	Ea	10.25	25594	81.50	203506	229,100	MMp109	MMp109
Insul., 2" Wall, 6" Pipe	24970	LF	5.85	146075	3.69	92139	238,214	MMp199	MMp199
HTW Pipe, 8" Sch 80 Steel	9460	LF	52.44	496082	24.48	231581	727,663	MMp107	MMp107
Joint Weld, 8" Sch 80	946	Ea	12.80	12109	102	96492	108,601	MMp109	MMp109
Insul., 2" Wall, 8" Pipe	9460	LF	6.95	65747	4.08	38597	104,344	MMp199	MMp199
HTW Pipe, 10" Sch 80 Stl	23540	LF	70.06	1649212	30.24	711850	2,361,062	MMp107	MMp107
Joint Weld, 10" Sch 80	2354	Ea	17.05	40136	136	320144	360,280	MMp109	MMp109
Insul., 2" Wall, 10" Pipe	23540	LF	8.65	203621	4.56	107342	310,963	MMp199	MMp199
Conduit, 20" Sch 40 Steel	33000	LF	75.05	2476650	62.04	2047320	4,523,970	MMp104	MMp104
Joint Weld, 20" Sch 40	3300	Ea	28.50	94050	226	745800	839,850	MMp109	MMp109
Conduit, 16" Sch 40 Steel	36410	LF	56.18	2045514	43.12	1569999	3,615,513	MMp104	MMp104
Joint Weld, 16" Sch 40	3641	Ea	23.50	85564	185	673585	759,149	MMp109	MMp109
Conduit, 14" Sch 40 Steel	20444	LF	48.06	982515	37.40	764587	1,747,102	MMp104	MMp104
Joint Weld, 14" Sch 40	2044	Ea	19.70	40274	157	320963	361,237	MMp109	MMp109
Valves, Fittings, etc.	All	--	10%	421704	10%	323560	745,264	Estimate	Estimate
Dozer Backfill, Trench	60900	CY	0.91	55419	0.30	18270	73,689	MMp23	MMp23
Compacting Backfill	60900	CY	1.31	79779	0.39	23751	103,530	MMp23	MMp23
Subtotal Bare Costs				10486375		10243236	\$20,729,611		
Retrofit Cost Factors			4.0%	419455	7.0%	717027	1,136,482	MMp4	MMp4
Subtotal				10905830		10960263	21,866,093		
City Cost Index (Sav. GA)			-2.4%	-261740	-40.4%	-4427946	(4,689,686)	MEp439	MEp439
Subtotal				10644090		6532317	17,176,407		
OH & Profit Markups			10.0%	1064409	50.0%	3266159	4,330,568	MEp5	MEpIBC
Subtotal				11708499		9798476	21,506,975		
Sales Taxes			4.0%	468340		NA	468,340		
Total Construction Cost				12176839		9798476	21,975,315		
Design Fee				NA	6.0%	1318519	1,318,519		
SIOH				NA	6.0%	1318519	1,318,519		
Subtotal				12176839		12435514	24,612,353		
Contingency			0.0%	0	0.0%	0	0	MEp4	MEp4
Total Project Cost				12176839		12435514	\$24,612,353		

LEGEND:

MMp### 1995 Means Mechanical Cost Data, page ###.




SUBJECT FORT STEWART
REPLACE HTW PIPING
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-7-96
DATE _____

Shallow Trench Piping System

Excavation & Backfill :



Cubic yards (CY) per linear foot

$$1' \times 3' \times 9' = 27 \text{ ft}^3$$

$$27 \text{ ft}^3 \div 27 \text{ cc/cy} = 1 \text{ CY / LF}$$

HTW pipe lengths and sizes were taken off of the Central Heating and Cooling drawings. A list of the pipe sizes and lengths used for cost estimating is contain on the following pages.

Fort Stewart
Estimate of HTW System Pipe Lengths
Filename: F-PIPING.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Ft w/loops	
HTWS	All (main)	10	3850	
HTWR	All (main)	10	3850	
HTWR	All (main)	10	5225	
STMS	All (main)	10	5390	
HTWS	All (main)	10	5225	
Subtotal			23540	LnFt
HTWR	All (main)	8	440	
HTWS	All (main)	8	440	
HTWS	All (main)	8	605	
HTWS	All (main)	8	1485	
HTWR	All (main)	8	605	
HTWR	All (main)	8	2200	
HTWS	All (main)	8	2200	
HTWR	All (main)	8	1485	
Subtotal			9460	LnFt
HTWR	All (main)	6	4070	
HTWS	All (main)	6	4070	
HTWS	All (main)	6	1980	
HTWR	All (main)	6	1980	
HTWS	All (main)	6	605	
HTWR	All (main)	6	605	
HTWR	All (main)	6	2035	
HTWS	All (main)	6	825	
HTWR	All (main)	6	825	
HTWS	All (main)	6	220	
HTWR	All (main)	6	220	
HTWS	All (main)	6	2035	
HTWS	All (main)	5	385	
HTWS	All (main)	5	990	
HTWR	All (main)	5	990	
HTWR	All (main)	5	385	
HTWR	All (main)	5	1375	
HTWS	All (main)	5	1375	
Subtotal			24970	LnFt
HTWR	All (main)	4	2860	
HTWS	All (main)	4	825	
HTWR	All (main)	4	825	
HTWS	All (main)	4	2860	
HTWS	All (main)	4	880	
HTWS	All (main)	4	550	
HTWR	All (main)	4	880	

Fort Stewart
 Estimate of HTW System Pipe Lengths
 Filename: F-PIPING.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Ft w/loops	
HTWS	All (main)	4	1650	
HTWR	All (main)	4	1100	
HTWR	All (main)	4	550	
HTWR	All (main)	4	1650	
HTWR	All (main)	4	5390	
HTWS	All (main)	4	1100	
HTWS	All (main)	3	880	
HTWR	All (main)	3	880	
Subtotal			22880	LnFt
HTWR	All (main)	2.5	1760	
HTWS	All (main)	2.5	1760	
HTWS	All (main)	2.5	440	
HTWR	All (main)	2.5	440	
HTWR	All (main)	2.5	550	
HTWS	All (main)	2.5	550	
HTWS	All (main)	2.25	990	
HTWR	All (main)	2.25	990	
HTWR	All (main)	2	990	
HTWS	All (main)	2	990	
HTWS	All (main)	2	770	
HTWR	All (main)	2	770	
HTWR	All (main)	2	5390	
HTWS	All (main)	2	770	
HTWR	All (main)	2	770	
HTWR	All (main)	2	4510	
HTWS	All (main)	2	4510	
HTWR	All (main)	2	880	
HTWS	All (main)	2	880	
HTWR	All (main)	2	880	
HTWS	All (main)	2	880	
HTWS	All (main)	1.5	330	
HTWR	All (main)	1.5	330	
HTWR	All (main)	1.25	1980	
HTWS	All (main)	1.25	1980	
Branch Piping (5% of mains)			1689	
Branch Piping (5% of mains)			1579	
Branch Piping (5% of mains)			1018	
Branch Piping (5% of mains)			1513	
Subtotal			40887	LnFt
Total			121737	LnFt

ECO NUMBER 2

**REDUCE BLOWDOWN OF THE CASCADE HEATERS AND THE
WOOD-FIRED BOILER**

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-2

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-2 REDUCE BLOWDOWN FREQUENCY

FISCAL YEAR 1995 DISCRETE PORTION NAME: REDUCE BLOWDOWN BY 50%

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	500.		
B. SIOH	\$	0.		
C. DESIGN COST	\$	0.		
D. TOTAL COST (1A+1B+1C)	\$	500.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		500.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1000.	\$ 1340.	14.88	\$ 19939.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1000.	\$ 1340.		\$ 19939.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	2505.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	37274.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 37274.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 3845.

5. SIMPLE PAYBACK PERIOD (1G/4) .13 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 57214.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 114.43
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: ECO-2X
 INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: ECO-2 REDUCE BLOWDOWN FREQUENCY
 FISCAL YEAR 1995 DISCRETE PORTION NAME: REDUCE BLOWDOWN BY 50%
 ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	500.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	500.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		500.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	864.	\$ 1158.	14.88	\$ 17227.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		864.	\$ 1158.		\$ 17227.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	2505.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	37274.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
------	------------------------------	-----------------	------------------------	---

d. TOTAL	\$	0.		0.
----------	----	----	--	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)	\$	37274.
---	----	--------

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$	\$	3663.
--	----	-------

5. SIMPLE PAYBACK PERIOD (1G/4)	.14 YEARS
---------------------------------	-----------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$	54502.
--	----	--------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)=	109.00
(IF < 1 PROJECT DOES NOT QUALIFY)	

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-2Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-2 REDUCE BLOWDOWN FREQUENCY

FISCAL YEAR 1995 DISCRETE PORTION NAME: REDUCE BLOWDOWN BY 50%

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	500.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	500.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	500.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	765.	\$ 1025.	14.88	\$ 15253.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		765.	\$ 1025.		\$ 15253.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 2505.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 37274.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 37274.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 3530.

5. SIMPLE PAYBACK PERIOD (1G/4) .14 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)\$ 52528.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 105.06
 (IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT Fort Stewart
Reduce Blowdown
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331052
SHEET _____ OF _____
DATE 2-7-96
DATE _____

ECO No. 2

REDUCE BLOWDOWN FREQUENCY

BOILER WATER TESTS SHOW WATER IS CLEANER THAN IT SHOULD BE IMPLYING BLOWDOWN FREQUENCY IS TOO HIGH FOR SOLIDS BEING GENERATED.

INITIALLY, BLOWDOWN FREQUENCY SHOULD BE REDUCED, PERHAPS TO 300 NUMBERED DAYS AND THE DURATION OF BLOWDOWN SHOULD NOT BE CHANGED.

CURRENT HTW USE (see table for calculation)

$$1440 \frac{\text{GAL}}{\text{Day}} \times 365 \text{ days/yr} = \underline{525600 \text{ GAL/yr}}$$

ANNUAL COST for O&M

$$30 \text{ min/day} \times 365 \text{ day/yr} \times \$ 25.86/\text{hr} = \underline{\$4720/\text{yr}}$$

HTW SAVINGS

CURRENT BOILER WATER CONCENTRATIONS ARE ABOUT $\frac{1}{2}$ THE RECOMMENDED VALUE, THEREFORE BLOWDOWN CAN BE CUT IN HALF.

$$525600 \text{ GAL/yr} \times 0.50 = \underline{262800 \text{ GAL/yr}}$$

O&M Cost Savings

$$\$4720/\text{yr} \times 0.5 = \boxed{\$2360/\text{yr}}$$

CAPITAL EXPENSE IS REQUIRED TO OBTAIN THIS SAVINGS.

Additional water analysis : 5 tests and reports \times \$100 ea = \$500

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Blowdown
ECO Number: 2

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:	1. HTW temperature	380 °F
	2. Make-up water temperature	70 °F
	3. Boiler efficiency	68%
	4. Average heating fuel cost	\$1.34 /MBtu
	5. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$525600 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 1359.7 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 1359.7 \text{ MBtu/yr} / 0.68 = \underline{1999.6 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 1999.6 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$2,679 \text{ /Year}$$

Water Cost:

$$525600 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \underline{\$292 \text{ /Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$2,679 /Year
Water Cost	\$292 /Year
	<hr/>
Total Utility Cost	\$2,971 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Reduce Blowdown
ECO Number: 2

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Average heating fuel cost	\$1.34 /MBtu
5. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$262800 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 679.9 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 679.9 \text{ MBtu/yr} / 0.68 = 999.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 999.8 \text{ MBtu/yr} \times \$1.34 / \text{MBtu} = \$1,340 / \text{Year}$$

Water Cost:

$$262800 \text{ Gal/Yr} \times \$0.5562 / \text{kGal} = \$146 / \text{Year}$$

Total Utility Cost:

Heating Fuel Cost	\$1,340 /Year
Water Cost	\$146 /Year
<hr/>	
Total Utility Cost	\$1,486 /Year

ANNUAL SAVINGS

$$\text{HEATING FUELS} = 2000 - 1000 = \boxed{1000 \text{ MBtu/Yr}}$$

$$\text{WATER COST} = \$292 - \$146 = \boxed{\$146 / \text{Yr}}$$

Estimated Water Consumption Due to Blowdown

Blowdown Point	Duration Est. (min)		Pipe Dia. (in)	Pipe Length (ft)	Pres. Drop (ft)	Flow			Average (gpd)
	Est. #1	Est. #2				(gpm)	(gpd, #1)	(gpd, #2)	
Intermittent (1)									
Heater #1	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #2	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #3	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
No. 4 Boiler									
East Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
West Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
Rear Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
East Drum	0.33	0.50	1	100	400	87.5	29.2	43.8	
West Drum	0.33	0.50	1	100	400	87.5	29.2	43.8	
Sub-total Intermittent Blowdown - Summer						448	343	395	
Heater #4	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #5	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Additional Intermittent Blowdown - Winter						201	83	142	
Continuous (2)									
Steam Drum	1440	0	1/16	100	400	1.353	1948	0	974
Total Blowdown - Summer						2396	343	1369	
Total Blowdown - Winter						2597	425	1511	

- (1) Assumes 200 psi, 1 inch orifice, square edged, C = 0.82; Cameron Hydraulic Data, pages 2-8 and 2-9.
 (2) Assumes 200 psi, 1/16 inch orifice, square edged, C = 0.82; Cameron Hydraulic Data, pages 2-8 and 2-9.

RS&H No.: 694-1331-002
Date: 05/24/96
Estimator: W.T.Todd
Filename: EST-2.WB2

LEGEND:
MMp### 1996 Means Mechanical Cost Data, page ###.

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 BOILER 4

Sample Number XCSTEWBW Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued 08/25/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... BW From Boiler 4 Pretreatment..... Resin Feedwater Temp (F)..... 212 Feedwater Deoxygenation Method(s): Mechanical..... Oxygen Scavenger..... Sodium Sulfite Boiler Type..... Water Tube Steam Gauge Pressure (PSIG)..... 220 Boiler Horsepower..... Boiler Output (PPH)..... 98,000 Boiler Treatment: pH Control..... Phosphate.....sodium hexametaphosphate Dispersant..... Condensate pH Control.....morpholine			
Boiler Water Analysis Report							
Test Description	P&A	Plant	Control	Comments			
Specific Sx Description							
Total Hardness, ppm CaCO ₃							
Filt Ortho Phos, ppm PO ₄							
Polymer, ppm							
Sulfite, ppm Na ₂ SO ₃							
P Alkalinity, ppm CaCO ₃							
Causticity, ppm OH ⁻							
pH							
Neut Conductivity, mhos							
Total Diss Solids, ppm							

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Test agreement is good overall noting only a minor discrepancy for phosphate . Sulfite difference is normal since sulfite will degrade over time.
2. Results show that phosphate is below the control range. Sulfite is significantly overdosed while causticity is within range. Blowdown is excessive based on low TDS.

continued...

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 BOILER 4

Sample Number RPSTEWBW Date Sampled 06/06/95 Date Received 06/16/95 Date Analyzed 06/27/95 Date Report Issued 07/06/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... BW From Boiler 4 Pretreatment..... Sodium Cycle Softener Feedwater Temp (F)..... 212 Feedwater Deoxygenation Method(s): Mechanical..... Oxygen Scavenger..... Sodium Sulfite Boiler Type..... Water Tube Steam Gauge Pressure (PSIG)..... 220 Boiler Horsepower..... Boiler Output (PPH)..... 98,000 Boiler Treatment: pH Control..... Phosphate.....sodium hexametaphosphate Dispersant..... Condensate pH Control.....morpholine <div style="text-align: center;">Comments</div>			
Boiler Water Analysis Report							
Test Description	P&A	Plant	Control				
Specific Sx Description							
Total Hardness, ppm CaCO_3	(2						
Filt Ortho Phos, ppm PO_4	44	40	30 - 60				
Tannin Color							
Polymer, ppm			N/A				
Sulfite, ppm Na_2SO_3	650	780	20 - 40				
P Alkalinity, ppm CaCO_3	410						
M Alkalinity, ppm CaCO_3							
Causticity, ppm OH^-	130	115	20 - 200				
pH	11.7	11.7					
Neut Conductivity, mmhos	2480	2300					
Total Diss Solids, ppm	1750	1610	3000 - 3500				

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Thank you for your comment on Form 276 regarding blowdown. We are glad to see that you are investigating the cause of low TDS and causticity which you believe is caused by something other than excessive blowdown because you have already reduced blowdown to a "bare minimum". Let us know what you find out and please see Recommendation #1 below for suggestions on how P&A can help via this sample program.
2. Test agreement is good.
3. Control of treatment levels is good except for sulfite which is much too high.

Continued...

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 BOILER 4

Sample Number BCSTEWBW Date Sampled 01/10/95 Date Received 01/17/95 Date Analyzed 01/24/95 Date Report Issued . 01/27/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Tester/Operator..... Eddie Bryant Building Sample is From..... Central Energy Plant Description of Sample..... BW From Boiler 4 Pretreatment..... Resin Feedwater Temp (F)..... 212 Feedwater Deoxygenation Method(s): Mechanical..... Oxygen Scavenger..... Sodium Sulfite Boiler Type..... Water Tube Steam Gauge Pressure (PSIG)..... 220 Boiler Horsepower..... Boiler Output (PPH)..... 98,000 Boiler Treatment: pH Control..... Phosphate.....sodium hexametaphosphate Dispersant..... Condensate pH Control.....morpholine			
Boiler Water Analysis Report							
Test Description	P&A	Plant	Control				
Specific Sx Description	Sample not full.						
Total Hardness, ppm CaCO_3	<2						
Filt Ortho Phos, ppm PO_4	47	45	30 - 60				
Tannin Color							
Polymer, ppm			N/A				
Sulfite, ppm Na_2SO_3	690		20 - 40				
P Alkalinity, ppm CaCO_3	460						
M Alkalinity, ppm CaCO_3							
Causticity, ppm OH^-	160	161	20 - 200				
pH	12.0	11.2					
Neut Conductivity, mnhos	2580						
Total Diss Solids, ppm	1800	1540	3000 - 3500				

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

- Excellent test agreement overall! There is some discrepancy on TDS however, our result is 260 ppm higher than the plant's c about 14%. Sulfite was not reported by the plant.
- Results show good control of phosphate and caustic dosage. Sulfite is highly overdosed. Blowdown is excessive based on lo. TDS.

RECOMMENDATIONS:

- Reduce sulfite dosage significantly.
- Calibrate conductivity meter to improve test agreement for conductivity/TDS.
- Reduce blowdown to allow TDS to rise into range.

REPORT PREPARED BY: J. Tiangco

A.3.2-12

Puckorius & Associates, Inc. P.O. Box 2440, Evergreen, CO 80439 303-674-9897

ECO NUMBER 3

**REDUCE SOOT BLOWING, INSTALL AN EXIT GAS TEMPERATURE
INDICATOR ON THE WOOD-FIRED BOILER**

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-3

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-3 REDUCE SOOT BLOWING

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	208.		
B. SIOH	\$	13.		
C. DESIGN COST	\$	13.		
D. TOTAL COST (1A+1B+1C)	\$	234.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		234.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1226.	\$ 1643.	14.88	\$ 24445.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1226.	\$ 1643.		\$ 24445.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	47.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	699.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 699.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1690.

5. SIMPLE PAYBACK PERIOD (1G/4) .14 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 25145.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 107.46
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-3X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-3 REDUCE SOOT BLOWING

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	208.		
B. SIOH	\$	13.		
C. DESIGN COST	\$	13.		
D. TOTAL COST (1A+1B+1C)	\$	234.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		234.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1060.	\$ 1420.	14.88	\$ 21136.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1060.	\$ 1420.		\$ 21136.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	47.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	699.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 699.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 1467.

5. SIMPLE PAYBACK PERIOD (1G/4) .16 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)\$ 21835.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 93.31
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-3Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-3 REDUCE SOOT BLOWING

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	208.		
B. SIOH	\$	13.		
C. DESIGN COST	\$	13.		
D. TOTAL COST (1A+1B+1C)	\$	234.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		234.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	937.	\$ 1256.	14.88	\$ 18683.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		937.	\$ 1256.		\$ 18683.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	47.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	699.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 699.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 1303.

5. SIMPLE PAYBACK PERIOD (1G/4) .18 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)\$ 19382.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 82.83
(IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT Fort Stewart
Reduce Soot Blowing
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-8-96
DATE _____

ECO No. 3

DECREASE SOOT BLOWING FREQUENCY

BOILER SOOT BLOWING WAS PERFORMED ONCE PER SHIFT REGARDLESS OF THE BOILER TYPE OR SIZE.

DIAMOND POWER (SOOT BLOWER MFG.) CALCULATES 325 LBS OF STEAM ARE CONSUMED WITH EACH OPERATION. THERE ARE 8 BLOWERS ON NO. 4 BOILER.

CURRENT USE

$$\text{Energy} = 2 \text{ blowers} \times 325 \frac{\text{lb steam}}{\text{blow}} \times 2 \frac{\text{blows}}{\text{shift}} \times 3 \frac{\text{shift}}{\text{day}} \times 365 \frac{\text{day}}{\text{yr}} = 1423500 \frac{\text{lb steam}}{\text{yr}}$$

$$1423500 \frac{\text{lb steam}}{\text{yr}} \times (1199.6 - (60 - 32)) \frac{\text{Btu}}{\text{lb}} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 1667.8 \frac{\text{MBtu}}{\text{yr}}$$

$$\text{Fuel} = 1667.8 \text{ MBtu/yr} \div 0.68 \text{ boiler eff.} = \underline{2453 \text{ MBtu/yr}}$$

$$\text{Water} = 1423500 \frac{\text{lb steam}}{\text{yr}} \div 8.34 \frac{\text{lb}}{\text{gal}} = \underline{170683 \text{ GAL/yr}} \quad \$95$$

DATA SHOWS EXIT GAS TEMPERATURE REMAINS NEARLY CONSTANT. IT IS THEREFORE REASONABLE TO ASSUME THAT THE BOILER IS NOT SUFFICIENTLY FOULED TO CAUSE EGT TO RISE. ASSUME THEREFORE THAT THE FREQUENCY COULD BE CUT IN HALF.

ANNUAL SAVINGS WOULD BE ABOUT 50%

ANNUAL SAVINGS

$$\text{Fuels} = 2453 \text{ MBtu/yr} \times 0.50 = \boxed{1226 \text{ MBtu/yr}}$$

$$\text{Water} = 170683 \text{ GAL/yr} \times 0.50 = \underline{85341 \text{ GAL/yr}}$$

$$\text{Water \$} = 85341 \frac{\text{GAL}}{\text{yr}} \times \$0.5562 / 1000 \text{ GAL} = \boxed{\$47/\text{yr}}$$

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-3.WB2

LEGEND:
MMp### 1996 Means Mechanical Cost Data, page ###.

ECO NUMBER 4

REPAIR HTW AND STEAM LEAKS IN THE CEP AND THE SEP

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-4

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-4 REPAIR LEAKS IN THE CEP AND THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	4057.		
B. SIOH	\$	244.		
C. DESIGN COST	\$	244.		
D. TOTAL COST (1A+1B+1C)	\$	4545.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		4545.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 21.	15.08	\$ 311.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1091.	\$ 1462.	14.88	\$ 21754.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1093.	\$ 1483.		\$ 22064.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	160.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	2381.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 2381.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1643.

5. SIMPLE PAYBACK PERIOD (1G/4) 2.77 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 24445.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 5.38
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-4X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-4 REPAIR LEAKS IN THE CEP AND THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	4057.		
B. SIOH	\$	244.		
C. DESIGN COST	\$	244.		
D. TOTAL COST (1A+1B+1C)	\$	4545.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		4545.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 21.	15.08	\$ 311.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	943.	\$ 1264.	14.88	\$ 18803.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		945.	\$ 1284.		\$ 19113.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	160.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	2381.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 2381.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1444.

5. SIMPLE PAYBACK PERIOD (1G/4) 3.15 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 21494.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 4.73
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-4Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-4 REPAIR LEAKS IN THE CEP AND THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	4057.	
B. SIOH	\$	244.	
C. DESIGN COST	\$	244.	
D. TOTAL COST (1A+1B+1C)	\$	4545.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		4545.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 21.	15.08	\$ 311.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	834.	\$ 1118.	14.88	\$ 16629.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		836.	\$ 1138.		\$ 16940.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	160.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	2381.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 2381.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 1298.

5. SIMPLE PAYBACK PERIOD (1G/4) 3.50 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 19321.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 4.25
(IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
Repair CEP & SEP Leaks
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF _____
DATE 2-12-96
DATE _____

ECO-4 REPAIR HTW AND STEAM LEAKS IN THE CEP AND SEP

The quantities of HTW losses are listed below and the calculations can be found on the following pages:

$$\underline{\text{Misc. CEP Leaks}} = 0.207 \text{ gpm} = 298 \text{ GPD}$$

These leaks are all from valves stems, fittings and pump glands. It is hard for the pump glands to handle the high system operating pressure so we assumed that only about 50% of these leaks could be repaired.

$$\underline{\text{Boiler No. 4 Leaks}} = 0.232 \text{ gpm} = 334 \text{ GPD}$$

These leaks include 3 faulty steam traps and two blowdown valves. Assume new steam traps and valves will reduce these leaks by about 90%.

$$\underline{\text{Misc. SEP Leaks}} = 0.233 \text{ gpm} = 336 \text{ GPD}$$

These leaks are mainly due to leaking blowdown valves on the cascade heaters. Assume replacing the blowdown valves and tightening the other valves will eliminate 100% of these leaks.

$$\text{Current HTW Losses} = (298 + 334 + 336) \text{ GPD} \times 365 \frac{\text{day}}{\text{YR}} = \underline{353320 \frac{\text{Gal}}{\text{YR}}}$$

$$\text{Proposed HTW Losses} = (298 \times 0.5 + 334 \times 0.1) \text{ GPD} \times 365 \frac{\text{day}}{\text{YR}} = \underline{66580 \frac{\text{Gal}}{\text{YR}}}$$



SUBJECT FORT STEWART
REPAIR CEP & SEP LEAKS
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF _____
DATE 2-12-95
DATE _____

ECO-4 SUMMARY

ANNUAL SAVINGS

$$\text{HEATING FUELS} = 1344 - 253 = \boxed{1091 \text{ MBtu/YR}}$$

$$\text{ELECTRICITY} = 1.8 - 0.3 = \boxed{1.5 \text{ MBtu/YR}}$$

$$\text{WATER} = \$197 - \$37 = \boxed{\$160/\text{YR}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Leaks in the CEP and SEP
ECO Number: 4

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/12/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$353320 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 914.0 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 914.0 \text{ MBtu/yr} / 0.68 = 1344.1 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 1344.1 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$1,801 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.67 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.071 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.071 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.059 \text{ kW}$$

$$\text{Electricity Use} = 0.059 \text{ kW} \times 8760 \text{ Hr/Yr} = 514 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 514 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 1.75 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 514 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$24 \text{ /Year}$$

Water Cost:

$$353320 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$197 \text{ /Year}$$

Total Utility Cost:

Heating Fuel Cost	\$1,801 /Year
Pumping (Elec) Cost	\$24 /Year
Water Cost	\$197 /Year
<hr/>	
Total Utility Cost	\$2,022 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Repair Leaks in the CEP and SEP
ECO Number: 4

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/12/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$66580 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 172.2 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 172.2 \text{ MBtu/yr} / 0.68 = 253.3 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 253.3 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$339 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.13 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.013 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.013 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.011 \text{ kW}$$

$$\text{Electricity Use} = 0.011 \text{ kW} \times 8760 \text{ Hr/Yr} = 97 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 97 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 0.33 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 97 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$5 \text{ /Year}$$

Water Cost:

$$66580 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$37 \text{ /Year}$$

Total Utility Cost:

Heating Fuel Cost	\$339 /Year
Pumping (Elec) Cost	\$5 /Year
Water Cost	\$37 /Year
<hr/>	
Total Utility Cost	\$381 /Year



SUBJECT FORT STEWART
CEP Misc. Leaks
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF 2
DATE 2-2-96
DATE _____

CEP MISCELLANEOUS LEAKS

Valves & Fittings:

Cascade Heater No. 1

- Valve to top of sight glass leaking steam
- Valve on top left of heater leaking steam

Leak Rate
Estimate

2 drop/sec
2 "

Cascade Heater No. 2

- Valve on bottom left of heater leaking steam

2 "

Cascade Heater No. 3

- Valve on top of sight glass leaking steam

2 "

Deaerator Tank

- Strainer next to control valve leaking steam and about 3 drops/second HTW.
- Valve above stairs leaking steam
- Vent to outside blowing steam (intermittant)

5 "

2 "

2 "

Total valves & fittings leaks

17 drops/sec

$$17 \text{ drops/second} \times 2.5 \times 10^{-3} \frac{\text{gpm}}{\text{d/s}} = \underline{0.042 \text{ gal/min}}$$

HTW Zone Pumps:

- P-4 & P-5 ~ 1 drop / 4 seconds

= 0.006 GPM

- P-10 ~ steady 1/8" stream *

= 0.109 GPM

- P-11 ~ Intermittant 1/8" stream *

= 0.054 GPM



SUBJECT Fort Stewart
CEP Misc. Leaks
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF 2
DATE 2-2-96
DATE _____

Pumps (continued)

- P-23 & P-24 ~ 2 drops / 3 seconds = 0.0017 GPM

* A $\frac{1}{8}$ " stream was measured and timed and found
to be $\sim 1.75 \text{ cups/min} \div 16 \frac{\text{cups}}{\text{gal}} \approx 0.109 \text{ GPM}$

Total leaks from HTW Pumps = 0.165 GPM

Total Miscellaneous CEP Leaks:

Valves & Fittings	0.042 GPM
HTW Zone Pumps	0.165 GPM
	<hr/>
Total	= 0.207 GPM
	<hr/>

Central Energy Plant (CEP) Leak Test #4 Boiler

On November 30, 1995 a leak test was conducted at CEP to determine the extent of the leaks associated with Boiler No.4. A significant amount of steam continually vents from the No.4 blowdown tank. To quantify this loss, a CEP leak test would be conducted with the No.4 boiler configured in as a "tight" a mode as possible, and then a second test would be conducted with No.4 in a "normal" (leaky) configuration. The difference in the test results would be the leaks due to No. 4's normal configuration.

The leak test consists of measuring the make-up water required to maintain constant heater levels over an 8 hour period. Unfortunately, the test results showed no heater level changes over the 6 hour test period when a 6-7 inch change in the gauge glass level was expected. This testing technique has yielded results in the past. No explanation for the lack of results was determined; however, improper system valving is strongly suspected.


Configuring the boiler in as tight a configuration as possible stopped the blowdown tank steam venting. Leaking steam traps in the main steam line, the soot blower warm-up line, and in the boiler feed pump turbine line are the sources of the steam venting. Furthermore, the rear water wall header blowdown valves are leaking slightly. This leak was so small that only warm water entered the blow down tank.

A graph (enclosed) of the daily make-up consumption data shows a wide scattering of data, perhaps lending credence to the suspicion that observing heater tank levels over a short period of time (8 hours) yields uncertain results. However, when averaged over longer periods of time (weeks), yields more reliable results. The graph shows the daily make-up consumption (DMC) prior to October 15, 1995 averaged about 7000 gpd (4.86 gpm) while unit 4 alone was operating. During the period October 15 through November 10, 1995 unit 4 was shut down and units 1,2 and 3 were operating, and the DMC fell to 5900 gpd (4.10 gpm). This reduction in DMC can be attributed to two principal causes; 1) the general leaky state of unit No. 4; and 2) the required consumption of steam for sootblowing. The magnitude of the change 1100 gpd (0.764 gpm) seems reasonable. The fact that the consumption returned to the original levels when 4 boiler was returned to service implies that some of the leaks are in fact related to unit No. 4.

No. 4 Boiler Operation Recommendations

1. Repair steam trap leaks.
2. Reduce soot blowing frequency. Change from a time based operation to an exit gas temperature based operation.
3. Reduce blow down frequency to maintain American Boiler Manufacturers Association standard of 3500 ppm total dissolved solids.

Ft. Stewart Make-up Flow vs Time



Satellite Energy Plant (SEP) Leak test.

On November 29, 1995 the SEP was tested for system leaks. The testing procedure consists of stopping all steam flow to, and condensate return flow from, the SEP, and measuring the decrease in the level of the two cascade heaters in the SEP. By calculating the volume change in the heaters, a leak rate may be determined.

Time (EST)	9:46	10:34	11:13	11:37	11:48
Level (in)	14.3	14.3	14.3	14.3	14.3
Temp (°F)	375	360	340	335	330
Pres. (psig)	190	140	115	105	100

The data from the 2 hour test indicated that the water level in the heaters never changed while the circulating hot water showed a -45° temperature change and a -90 psig pressure change. It was concluded therefore the SEP system was "tight".

It is important to note however that the testing method used is quite crude over the short time period of the test. The two, 4000 gallon, cascade heaters are connected by symmetrical piping assuring "equal" water levels in both heaters. A one inch change in water level, at normal operating level, would be equivalent to 140 gallons of water. The leaks found and measured during the test are tabulated below.

<u>Location</u>	<u>Amount (gpm)</u>
East Heater gauge glass	2.23×10^{-4}
East Heater Steam Stop valve	2.11×10^{-3}
West Heater Equalization valve	1.00×10^{-3}
HTWS Check Valve	0.03
Both Heaters blow down valves	<u>0.2</u>
TOTAL	0.233

The total amount of water lost during the test is $0.233 \text{ gpm} \times 122 \text{ min.} = 29 \text{ gals.}$, or approximately 0.2 inches on the gauge glass. With normal, slow, level swings (generally attributable to sloshing) between the tanks, this leak rate is barely detectable in the sight glass over the time span of the test. Because of the large heater storage capacity, a longer test period is warranted. In the future this test could be a reasonable leak detection and quantification method at the SEP if conducted over longer testing periods. The best time for the test would be when the heat load from the SEP is minimal, perhaps on a warm day after a cool night.

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Leaks in the CEP and SEP
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 4

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-4.WB2

[illegible]

LEGEND:

- (1) Estimate 30 minutes for CEP to SEP round trip.
(2) Estimate 15 minutes per valve for 11 valves.
MMp### 1996 Means Mechanical Cost Data, page ###.

Installing Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of state rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with smaller annual billing. The overhead percentages for any given contractor may vary greatly and depend on a number of factors, such as the contractor's annual volume, engineering and logistical support costs, and staff requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevailing economic conditions. All factors should be examined very carefully for each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

		A		B	C	D	E	F	G	H	I
Abbr.	Trade	Base Rate Incl. Fringes		Work-ers' Comp. Ins.	Average Fixed Over-head	Over-head	Profit	Total Overhead & Profit		Rate with O & P	
		Hourly	Daily					%	Amount	Hourly	Daily
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10%	60.0%	\$15.55	\$41.50	\$332.00
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40	30.65	245.20
	Foreman Average, inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85	42.30	338.40
	Foreman Average, Outside (\$2.00 over trade)	27.95	223.60	20.2		13.0		60.0	16.75	44.70	357.60
	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80	31.60	252.80
Clab	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85	46.40	371.20
	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20	48.25	386.00
	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45	31.45	251.60
	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05	40.25	322.00
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30	36.65	293.20
	Electricians	29.30	234.40	8.0		16.0		50.8	14.90	44.20	353.60
	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75	45.80	366.40
	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35	41.10	328.80
	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80	39.50	316.00
Eqlt	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25	37.95	303.60
	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75	33.65	269.20
	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80	42.35	338.80
	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40	38.30	306.40
	Lathers	24.95	199.60	13.5		11.0		51.3	12.80	37.75	302.00
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65	40.30	322.40
	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55	40.10	320.80
	Mosaic & Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30	37.55	300.40
	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55	35.50	284.00
	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00	47.95	383.60
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70	36.00	288.00
	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35	44.70	357.60
	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35	37.55	300.40
	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10	31.25	250.00
	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95	46.00	368.00
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40	49.15	393.20
	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95	39.50	316.00
	Roofers, Tile & Slate	22.60	180.80	37.4		11.0		75.2	17.00	39.60	316.80
	Roofers, Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00	27.95	223.60
	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40	45.35	362.80
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65	47.95	383.60
	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05	46.35	370.80
	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20	37.25	298.00
Tilh	Tile Layers Helpers	20.30	162.40	11.0		11.0		48.8	9.90	30.20	241.60
	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15	31.50	252.00
	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35	32.05	256.40
	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
	*Wrecking	19.80	158.40	44.8	↓	11.0	↓	82.6	16.35	36.15	289.20

*Not included in Averages.

City Cost Indexes

DIVISION	FLORIDA																	
	MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6
031 CONCRETE FORMWORK	94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7
032 CONCRETE REINFORCEMENT	95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3
033 CAST IN PLACE CONCRETE	91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5
3 CONCRETE	87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3
4 MASONRY	76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4
5 METALS	98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0
6 WOOD & PLASTICS	88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0
7 THERMAL & MOISTURE PROTECTION	99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1
8 DOORS & WINDOWS	95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4
092 LATH, PLASTER & GYPSUM BOARD	101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9
096 FLOORING & CARPET	121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8
099 PAINTING & WALL COVERINGS	100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0
9 FINISHES	108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3
10-14 TOTAL DIV. 10-14	100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5
15 MECHANICAL	100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0
16 ELECTRICAL	98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5
1-16 WEIGHTED AVERAGE	97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9

DIVISION	FLORIDA						GEORGIA											
	TAMPA			ALBANY			ATLANTA			AUGUSTA			COLUMBUS			MACON		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8	110.4	74.3	82.6	111.6	91.9	96.5
031 CONCRETE FORMWORK	97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7	96.9	50.4	57.4	95.9	65.9	70.5
032 CONCRETE REINFORCEMENT	95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4	95.1	76.4	84.6	97.4	76.7	85.8
033 CAST IN PLACE CONCRETE	101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5	95.5	49.5	75.8	95.5	53.3	77.5
3 CONCRETE	92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2	89.4	57.0	73.0	89.7	65.1	77.3
4 MASONRY	82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4	83.4	39.3	56.0	98.6	46.7	66.4
5 METALS	102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7	96.7	89.3	93.9	91.7	90.1	91.1
6 WOOD & PLASTICS	94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3	93.7	51.3	72.5	97.4	69.9	83.6
7 THERMAL & MOISTURE PROTECTION	96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9	96.1	55.7	77.5	95.1	62.9	80.2
8 DOORS & WINDOWS	98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1	95.9	53.8	85.7	94.2	64.8	87.1
092 LATH, PLASTER & GYPSUM BOARD	101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7	101.6	50.4	68.4	108.3	69.5	83.2
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8	102.4	50.4	68.7	95.9	69.5	78.8
096 FLOORING & CARPET	113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2	113.0	41.0	95.7	87.8	47.5	78.2
099 PAINTING & WALL COVERINGS	104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3	100.9	48.3	70.3	102.4	59.0	77.2
9 FINISHES	107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1	105.7	47.8	76.2	91.5	62.0	76.5
10-14 TOTAL DIV. 10-14	100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8	100.0	69.4	93.5	100.0	73.6	94.4
15 MECHANICAL	100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7	100.0	46.2	76.2	100.0	52.1	78.8
16 ELECTRICAL	97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2	93.3	49.4	64.0	91.4	63.3	72.7
1-16 WEIGHTED AVERAGE	99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5	97.1	55.7	77.1	95.4	65.4	80.9

DIVISION	GEORGIA						HAWAII			IDAHO					
	SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2
031 CONCRETE FORMWORK	97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0
032 CONCRETE REINFORCEMENT	100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6
033 CAST IN PLACE CONCRETE	91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8
3 CONCRETE	88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1
4 MASONRY	86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8
5 METALS	97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1
6 WOOD & PLASTICS	93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2
7 THERMAL & MOISTURE PROTECTION	96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7
8 DOORS & WINDOWS	95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7
092 LATH, PLASTER & GYPSUM BOARD	101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8
096 FLOORING & CARPET	113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2
099 PAINTING & WALL COVERINGS	100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3
9 FINISHES	105.8	60.5	82.8	101.9	50.0	75.5	124.5	153.9	139.5	93.2	84.6	88.8	156.4	89.0	122.1
10-14 TOTAL DIV. 10-14	100.0	71.7	94.0	100.0	70.1	93.7	100.0	129.2	106.2	100.0	86.1	97.0	100.0	100.6	100.1
15 MECHANICAL	100.0	55.8	80.5	100.0	48.7	77.3	100.1	119.4	108.6	99.8	85.6	93.5	100.6	94.1	97.7
16 ELECTRICAL	93.3	65.4	74.7	90.2	40.8	57.2	109.7	128.8	122.5	85.2	78.7	80.9	87.5	92.2	90.6
1-16 WEIGHTED AVERAGE	97.2	64.6	81.4	96.8	55.0	76.6	115.9	129.5	122.5	101.0	85.2	93.4	111.9	92.1	102.3

ECO NUMBER 5

REPAIR HTW LEAKS IN THE MECHANICAL EQUIPMENT ROOMS

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-5

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-5 REPAIR HTW LEAKS IN MECHANICAL ROOMS

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	3804.		
B. SIOH	\$	229.		
C. DESIGN COST	\$	229.		
D. TOTAL COST (1A+1B+1C)	\$	4262.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		4262.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 29.	15.08	\$ 435.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1612.	\$ 2160.	14.88	\$ 32142.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1614.	\$ 2189.		\$ 32577.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	235.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	3497.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 3497.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 2424.

5. SIMPLE PAYBACK PERIOD (1G/4) 1.76 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 36074.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 8.46
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: ECO-5X
 LCCID FY95 (92)
 INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: ECO-5 REPAIR HTW LEAKS IN MECHANICAL ROOMS
 FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A
 ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	3804.	
B. SIOH	\$	229.	
C. DESIGN COST	\$	229.	
D. TOTAL COST (1A+1B+1C)	\$	4262.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		4262.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 29.	15.08	\$ 435.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1393.	\$ 1867.	14.88	\$ 27775.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1395.	\$ 1895.		\$ 28210.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	235.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	3497.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 3497.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 2130.

5. SIMPLE PAYBACK PERIOD (1G/4) 2.00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 31707.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 7.44
 (IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY
 ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) STUDY: ECO-5Y
 LCCID FY95 (92)
 INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3
 PROJECT NO. & TITLE: ECO-5 REPAIR HTW LEAKS IN MECHANICAL ROOMS
 FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A
 ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	3804.	
B. SIOH	\$	229.	
C. DESIGN COST	\$	229.	
D. TOTAL COST (1A+1B+1C)	\$	4262.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	4262.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 29.	15.08	\$ 435.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1232.	\$ 1651.	14.88	\$ 24565.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1234.	\$ 1680.		\$ 25000.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	235.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	3497.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 3497.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1915.

5. SIMPLE PAYBACK PERIOD (1G/4) 2.23 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 28497.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 6.69
 (IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
REPAIR MECH. RM. LEAKS
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-8-96
DATE _____

ECO-5 SUMMARY

ANNUAL SAVINGS

$$\text{HEATING FUELS} = 1750 - 138 = \boxed{1612 \text{ MBTU/YR}}$$

$$\text{ELECTRICITY} = 2.3 - 0.2 = \boxed{2.1 \text{ MBTU/YR}}$$

$$\text{WATER} = \$256 - \$20 = \boxed{\$236/\text{YR}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Leaks in Mech. Rooms
ECO Number: 5

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$459900 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 1189.7 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 1189.7 \text{ MBtu/yr} / 0.68 = 1749.6 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 1749.6 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$2,344 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.88 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.09 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.09 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.08 \text{ kW}$$

$$\text{Electricity Use} = 0.08 \text{ kW} \times 8760 \text{ Hr/Yr} = 669 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 669 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 2.3 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 669 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$31 \text{ /Year}$$

Water Cost:

$$459900 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$256 \text{ /Year}$$

Total Utility Cost:

Heating Fuel Cost	\$2,344 /Year
Pumping (Elec) Cost	\$31 /Year
Water Cost	\$256 /Year
<hr/>	
Total Utility Cost	\$2,631 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Repair Leaks in Mech. Rooms
ECO Number: 5

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$36260 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 93.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 93.8 \text{ MBtu/yr} / 0.68 = \underline{137.9 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 137.9 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$185 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.07 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.01 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.01 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.01 \text{ kW}$$

$$\text{Electricity Use} = 0.01 \text{ kW} \times 8760 \text{ Hr/Yr} = 53 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 53 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = \underline{0.2 \text{ MBtu/Yr}}$$

$$\text{Electricity Cost} = 53 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$2 \text{ /Year}$$

Water Cost:

$$36260 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \underline{\$20 \text{ /Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$185 /Year
Pumping (Elec) Cost	\$2 /Year
Water Cost	\$20 /Year
Total Utility Cost	<u>\$207 /Year</u>



SUBJECT Fort Stewart
Repair Leaks in ME Rooms
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-6-76
DATE _____

HTW Losses

The spreadsheet on the following pages lists the leaks found in all of the mechanical rooms. The leaks were measured with a beaker and timed with a stopwatch.

Major Leaks:

There are 8 major leaks totaling 0.737 GPM

$$0.737 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} = 387,370 \text{ GAL/YR}$$

Assume all of these leaks can be repaired.

Minor Leaks:

There are 38 minor leaks totaling 0.138 GPM

Assume 50% of the leaks can be repaired.

$$0.138 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} \times 0.5 = 36,270 \text{ GAL/YR}$$

$$\text{Current HTW losses} = 0.875 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} = \underline{459,900 \frac{\text{GAL}}{\text{YR}}}$$

$$\text{Savings} = (387,370 + 36,270) \text{ GAL/YR} = 423,640 \frac{\text{GAL}}{\text{YR}}$$

$$\text{New HTW losses} = 459,900 \frac{\text{GAL}}{\text{YR}} - 423,640 \frac{\text{GAL}}{\text{YR}} = \underline{36,260 \frac{\text{GAL}}{\text{YR}}}$$

There are 36 leaking valves. Assuming 25% of them will have to be replaced:

$$36 \text{ valves} \times .25 \Rightarrow 9 \text{ valves to be replaced}$$

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
206	3	Learning Center	80	DHW	Y	Y	Y	2.00	0.33
207	3	Dining Facility	124	DHW	Y	N	N		
208	3	Fitness Center	113	DHW	Y	Y	N	0.06	
211	3	Admin.	N/A	N/A	Y	Y	N	4.00	
212	3	Admin/Barracks	131	DHW	Y	N	N		
213	3	Barracks	120	DHW	Y	N	N		
215	3	Barracks	137	DHW	Y	Y	N	2.00	1.50
216	3	Barracks	110	DHW	Y	Y	N	2.50	
217	3	Admin.	N/A	N/A	Y	Y	N	0.13	
218	3	Barracks	124	DHW	Y	N	Y		
223	3	Admin.	N/A	N/A	Y	Y	N	0.17	
224	3	Admin.	N/A	N/A	Y	Y	N	5.00	6.67
225	3	Admin.	N/A	N/A	Y	N	N		
230	3	Tac Equip Shop	N/A	N/A	Y	N	N		
241	3	Tac Equip Shop	N/A	N/A	Y	N	N		
260	3	Tac Equip Shop	N/A	N/A	Y	N	N		
270	3	Tac Equip Shop	N/A	N/A	Y	Y	N	2.20	
276	3	Tac Equip Shop	N/A	N/A	N				
302	3	Hospital	137	DHW	Y	N	N		
403	N/A	Child Care Ctr	N/A	N/A	Y	N/A	N		
439	N/A	Fitness Center	139	DHW	Y	N/A	N		
440	2	Dental Clinic	114	DHW	Y	N	N		
501	2	Barracks	134	DHW	Y	Y	N	0.33	
503	2	Barracks	122	DHW	Y	Y	N	2.00	0.25
504	2	Barracks	158	DHW	Y	Y	N		0.75
506	2	Admin.	N/A	N/A	Y	N	N		
507	2	Admin.	N/A	N/A	Y	Y	N	1.00	
508	2	Admin.	N/A	N/A	Y	N	N		
509	2	Admin.	N/A	N/A	Y	N	Y		
512	2	Dining Facility	145	DHW	Y	?	Y		1.17
514	2	Barracks	126	DHW	Y	Y	N	1.25	
515	2	Barracks	123	DHW	Y	N	Y		
516	2	Barracks	145	DHW	Y	?	Y		
517	2	Barracks	175	DHW	LOCKED				
518	2	Barracks	183	DHW	Y	?	Y	3.33	
520	2	Admin.	N/A	N/A	Y	N	Y		
521	2	Admin.	N/A	N/A	Y	Y	N	0.50	
522	2	Admin.	N/A	N/A	Y	Y	N	0.25	
523	2	Admin.	N/A	N/A	Y	N	N		
524	2	Admin.	N/A	N/A	Y	N	N		
525	2	Admin.	N/A	N/A	Y	Y	N	0.09	

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
608	2	Fitness Center	127	DHW	Y	Y	N	0.08	
610	2	Chapel	115	DHW	Y	N	N		
612	2	Admin.	N/A	N/A	Y	Y	Y	0.08	
614	1	Admin.	N/A	N/A	Y	N	Y		
616	1	Admin.	N/A	N/A	Y	N	Y		
617	1	Admin.	N/A	N/A	Y	N	N		
618	1	Admin.	N/A	N/A	Y	N	N		
619	1	Admin.	N/A	N/A	Y	N	N		
620	1	Admin.	112	DHW	Y	N	N		
621	1	Admin.	91	DHW	Y	N	N		
622	1	Admin.	85	DHW	Y	N	N		
623	1	Admin.	109	DHW	Y	N	Y		
624	1	Admin.	109	DHW	Y	N	Y		
626	1	Dining Facility	145	DHW	Y	N	N		
628	1	Admin.	N/A	N/A	Y	Y	N	0.20	
629	1	Barracks	160	DHW	Y	?	Y		
630	1	Barracks	117	DHW	Y	N	Y		
631	1	Barracks	142	DHW	Y	Y	Y		0.88
632	1	Barracks	160	DHW	Y	N	Y		
633	1	Barracks	128	DHW	Y	Y	Y	2.00	
634	1	Barracks	LOCKED	LOCKED	Y	N	N		
635	1	Barracks	140	DHW	Y	Y	N	1.59	
636	1	Barracks	138	DHW	Y	Y	Y	1.22	
637	1	Barracks	158	DHW	Y	N	N		
638	1	Admin.	N/A	N/A	Y	N	Y		
639	1	Admin.	N/A	N/A	Y	Y	N	1.56	
640	1	Admin.	N/A	N/A	Y	N	N		
641	1	Admin.	N/A	N/A	Y	N	N		
642	1	Dining Facility	154	DHW	Y	N	Y		
643	1	Admin.	N/A	N/A	Y	Y	N	0.10	
644	1	Admin.	N/A	N/A	Y	Y	N	0.33	
645	1	Admin.	N/A	N/A	Y	N	N		
646	1	Admin.	N/A	N/A	Y	N	N		
647	1	Admin.	N/A	N/A	Y	Y	N	0.20	
648	1	Admin.	N/A	N/A	Y	N	Y		
649	1	Admin.	N/A	N/A	Y	N	N		

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
701	1	Health Clinic	152	DHW	Y	Y	N	1.00	
702	1	Ent. Center	143	DHW	Y	N	N		
703	1	Enl. Mens Club	N/A	N/A	LOCKED		Y		
704	1	Theater	N/A	N/A	Y	N	Y		
706	1	Branch Exchange	N/A	N/A	Y	N	Y		
708	1	Fitness Center	131	DHW	Y	N	Y		
710	1	Admin.	N/A	N/A	Y	N	Y		
712	1	Barracks	135	DHW	Y	N	Y		
713	1	Barracks	133	DHW	Y	N	Y		
714	1	Barracks	137	DHW	Y	N	Y		
715	1	Barracks	135	DHW	Y	Y	N	0.20	
717	1	Barracks	131	DHW	Y	N	N		
718	1	Barracks	124	DHW	Y	Y	Y	0.20	
719	1	Barracks	112	DHW	Y	Y	N	1.00	
720	1	Barracks	130	DHW	Y	N	Y		
721	1	Admin.	N/A	N/A	Y	N	N		
722	1	Admin.	N/A	N/A	Y	Y	Y	5.00	
723	1	Admin.	N/A	N/A	Y	N	N		
724	1	Admin.	N/A	N/A	Y	N	N		
725	1	Admin.	N/A	N/A	Y	N	N		
726	1	Dining Facility	158	DHW	Y	N	Y		
727	N/A	Training Facility	N/A	N/A	Y	N/A	N		
728	1	Admin.	N/A	N/A	Y	Y	N	3.05	
810	1	Barracks	131	DHW	Y	N	N		
811	1	Admin.	N/A	N/A	Y	N	N		
812	1	Admin.	N/A	N/A	Y	N	N		
813	1	Admin.	N/A	N/A	Y	N	N		
814	1	Admin.	N/A	N/A	Y	N	Y		
815	1	Admin.	N/A	N/A	Y	N	N		
816	1	Admin.	N/A	N/A	Y	N	Y		
818	1	Admin.	N/A	N/A	Y	N	N		
819	1	Admin.	N/A	N/A	Y	Y	N	0.13	

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
1160	3	D.S. Maint Fac	N/A	N/A	Y	Y	N	2.03	
1170	3	G.S. Maint Fac	N/A	N/A	Y	N	N		
1208	1	Tac Equip Shop	N/A	N/A	Y	N	Y		
1209	1	Tac Equip Shop	N/A	N/A	Y	N	N		
1211	1	Tac Equip Shop	N/A	N/A	Y	N	N		
1245	N/A	Tac Equip Shop	N/A	N/A	Y	N/A	Y		
1259	1	Tac Equip Shop	N/A	N/A	Y	Y	N		0.25
1261	2	Tac Equip Shop	N/A	N/A	N				
1265	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1280	N/A	Tac Equip Shop	N/A	N/A	Y	N/A	Y		
1320	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1330	2	Tac Equip Shop	N/A	N/A	Y	Y	N	0.13	
1340	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1412		C. Energy Plant	N/A	HTW	Y	Y			
1500	3	Div Logis Fac	N/A	N/A	w/ 1509?				
1503	3	Auto Hobby Shop	N/A	N/A	LOCKED				
1509	3	Div Logis Fac	N/A	N/A	Y	Y	Y	3.00	
1510	3	Tac Equip Shop	N/A	N/A	N				
1540	3	Tac Equip Shop	95	PW	N				
1720	2	D.S. Maint Fac	148	DHW	Y	N-N/A	N		
1810	2	Tac Equip Shop	N/A	N/A	N				
1820	2	Tac Equip Shop	N/A	N/A	Y	N-N/A	N		
1840	2	Tac Equip Shop	N/A	N/A	Y	N	Y		
2115	1	Dental Clinic	N/A	N/A	Y	N	N		
2125	1	Chapel	120	DHW	Y	N	N		
3001	S	S. Energy Plant	N/A	N/A	Y	Y			
3002	S	Admin.	N/A	N/A	Y	Y	N	5.20	
4502	S	Tac Equip Shop	N/A	N/A	N				
4528	S	Tac Equip Shop	N/A	N/A	N				
4577	S	Tac Equip Shop	N/A	N/A	N				
4578	S	Tac Equip Shop	N/A	N/A	N				

TOTALS	140				127	42	41	55.11 Drop/Sec	11.80 Cup/Min
Leaks (GPM) =								0.138	0.737
% of Total =								16%	84%
Total Leaks =								0.875 GPM	

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Leaks in Mechanical Rooms
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 5

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-5.WQ1

[illegible]


LEGEND:

- (1) Estimate 10 minutes per building for 42 buildings.
 (2) Estimate 10 minutes per valve for 27 valves (also see note 4).
 (3) Estimate 10 minutes per flange for 14 flanges.
 (4) Assumes 25 % of the 36 leaking valves will be replaced.
- MMp### 1996 Means Mechanical Cost Data, page ###.

151 | Pipe & Fittings

151 950 | Valves

R151
-090



	CREW	DAILY OUTPUT	LABOR- HOURS	UNIT	1996 BARE COSTS				TOTAL INCL O&P
					MAT.	LABOR	EQUIP.	TOTAL	
1050 3" size	Q-1	8	2	Ea.	175	54		229	276
1060 4" size	↓	5	3.200		215	86.50		301.50	370
1070 5" size	Q-2	5	4.800		250	135		385	480
1080 6" size	↓	5	4.800		273	135		408	505
1090 8" size	↓	4.50	5.333		360	150		510	625
1100 10" size	↓	4	6		415	168		583	715
1110 12" size	↓	3	8	↓	570	224		794	970
1200 Lug type, lever actuator									
1220 2" size	1 Plum	14	.571	Ea.	87	17.15		104.15	122
1230 2-1/2" size	Q-1	9	1.778		89	48		137	172
1240 3" size	↓	8	2		95	54		149	188
1250 4" size	↓	5	3.200		121	86.50		207.50	265
1260 5" size	Q-2	5	4.800		175	135		310	400
1270 6" size	↓	5	4.800		197	135		332	425
1280 8" size	↓	4.50	5.333		281	150		431	540
1290 10" size	↓	4	6		390	168		558	690
1300 12" size	↓	3	8	↓	595	224		819	1,000
1320 For gear actuator, add				↓	60%				
1400 Diverter, 150 lb. flanged, bronze or iron plugs									
1440 2" pipe size	Q-1	2	8	Ea.	2,475	216		2,691	3,050
1450 3" pipe size	"	1.50	10.667	"	3,550	289		3,839	4,350
1650 Gate, 125 lb., N.R.S.,									
2150 Flanged									
2200 2" size	1 Plum	5	1.600	Ea.	252	48		300	350
2240 2-1/2" size	Q-1	5	3.200		258	86.50		344.50	415
2260 3" size	↓	4.50	3.556		290	96		386	465
2280 4" size	↓	3	5.333		415	144		559	675
2290 5" size	Q-2	3.40	7.059		705	198		903	1,075
2300 6" size	↓	3	8		705	224		929	1,125
2320 8" size	↓	2.50	9.600		1,225	269		1,494	1,750
2340 10" size	↓	2.20	10.909		2,150	305		2,455	2,850
2360 12" size	↓	1.70	14.118		2,950	395		3,345	3,850
2370 14" size	↓	1.30	18.462		3,575	520		4,095	4,725
2380 16" size	↓	1	24		5,225	675		5,900	6,775
2420 For 250 lb., flanged, add				↓	200%	10%			
3550 OS&Y, flanged									
3600 2" size	1 Plum	5	1.600	Ea.	128	48		176	215
3640 2-1/2" size	Q-1	5	3.200		132	86.50		218.50	277
3660 3" size	↓	4.50	3.556		149	96		245	310
3670 3-1/2" size	↓	3	5.333		212	144		356	455
3680 4" size	↓	3	5.333		212	144		356	455
3690 5" size	Q-2	3.40	7.059		350	198		548	690
3700 6" size	↓	3	8		350	224		574	730
3720 8" size	↓	2.50	9.600		625	269		894	1,100
3740 10" size	↓	2.20	10.909		1,150	305		1,455	1,750
3760 12" size	↓	1.70	14.118		1,525	395		1,920	2,275
3770 14" size	↓	1.30	18.462		2,950	520		3,470	4,050
3780 16" size	↓	1	24		4,575	675		5,250	6,050
3790 18" size	↓	.80	30		6,125	840		6,965	8,050
3800 20" size	↓	.60	40		8,550	1,125		9,675	11,100
3830 24" size	↓	.50	48	↓	12,700	1,350		14,050	16,100
3900 For 250 lb flanged, add				↓	200%	10%			
4350 Globe, OS&Y,									
4540 Class 125, flanged									
4550 2" size	1 Plum	5	1.600	Ea.	266	48		314	365
4560 2-1/2" size	Q-1	5	3.200	↓	281	86.50		367.50	440

Installing Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of state rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with smaller annual billing. The overhead percentages for any given contractor may vary greatly and depend on a number of factors, such as the contractor's annual volume, engineering and logistical support costs, and staff requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevailing economic conditions. All factors should be examined very carefully for each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

		A		B	C	D	E	F	G	H	I
Abbr.	Trade	Base Rate Incl. Fringes		Work-ers' Comp. Ins.	Average Fixed Over-head	Over-head	Profit	Total Overhead & Profit		Rate with O & P	
		Hourly	Daily					%	Amount	Hourly	Daily
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10%	60.0%	\$15.55	\$41.50	\$332.00
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40	30.65	245.20
	Foreman Average, Inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85	42.30	338.40
	Foreman Average, Outside (\$.20 over trade)	27.95	223.60	20.2		13.0		60.0	16.75	44.70	357.60
	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80	31.60	252.80
Clab											
Asbe	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85	46.40	371.20
Boil	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20	48.25	386.00
Bric	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
Brhe	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45	31.45	251.60
Carp	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05	40.25	322.00
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30	36.65	293.20
Elec	Electricians	29.30	234.40	8.0		16.0		50.8	14.90	44.20	353.60
Elev	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75	45.80	366.40
Eqhv	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35	41.10	328.80
Eqmd	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80	39.50	316.00
Eqit	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25	37.95	303.60
Eqol	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75	33.65	269.20
Eqmm	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80	42.35	338.80
Glaz	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40	38.30	306.40
Lath	Lathers	24.95	199.60	13.5		11.0		51.3	12.80	37.75	302.00
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65	40.30	322.40
Mill	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55	40.10	320.80
Mstz	Mosaic & Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30	37.55	300.40
Pord	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55	35.50	284.00
Psst	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00	47.95	383.60
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70	36.00	288.00
Pile	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35	44.70	357.60
Plas	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35	37.55	300.40
Plah	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10	31.25	250.00
Plum	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95	46.00	368.00
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40	49.15	393.20
Rofc	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95	39.50	316.00
Rots	Roofers, Tile & Slate	22.60	180.80	37.4		11.0		75.2	17.00	39.60	316.80
Rohe	Roofers, Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00	27.95	223.60
Shee	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40	45.35	362.80
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65	47.95	383.60
Stpi	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05	46.35	370.80
Ston	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
Sswk	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
Tilf	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20	37.25	298.00
Tilh	Tile Layers Helpers	20.30	162.40	11.0		11.0		48.8	9.90	30.20	241.60
Trit	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15	31.50	252.00
Trhv	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35	32.05	256.40
Sswl	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
Wrck	*Wrecking	19.80	158.40	44.8	↓	11.0	↓	82.6	16.35	36.15	289.20

Not included in Averages.

City Cost Indexes

DIVISION	FLORIDA																	
	MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6
031 CONCRETE FORMWORK	94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7
032 CONCRETE REINFORCEMENT	95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3
033 CAST IN PLACE CONCRETE	91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5
3 CONCRETE	87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3
4 MASONRY	76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4
5 METALS	98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0
6 WOOD & PLASTICS	88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0
7 THERMAL & MOISTURE PROTECTION	99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1
8 DOORS & WINDOWS	95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4
092 LATH, PLASTER & GYPSUM BOARD	101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9
096 FLOORING & CARPET	121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8
099 PAINTING & WALL COVERINGS	100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0
9 FINISHES	108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3
10-14 TOTAL DIV. 10-14	100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5
15 MECHANICAL	100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0
16 ELECTRICAL	98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5
1-16 WEIGHTED AVERAGE	97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9
DIVISION	FLORIDA						GEORGIA											
	TAMPA			ALBANY			ATLANTA			AUGUSTA			COLUMBUS			MACON		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8	110.4	74.3	82.6	111.6	91.9	96.5
031 CONCRETE FORMWORK	97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7	96.9	50.4	57.4	95.9	65.9	70.5
032 CONCRETE REINFORCEMENT	95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4	95.1	76.4	84.6	97.4	76.7	85.8
033 CAST IN PLACE CONCRETE	101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5	95.5	49.5	75.8	95.5	53.3	77.5
3 CONCRETE	92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2	89.4	57.0	73.0	89.7	65.1	77.3
4 MASONRY	82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4	83.4	39.3	56.0	98.6	46.7	66.4
5 METALS	102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7	96.7	89.3	93.9	91.7	90.1	91.1
6 WOOD & PLASTICS	94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3	93.7	51.3	72.5	97.4	69.9	83.6
7 THERMAL & MOISTURE PROTECTION	96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9	96.1	55.7	77.5	95.1	62.9	80.2
8 DOORS & WINDOWS	98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1	95.9	53.8	85.7	94.2	64.8	87.1
092 LATH, PLASTER & GYPSUM BOARD	101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7	101.6	50.4	68.4	108.3	69.5	83.2
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8	102.4	50.4	68.7	95.9	69.5	78.8
096 FLOORING & CARPET	113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2	113.0	41.0	95.7	87.8	47.5	78.2
099 PAINTING & WALL COVERINGS	104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3	100.9	48.3	70.3	102.4	59.0	77.2
9 FINISHES	107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1	105.7	47.8	76.2	91.5	62.0	76.5
10-14 TOTAL DIV. 10-14	100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8	100.0	69.4	93.5	100.0	73.6	94.4
15 MECHANICAL	100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7	100.0	46.2	76.2	100.0	52.1	78.8
16 ELECTRICAL	97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2	93.3	49.4	64.0	91.4	63.3	72.7
1-16 WEIGHTED AVERAGE	99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5	97.1	55.7	77.1	95.4	65.4	80.9
DIVISION	GEORGIA						HAWAII			IDAHO								
	SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON			POCATELLO		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2	89.1	99.3	96.9
031 CONCRETE FORMWORK	97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0	97.4	89.3	90.5
032 CONCRETE REINFORCEMENT	100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6	96.3	78.5	86.3
033 CAST IN PLACE CONCRETE	91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8	99.6	93.8	97.1
3 CONCRETE	88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1	103.7	88.6	96.1
4 MASONRY	86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8	136.3	82.7	103.0
5 METALS	97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1	112.5	82.2	101.1
6 WOOD & PLASTICS	93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2	95.1	88.5	91.8
7 THERMAL & MOISTURE PROTECTION	96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7	98.0	83.8	91.5
8 DOORS & WINDOWS	95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7	94.9	78.5	91.0
092 LATH, PLASTER & GYPSUM BOARD	101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4	89.0	87.9	88.3
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8	96.2	87.9	90.8
096 FLOORING & CARPET	113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2	97.5	74.8	92.1
099 PAINTING & WALL COVERINGS	100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3	109.4	78.2	91.3
9 FINISHES	105.8	60.5	82.8	101.9	50.0	75.5	124.5	153.9	139.5	93.2	84.6	88.8	156.4	89.0	122.1	93.2	85.8	89.4
10-14 TOTAL DIV. 10-14	100.0	71.7	94.0	100.0	70.1	93.7	100.0	129.2	106.2	100.0	86.1	97.0	100.0	100.6	100.1	100.0	86.1	97.0
15 MECHANICAL	100.0	55.8	80.5	100.0	40.7	77.3	100.1	119.4	108.6	99.8	85.6	93.5	100.6	94.1	97.7	99.8	85.6	93.5
16 ELECTRICAL	93.3	65.4	74.7	90.2	48.8	57.2	109.7	128.8	122.5	85.2	78.7	80.9	87.5	92.2	90.6	85.7	79.4	81.5
1-16 WEIGHTED AVERAGE	97.2	64.6	81.4	96.8	55.0	76.6	115.9	129.5	122.5	101.0	85.2	93.4	111.9	92.1	102.3	101.3	85.5	93.7

A.3.5-16

ECO NUMBER 6

REPAIR BUILDING SIDE DHW AND HVAC HOT WATER LEAKS

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-6

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-6 REPAIR DHW AND HHW LEAKS

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	1448.		
B. SIOH	\$	87.		
C. DESIGN COST	\$	87.		
D. TOTAL COST (1A+1B+1C)	\$	1622.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		1622.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1111.	\$ 1489.	14.88	\$ 22152.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1111.	\$ 1489.		\$ 22152.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		
(1) DISCOUNT FACTOR (TABLE A)	14.88	\$ 530.
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 7886.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 7886.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 2019.

5. SIMPLE PAYBACK PERIOD (1G/4) .80 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 30039.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 18.52
(IF < 1 PROJECT DOES NOT QUALIFY)

Location: Fort Stewart, GA
 AEP Number: 694-1331-002
 Project: Repair DHW and HHW Leaks
 ECO Number: 6

Reynolds, Smith and Hills, Inc.
 Designer: W. T. Todd
 Date: 02/08/96

Assumptions:

1. HHW temperature	180 °F
2. Make-up water temperature	70 °F
3. Condensate temperature	200 °F
4. Boiler efficiency	68%
5. Average heating fuel cost	\$1.34 /MBtu
6. Water cost	\$0.5562 /kGallons

Bldg.	Leak	Location	Cup/Min	Drop/Sec	GPM	Temp., °F	MBtu/Yr
218	DHW	from circ. pump	1.0		0.0625	124	14.8
512	COND	from T at cond. tank		10.0	0.0250	200	14.2
515	DHW	from circ. pump		1.0	0.0025	123	0.6
516	DHW	from relief valve	6.0		0.3750	125	90.4
518	DHW	from relief valve	3.5		0.2188	183	108.4
624	COND	from near cond. tank		12.0	0.0300	200	17.1
629	HHW	from relief valve	6.0		0.3750	211	231.8
630	HHW	from relief valve		0.2	0.0005	180	0.2
630	HHW	from air separator		0.4	0.0010	180	0.5
631	HHW	supply side of ht ex		1.0	0.0025	180	1.2
633	HHW	from relief valve		1.0	0.0025	180	1.2
636	DHW	from HWG drain pipe		15.0	0.0375	138	11.2
638	HHW	from circ. pump		0.3	0.0008	180	0.4
642	DHW	from pipe above tank		5.0	0.0125	154	4.6
644	HHW	from relief valve	1.1		0.0703	180	33.9
648	HHW	from relief valve		1.0	0.0025	180	1.2
706	HHW	from circ. pump		3.0	0.0075	180	3.6
708	HHW	from relief valve		5.0	0.0125	180	6.0
708	DHW	from relief valve	1.0		0.0625	131	16.7
722	HHW	from circ. pump		2.0	0.0050	200	2.8
726	COND	at cond. tank		1.0	0.0025	200	1.4
726	DHW	from circ. pump		5.0	0.0125	158	4.8
814	HHW	from circ. pump		3.0	0.0075	180	3.6
816	HHW	from drain valve		0.1	0.0003	180	0.1
1208	HHW	from drain valve		0.2	0.0005	180	0.2
1245	HHW	from circ. pump		1.0	0.0025	180	1.2
1280	HHW	from relief valve	7.0		0.4375	150	153.4
1509	HHW	from relief valve	2.1		0.1328	180	64.0
1840	HHW	from circ. pump		1.0	0.0025	180	1.2
29	Current HTW Losses		27.8	68.2	1.9049	GPM	791.0 MBtu/Yr
			x 1.00	x 0.50			
	Proposed HTW Savings		27.8	34.1	1.8196	GPM	755.6 MBtu/Yr
	Proposed HTW Losses				0.0853	GPM	35.4 MBtu/Yr

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

Current Fuel Use = 791.0 MBtu/yr / 0.68 = 1163.2 MBtu/Yr
 Current Fuel Cost = 1163.2 MBtu/yr x \$1.34 /MBtu = \$1,559 /Year

New Fuel Use = 35.4 MBtu/yr / 0.68 = 52.1 MBtu/Yr
 New Fuel Cost = 52.1 MBtu/yr x \$1.34 /MBtu = \$70 /Year

Water Cost:

Current water cost = 1001224 Gal/Yr x \$0.5562 /kGal = \$557 /Year
 New water cost = 44818 Gal/Yr x \$0.5562 /kGal = \$25 /Year

CONSTRUCTION COST ESTIMATE

Project: Repair DHW and HHW Leaks in Mechanical Rooms
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 6

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-6.WQ1

[illegible]

LEGEND:

- (1) Estimate 10 minutes per building for 26 buildings.
 (2) Estimate 20 minutes per fitting for 18 fittings.
 MMp### 1996 Means Mechanical Cost Data, page ###.

151 | Pipe & Fittings

151 950 | Valves

			CREW	DAILY OUTPUT	LABOR- HOURS	UNIT	1996 BARE COSTS				TOTAL INCL O&P
							MAT.	LABOR	EQUIP.	TOTAL	
955	3420	3/8" size	1 Plum	24	.333	Ea.	18.50	10		28.50	36
	3430	1/2" size		24	.333		16.65	10		26.65	33.50
	3440	3/4" size		20	.400		19.80	12		31.80	40.50
	3450	1" size		19	.421		26	12.65		38.65	48
	3460	1-1/4" size		15	.533		35	16.05		51.05	63
	3470	1-1/2" size		13	.615		43	18.50		61.50	76
	3480	2" size		11	.727		59.50	22		81.50	99
	3490	2-1/2" size	Q-1	15	1.067		138	29		167	196
	3500	3" size		13	1.231		195	33.50		228.50	266
	3850	Rising stem, soldered, 300 psi									
	3900	3/8" size	1 Plum	24	.333	Ea.	25	10		35	43
	3920	1/2" size		24	.333		29	10		39	47.50
	3940	3/4" size		20	.400		37.50	12		49.50	60
	3950	1" size		19	.421		41	12.65		53.65	65
	3960	1-1/4" size		15	.533		69	16.05		85.05	100
	3970	1-1/2" size		13	.615		78.50	18.50		97	115
	3980	2" size		11	.727		110	22		132	155
	3990	2-1/2" size	Q-1	15	1.067		251	29		280	320
	4000	3" size		13	1.231		350	33.50		383.50	435
	4250	Threaded, class 150									
	4310	1/4" size	1 Plum	24	.333	Ea.	16.85	10		26.85	34
	4320	3/8" size		24	.333		16.85	10		26.85	34
	4330	1/2" size		24	.333		16	10		26	33
	4340	3/4" size		20	.400		19.10	12		31.10	39.50
	4350	1" size		19	.421		25	12.65		37.65	47
	4360	1-1/4" size		15	.533		34	16.05		50.05	62
	4370	1-1/2" size		13	.615		41.50	18.50		60	74
	4380	2" size		11	.727		57.50	22		79.50	97
	4390	2-1/2" size	Q-1	15	1.067		133	29		162	190
	4400	3" size		13	1.231		187	33.50		220.50	257
	4500	For 300 psi, threaded, add					100%	15%			
	4540	For chain operated type, add					15%				
	4850	Globe, class 150, rising stem, threaded									
	4920	1/4" size	1 Plum	24	.333	Ea.	23.50	10		33.50	41.50
	4940	3/8" size		24	.333		23.50	10		33.50	41.50
	4950	1/2" size		24	.333		23.50	10		33.50	41.50
	4960	3/4" size		20	.400		32	12		44	53.50
	4970	1" size		19	.421		50	12.65		62.65	74.50
	4980	1-1/4" size		15	.533		78.50	16.05		94.55	111
	4990	1-1/2" size		13	.615		94.50	18.50		113	133
	5000	2" size		11	.727		143	22		165	191
	5010	2-1/2" size	Q-1	15	1.067		287	29		316	360
	5020	3" size		13	1.231		410	33.50		443.50	500
	5120	For class 300, threaded, add					50%	15%			
	5130	Globe, 300 lb., sweat, 3/8" size	1 Plum	24	.333		26	10		36	44
	5140	1/2" size		24	.333		26	10		36	44
	5150	3/4" size		20	.400		38	12		50	60.50
	5160	1" size		19	.421		57	12.65		69.65	82
	5170	1-1/4" size		15	.533		87	16.05		103.05	120
	5180	1-1/2" size		13	.615		104	18.50		122.50	143
	5190	2" size		11	.727		157	22		179	207
	5200	2-1/2" size	Q-1	15	1.067		345	29		374	425
	5210	3" size		13	1.231		505	33.50		538.50	605
	5600	Relief, pressure & temperature, self-closing, ASME									
	5640	3/4" size	1 Plum	28	.286	Ea.	51.50	8.60		60.10	69.50
	5650	1" size		24	.333		79	10		89	102

A.3.6-5

Installing Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of state rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with smaller annual billing. The overhead percentages for any given contractor may vary greatly and depend on a number of factors, such as the contractor's annual volume, engineering and logistical support costs, and staff requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevailing economic conditions. All factors should be examined very carefully for each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

		A		B	C	D	E	F	G	H	I
Abbr.	Trade	Base Rate Incl. Fringes		Work-ers' Comp. Ins.	Average Fixed Over-head	Over-head	Profit	Total Overhead & Profit		Rate with O & P	
		Hourly	Daily					%	Amount	Hourly	Daily
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10%	60.0%	\$15.55	\$41.50	\$332.00
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40	30.65	245.20
	Foreman Average, Inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85	42.30	338.40
	Foreman Average, Outside (\$2.00 over trade)	27.95	223.60	20.2		13.0		60.0	16.75	44.70	357.60
	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80	31.60	252.80
Clab											
Asbe	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85	46.40	371.20
Boil	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20	48.25	386.00
Bric	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
Brhe	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45	31.45	251.60
Carp	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05	40.25	322.00
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30	36.65	293.20
Elec	Electricians	29.30	234.40	8.0		16.0		50.8	14.90	44.20	353.60
Elev	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75	45.80	366.40
Eqhv	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35	41.10	328.80
Eqmd	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80	39.50	316.00
Eqlt	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25	37.95	303.60
Eqol	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75	33.65	269.20
Eqmm	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80	42.35	338.80
Glaz	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40	38.30	306.40
Lath	Lathers	24.95	199.60	13.5		11.0		51.3	12.80	37.75	302.00
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65	40.30	322.40
Mill	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55	40.10	320.80
Mstz	Mosaic & Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30	37.55	300.40
Pord	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55	35.50	284.00
Psst	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00	47.95	383.60
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70	36.00	288.00
Pile	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35	44.70	357.60
Plas	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35	37.55	300.40
Plah	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10	31.25	250.00
Plum	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95	46.00	368.00
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40	49.15	393.20
Rofc	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95	39.50	316.00
Rots	Roofers, Tile & Slate	22.60	180.80	37.4		11.0		75.2	17.00	39.60	316.80
Rohe	Roofers, Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00	27.95	223.60
Shee	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40	45.35	362.80
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65	47.95	383.60
Stoi	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05	46.35	370.80
Ston	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
Sswk	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
Tilf	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20	37.25	298.00
Tilh	Tile Layers Helpers	20.30	162.40	11.0		11.0		48.8	9.90	30.20	241.60
Trlt	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15	31.50	252.00
Trhv	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35	32.05	256.40
Sswl	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
Wrck	*Wrecking	19.80	158.40	44.8	↓	11.0	↓	82.6	16.35	36.15	289.20

*Not included in Averages.

City Cost Indexes

DIVISION	FLORIDA																					
	MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE						
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	
2 SITE WORK	110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6				
031 CONCRETE FORMWORK	94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7				
032 CONCRETE REINFORCEMENT	95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3				
033 CAST IN PLACE CONCRETE	91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5				
3 CONCRETE	87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3				
4 MASONRY	76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4				
5 METALS	98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0				
6 WOOD & PLASTICS	88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0				
7 THERMAL & MOISTURE PROTECTION	99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1				
8 DOORS & WINDOWS	95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4				
092 LATH, PLASTER & GYPSUM BOARD	101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6				
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9				
096 FLOORING & CARPET	121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8				
099 PAINTING & WALL COVERINGS	100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0				
9 FINISHES	108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3				
10-14 TOTAL DIV. 10-14	100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5				
15 MECHANICAL	100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0				
16 ELECTRICAL	98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5				
1-16 WEIGHTED AVERAGE	97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9				
DIVISION	FLORIDA						GEORGIA															
	TAMPA			ALBANY			ATLANTA			AUGUSTA			COLUMBUS			MACON						
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	
2 SITE WORK	126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8	110.4	74.3	82.6	111.6	91.9	96.5				
031 CONCRETE FORMWORK	97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7	96.9	50.4	57.4	95.9	65.9	70.5				
032 CONCRETE REINFORCEMENT	95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4	95.1	76.4	84.6	97.4	76.7	85.8				
033 CAST IN PLACE CONCRETE	101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5	95.5	49.5	75.8	95.5	53.3	77.5				
3 CONCRETE	92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2	89.4	57.0	73.0	89.7	65.1	77.3				
4 MASONRY	82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4	83.4	39.3	56.0	98.6	46.7	66.4				
5 METALS	102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7	96.7	89.3	93.9	91.7	90.1	91.1				
6 WOOD & PLASTICS	94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3	93.7	51.3	72.5	97.4	69.9	83.6				
7 THERMAL & MOISTURE PROTECTION	96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9	96.1	55.7	77.5	95.1	62.9	80.2				
8 DOORS & WINDOWS	98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1	95.9	53.8	85.7	94.2	64.8	87.1				
092 LATH, PLASTER & GYPSUM BOARD	101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7	101.6	50.4	68.4	108.3	69.5	83.2				
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8	102.4	50.4	68.7	95.9	69.5	78.8				
096 FLOORING & CARPET	113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2	113.0	41.0	95.7	87.8	47.5	78.2				
099 PAINTING & WALL COVERINGS	104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3	100.9	48.3	70.3	102.4	59.0	77.2				
9 FINISHES	107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1	105.7	47.8	76.2	91.5	62.0	76.5				
10-14 TOTAL DIV. 10-14	100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8	100.0	69.4	93.5	100.0	73.6	94.4				
15 MECHANICAL	100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7	100.0	46.2	76.2	100.0	52.1	78.8				
16 ELECTRICAL	97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2	93.3	49.4	64.0	91.4	63.3	72.7				
1-16 WEIGHTED AVERAGE	99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5	97.1	55.7	77.1	95.4	65.4	80.9				
DIVISION	GEORGIA						HAWAII			IDAHO												
	SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON			POCATELLO						
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	
2 SITE WORK	110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2	89.1	99.3	96.9				
031 CONCRETE FORMWORK	97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0	97.4	89.3	90.5				
032 CONCRETE REINFORCEMENT	100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6	96.3	78.5	86.3				
033 CAST IN PLACE CONCRETE	91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8	99.6	93.8	97.1				
3 CONCRETE	88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1	103.7	88.6	96.1				
4 MASONRY	86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8	136.3	82.7	103.0				
5 METALS	97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1	112.5	82.2	101.1				
6 WOOD & PLASTICS	93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2	95.1	88.5	91.8				
7 THERMAL & MOISTURE PROTECTION	96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7	98.0	83.8	91.5				
8 DOORS & WINDOWS	95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7	94.9	78.5	91.0				
092 LATH, PLASTER & GYPSUM BOARD	101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4	89.0	87.9	88.3				
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8	96.2	87.9	90.8				
096 FLOORING & CARPET	113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2	97.5	74.8	92.1				
099 PAINTING & WALL COVERINGS	100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3	109.4	78.2	91.3				
9 FINISHES	105.8	60.5	82.8	101.9	50.0	75.5	124.5	153.9	139.5	93.2	84.6	88.8	156.4	89.0	122.1	93.2	85.8	89.4				
10-14 TOTAL DIV. 10-14	100.0	71.7	94																			

ECO NUMBER 7

REPAIR HTW LEAKS IN VALVE PITS

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-7

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-7 REPAIR HTW LEAKS IN VALVE PITS

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	2480.	
B. SIOH	\$	149.	
C. DESIGN COST	\$	149.	
D. TOTAL COST (1A+1B+1C)	\$	2778.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		2778.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 33.	15.08	\$ 497.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1873.	\$ 2510.	14.88	\$ 37346.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1875.	\$ 2543.		\$ 37843.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	275.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	4092.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
------	------------------------------	-----------------	------------------------	---

d. TOTAL	\$	0.		0.
----------	----	----	--	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)	\$	4092.
---	----	-------

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$	\$	2818.
--	----	-------

5. SIMPLE PAYBACK PERIOD (1G/4)	.99 YEARS
---------------------------------	-----------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$	41935.
--	----	--------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)=	15.10
(IF < 1 PROJECT DOES NOT QUALIFY)	

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-7X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-7 REPAIR HTW LEAKS IN VALVE PITS

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	2480.	
B. SIOH	\$	149.	
C. DESIGN COST	\$	149.	
D. TOTAL COST (1A+1B+1C)	\$	2778.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	2778.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 33.	15.08	\$ 497.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1619.	\$ 2169.	14.88	\$ 32282.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1621.	\$ 2202.		\$ 32779.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	275.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	4092.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 4092.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 2477.

5. SIMPLE PAYBACK PERIOD (1G/4) 1.12 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 36871.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 13.27
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-7Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-7 REPAIR HTW LEAKS IN VALVE PITS

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	2480.	
B. SIOH	\$	149.	
C. DESIGN COST	\$	149.	
D. TOTAL COST (1A+1B+1C)	\$	2778.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	2778.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	2.	\$ 33.	15.08	\$ 497.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	1432.	\$ 1919.	14.88	\$ 28553.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		1434.	\$ 1952.		\$ 29050.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 275.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 4092.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 4092.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 2227.

5. SIMPLE PAYBACK PERIOD (1G/4) 1.25 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 33142.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 11.93
(IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
REPAIR LEAKS IN VALVE PITS
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-8-96
DATE _____

ECO - 7 SUMMARY

ANNUAL SAVINGS

$$\text{ELECTRICITY} = 2.5 - 0.1 = \boxed{2.4 \text{ MBtu/YR}}$$

$$\text{HEATING FUELS} = 1942 - 69 = \boxed{1873 \text{ MBtu/YR}}$$

$$\text{WATER} = \$284 - \$10 = \boxed{\$274 / \text{YR}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Leaks in Valve Pits
ECO Number: 7

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$510360 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 1320.3 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 1320.3 \text{ MBtu/yr} / 0.68 = \underline{1941.6 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 1941.6 \text{ MBtu/yr} \times \$1.34 / \text{MBtu} = \$2,602 / \text{Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.97 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.10 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.10 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.08 \text{ kW}$$

$$\text{Electricity Use} = 0.08 \text{ kW} \times 8760 \text{ Hr/Yr} = 742 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 742 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = \underline{2.5 \text{ MBtu/Yr}}$$

$$\text{Electricity Cost} = 742 \text{ kWh/Yr} \times \$0.0469 / \text{kWh} = \$35 / \text{Year}$$

Water Cost:

$$510360 \text{ Gal/Yr} \times \$0.5562 / \text{kGal} = \underline{\$284 / \text{Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$2,602 /Year
Pumping (Elec) Cost	\$35 /Year
Water Cost	\$284 /Year
<hr/>	
Total Utility Cost	\$2,921 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Repair Leaks in Valve Pits
ECO Number: 7

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/08/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$18130 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 46.9 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 46.9 \text{ MBtu/yr} / 0.68 = \underline{69.0 \text{ MBtu/Yr}}$$

$$\text{Heating Fuel Cost} = 69.0 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$92 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.03 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.00 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.00 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.00 \text{ kW}$$

$$\text{Electricity Use} = 0.00 \text{ kW} \times 8760 \text{ Hr/Yr} = 26 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 26 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = \underline{0.1 \text{ MBtu/Yr}}$$

$$\text{Electricity Cost} = 26 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$1 \text{ /Year}$$

Water Cost:

$$18130 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \underline{\$10 \text{ /Year}}$$

Total Utility Cost:

Heating Fuel Cost	\$92 /Year
Pumping (Elec) Cost	\$1 /Year
Water Cost	\$10 /Year
<hr/> Total Utility Cost	<hr/> \$103 /Year



SUBJECT Fort Stewart
Repair Leaks in Valve Pits
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-5-96
DATE _____

<u>Valve Pit No. / Near</u>	<u>Drops / Sec</u>	<u>Stream Dia. / GPM</u>	<u>Leak From</u>
VP-1-11 / 704	1/3	- -	Valve
VP-1-16 / 726	3+2	- -	
VP-2N-5 / 1820	5+	- -	
VP-2S-1 / 6th St.	2	- -	
VP-2S-3 / 517	2	- -	
VP-2S-8 / 512	2+2	- -	2 valves
VP-3-1 / 1540	2	1/4" / 0.438	Flange
VP-3-5 / 1170	1/10 + 2	- -	Valve
VP-3-11 / 419	-	1/8" / 0.109	"
VP-3-15 / 200 ^{0.1k} Field	-	1/8" / 0.109	Flange
VP-3-16 / 225	-	3/16" / 0.246	
VP-3-18 / 218	2	- -	
VP-3-27 / 213	1+2	- -	
Totals 13 Pits	27.4 D/s	0.902 GPM	

Minor Leaks :

$$27.4 \text{ drop/s} \times 2.5 \times 10^{-3} \frac{\text{GPM}}{\text{d/s}} = 0.069 \text{ GPM} = 36,270 \frac{\text{GAL}}{\text{YR}}$$

Proposed HTW losses : Assume 50% of minor leaks :

$$0.069 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} \times 0.5 = 18130 \frac{\text{GAL}}{\text{YR}}$$

Major Leaks : (Assume 100% can be repaired)

$$0.902 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} = 474,090 \text{ GAL/YR}$$

Current HTW Losses :

$$474,090 \frac{\text{GAL}}{\text{YR}} + 18,130 \frac{\text{GAL}}{\text{YR}} = 492,220 \frac{\text{GAL}}{\text{YR}}$$

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Leaks in Valve Pits
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 7

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-7.WQ1

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Travel time to bldgs.	2.2	hr		0	30.3	66	66		(1)
Repair/tighten valves	1.8	hr		0	30.3	53	53		(2)
Repair/tighten flanges	1.3	hr		0	30.3	38	38		(3)
Remove valves (4)	2	Ea		0	217.8	436	436		MMp191
6" gate valve, 250 lb (4)	2	Ea	700	1400	217.8	436	1,836	MMp191	MMp191
Subtotal Bare Costs				1400		1029	\$2,429		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				1400		1029	2,429		
City Cost Index (Sav. GA)			0%	0	-44%	-455	(455)	MMp533	MMp533
Subtotal				1400		574	1,974		
OH & Profit Markup			10%	140	53%	304	444	MMp7	MMp475
Subtotal				1540		878	2,418		
Sales Taxes			4.0%	62		NA	62	MMp476	
Total Construction Cost				1602		878	2,480		
Design Fee				NA	6.0%	149	149		
SIOH				NA	6.0%	149	149		
Subtotal				1602		1176	2,778		
Contingency			0%	0	0%	0	0	MEp6	MEp6
Total Project Cost				1602		1176	\$2,778		

LEGEND:

- (1) Estimate 10 minutes per valve pit for 13 valve pits.
(2) Estimate 15 minutes per valve for 7 valves (also see note 4).
(3) Estimate 15 minutes per flange for 5 flanges.
(4) Assumes 25 % of the 9 leaking valves will be replaced.
- MMp### 1996 Means Mechanical Cost Data, page ###.

151 | Pipe & Fittings

151 950 | Valves

			CREW	DAILY OUTPUT	LABOR- HOURS	UNIT	1996 BARE COSTS				TOTAL INCL O&P	
							MAT.	LABOR	EQUIP.	TOTAL		
960	1050	3" size	Q-1	8	2	Ea.	175	54		229	276	960
	1060	4" size	↓	5	3.200		215	86.50		301.50	370	
	1070	5" size	Q-2	5	4.800		250	135		385	480	
	1080	6" size	↓	5	4.800		273	135		408	505	
	1090	8" size	↓	4.50	5.333		360	150		510	625	
	1100	10" size	↓	4	6		415	168		583	715	
	1110	12" size	↓	3	8	↓	570	224		794	970	
	1200	Lug type, lever actuator										
	1220	2" size	1 Plum	14	.571	Ea.	87	17.15		104.15	122	
	1230	2-1/2" size	Q-1	9	1.778		89	48		137	172	
	1240	3" size	↓	8	2		95	54		149	188	
	1250	4" size	↓	5	3.200		121	86.50		207.50	265	
	1260	5" size	Q-2	5	4.800		175	135		310	400	
	1270	6" size	↓	5	4.800		197	135		332	425	
	1280	8" size	↓	4.50	5.333		281	150		431	540	
	1290	10" size	↓	4	6		390	168		558	690	
	1300	12" size	↓	3	8	↓	595	224		819	1,000	
	1320	For gear actuator, add					60%					
	1400	Diverter, 150 lb. flanged, bronze or iron plugs										
	1440	2" pipe size	Q-1	2	8	Ea.	2,475	216		2,691	3,050	
	1450	3" pipe size		1.50	10.667		3,550	289		3,839	4,350	
	1650	Gate, 125 lb., N.R.S.,										
	2150	Flanged										
	2200	2" size	1 Plum	5	1.600	Ea.	252	48		300	350	
	2240	2-1/2" size	Q-1	5	3.200		258	86.50		344.50	415	
	2260	3" size	↓	4.50	3.556		290	96		386	465	
	2280	4" size	↓	3	5.333		415	144		559	675	
	2290	5" size	Q-2	3.40	7.059		705	198		903	1,075	
	2300	6" size	↓	3	8		705	224		929	1,125	
	2320	8" size	↓	2.50	9.600		1,225	269		1,494	1,750	
	2340	10" size	↓	2.20	10.909		2,150	305		2,455	2,850	
	2360	12" size	↓	1.70	14.118		2,950	395		3,345	3,850	
	2370	14" size	↓	1.30	18.462		3,575	520		4,095	4,725	
	2380	16" size	↓	1	24		5,225	675		5,900	6,775	
	2420	For 250 lb., flanged, add					200%	10%				
	3550	OS&Y, flanged										
	3600	2" size	1 Plum	5	1.600	Ea.	128	48		176	215	
	3640	2-1/2" size	Q-1	5	3.200		132	86.50		218.50	277	
	3660	3" size	↓	4.50	3.556		149	96		245	310	
	3670	3-1/2" size	↓	3	5.333		212	144		356	455	
	3680	4" size	↓	3	5.333		212	144		356	455	
	3690	5" size	Q-2	3.40	7.059		350	198		548	690	
	3700	6" size	↓	3	8		350	224		574	730	
	3720	8" size	↓	2.50	9.600		625	269		894	1,100	
	3740	10" size	↓	2.20	10.909		1,150	305		1,455	1,750	
	3760	12" size	↓	1.70	14.118		1,525	395		1,920	2,275	
	3770	14" size	↓	1.30	18.462		2,950	520		3,470	4,050	
	3780	16" size	↓	1	24		4,575	675		5,250	6,050	
	3790	18" size	↓	.80	30		6,125	840		6,965	8,050	
	3800	20" size	↓	.60	40		8,550	1,125		9,675	11,100	
	3830	24" size	↓	.50	48		12,700	1,350		14,050	16,100	
	3900	For 250 lb flanged, add					200%	10%				
	4350	Globe, OS&Y,										
	4540	Class 125, flanged										
	4550	2" size	1 Plum	5	1.600	Ea.	266	48		314	365	
	4560	2-1/2" size	Q-1	5	3.200	↓	281	86.50		367.50	440	

A.3.7-10

ECO NUMBER 8

REPAIR UNDERGROUND HTW DISTRIBUTION SYSTEM LEAKS

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-08

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-8 REPAIR LEAKS IN UNDERGROUND HTW PIPING

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 04-16-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	127866.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	127866.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	127866.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	4.	\$ 59.	15.08	\$ 897.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	3319.	\$ 4448.	14.88	\$ 66184.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		3324.	\$ 4507.		\$ 67081.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 485.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 7217.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 7217.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 4992.

5. SIMPLE PAYBACK PERIOD (1G/4) 25.61 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 74298.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= .58
(IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
REPAIR LEAKS IN HTW AIPWG
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 4/11/96
DATE _____

ECO - B

The survey of valve pits indicated 28 sections of HTW piping with possible underground leaks. Based on the observed flow from the conduit vents, there are no large leaks in the system.

The leak locating tests were inconclusive. The background noise (flow, boiling, water hammer, etc.) was too great and the leaks are too small to obtain a good correlation. Shutting down the CEP and/or various HTW zones was discussed with the DPW staff, and it was decided that it was not a good idea to shut off the hospital and dining facilities to try and locate about 2 GPM of leaks.

ASSUMPTIONS

- 1) There is one small leak in each of the 28 sections of pipe identified during the survey.
- 2) The total flow of HTW from all of the leaks combined is about 1.66 gallons per minute.
- 3) All of the leaks can be found and repaired with three dig and cut operations per leak.

Note: Assumptions 1 and 3 are conservative estimates and can not be verified prior to the actual construction.

Energy and Cost Savings were calculated using a spreadsheet computer program. The calculations and results are shown on the following sheet.

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Leaks in HTW Piping
ECO Number: 8

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 04/15/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$872496 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^{\circ}\text{F} \times 310^{\circ}\text{F} = 2257.1 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 2257.1 \text{ MBtu/yr} / 0.68 = 3319.3 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 3319.3 \text{ MBtu/yr} \times \$1.34 / \text{MBtu} = \$4,448 / \text{Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{1.66 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.175 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.175 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.145 \text{ kW}$$

$$\text{Electricity Use} = 0.145 \text{ kW} \times 8760 \text{ Hr/Yr} = 1268 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 1268 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 4.33 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 1268 \text{ kWh/Yr} \times \$0.0469 / \text{kWh} = \$59 / \text{Year}$$

Water Cost:

$$872496 \text{ Gal/Yr} \times \$0.5562 / \text{kGal} = \$485 / \text{Year}$$

Total Utility Cost:

Heating Fuel Cost	\$4,448 /Year
Pumping (Elec) Cost	\$59 /Year
Water Cost	\$485 /Year
Total Utility Cost	\$4,992 /Year



SUBJECT FORT STEWART
REPAIR HTW PIPING LEAKS
DESIGNER W. TODD
CHECKER _____

AEP NO 694-1331-002
SHEET _____ OF _____
DATE 4/11/96
DATE _____

<u>Valve Pit No.</u>	<u>No. of Conduit Vents w/Steam Flow</u>
VP-1-4	2
VP-1-10	1
DP-1-13	1
VP-1-13	1
VP-1-14	1
VP-1-16	1
VP-1-17	1
DP-1-17/18	1
VP-1-18	1
VP-2N-1	1
VP-3-2	1
VP-3-2A	1
VP-3-3	1
VP-3-7	2
VP-3-9	2
VP-3-10	2
VP-3-11	3
VP-3-12	1
VP-3-13A	1
VP-3-14	2
VP-S-12	1
Total	<hr/> 28

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Piping Leaks
 Location: Fort Stewart, GA
 Basis: Schematic Design
 ECO Number: 8

RS&H No.: 694-1331-002
 Date: 04/16/96
 Estimator: W.T.Todd
 Filename: EST-8A.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Shut off HTW zone	4	MH	0	0	30.30	121	121		MMp475
Excavation, backhoe to 6'	90	CY	1.43	129	1.82	164	293	MMp28	MMp28
Excavation, by hand to 6'	60	CY	0	0	29.65	1779	1,779	MMp28	MMp28
Remove conduit, torch	18	LF	1.06	19	4.95	89	108	MMp22	MMp22
Remove pipe insulation	6	LF	0	0	4.84	29	29		MMp236
Valve off and drain pipe	0.50	MH	0	0	30.30	15	15		MMp475
Repair HTW leak - Weld	1	Ea	1.95	2	16.05	16	18	MMp144	MMp144
Open valves - fill pipe	0.50	Ea	0	0	30.30	15	15		MMp475
Replace pipe insulation	6	LF	0	0	4.84	29	29		MMp236
Weld conduit, 24" Sch 40	3	Ea	35	105	289	867	972	MMp144	MMp144
Backfill trench, by hand	60	CY		0	12.85	771	771	MMp28	MMp28
Compact backfill, by hand	60	CY		0	4.66	280	280	MMp28	MMp28
Backfill trench, dozer	90	CY	0.95	86	0.32	29	115	MMp28	MMp28
Compact backfill, dozer	90	CY	1.37	123	0.41	37	160	MMp28	MMp28
Total Cost per Leak				464		4241	4,705		
Total Cost for All Leaks	28	Ea	464	12992	4241	118748	131,740		
Subtotal Bare Costs				12992		118748	\$131,740		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				12992		118748	131,740		
City Cost Index (Sav. GA)			0%	0	-44%	-52487	(52,487)	MMp533	MMp533
Subtotal				12992		66261	79,253		
OH & Profit Markups			10%	1299	53%	35118	36,417	MMp7	MMp475
Subtotal				14291		101379	115,670		
Sales Taxes			4.0%	572		NA	572	MMp476	
Subtotal				14863		101379	116,242		
Contingency			10%	1486	10%	10138	11,624	MEp6	MEp6
Total Construction Cost				16349		111517	127,866		
Design Fee				NA	0.0%	0	0		
SIOH				NA	0.0%	0	0		
Total Project Cost				16349		111517	\$127,866		

LEGEND:

MEp### 1996 Means Electrical Cost Data, page ###.
 MMp### 1996 Means Mechanical Cost Data, page ###.



Telephone Call Confirmation

Project Number 694 1331 002

Local _____ (L.D.) _____ (Placed) B. Todd Rec'd _____ Date 4/11/96

Conversed with Gene Smith or Fort Stewart DPW (912) 767-2138

Regarding Leak Repair of HTW Piping

Current leak repair method:

- Make an educated guess at where to start digging based on flow from valve pits and dig up trench.
- Remove (with cutting torch) a piece of conduit and look for leak. If not there, check direction of water flow in conduit and make another guess as to where to dig. Reweld conduit.
- Repeat above steps until leak is found. The leak is typically only about $\frac{1}{4}$ " in diameter and they can weld it shut.

Distribution:

Installing Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of state rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with smaller annual billing. The overhead percentages for any given contractor may vary greatly and depend on a number of factors, such as the contractor's annual volume, engineering and logistical support costs, and staff requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevailing economic conditions. All factors should be examined very carefully for each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

Abbr.	Trade	A		B	C	D	E	F		G	H		I
		Base Rate Incl. Fringes		Work- ers' Comp. Ins.	Average Fixed Over- head	Over- head	Profit	Total Overhead & Profit		Amount	Rate with O & P		
		Hourly	Daily					%			Hourly	Daily	
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10%	60.0%	\$15.55	\$41.50	\$332.00		
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40	30.65	245.20		
	Foreman Average, Inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85	42.30	338.40		
	Foreman Average, Outside (\$2.00 over trade)	27.95	223.60	20.2		13.0		60.0	16.75	44.70	357.60		
	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80	31.60	252.80		
Clab													
Asbe	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85	46.40	371.20		
Boil	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20	48.25	386.00		
Bric	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60		
Brhe	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45	31.45	251.60		
Carp	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05	40.25	322.00		
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30	36.65	293.20		
Elec	Electricians	29.30	234.40	8.0		16.0		50.8	14.90	44.20	353.60		
Elev	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75	45.80	366.40		
Eqhv	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35	41.10	328.80		
Eqmd	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80	39.50	316.00		
Eqit	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25	37.95	303.60		
Eqol	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75	33.65	269.20		
Eqmm	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80	42.35	338.80		
Glaz	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40	38.30	306.40		
Lath	Lathers	24.95	199.60	13.5		11.0		51.3	12.80	37.75	302.00		
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65	40.30	322.40		
Mill	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55	40.10	320.80		
Mstz	Mosaic & Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30	37.55	300.40		
Pord	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55	35.50	284.00		
Psst	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00	47.95	383.60		
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70	36.00	288.00		
Pile	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35	44.70	357.60		
Plas	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35	37.55	300.40		
Plah	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10	31.25	250.00		
Plum	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95	46.00	368.00		
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40	49.15	393.20		
Rofc	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95	39.50	316.00		
Rots	Roofers, Tile & Slate	22.60	180.80	37.4		11.0		75.2	17.00	39.60	316.80		
Rohe	Roofers, Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00	27.95	223.60		
Shee	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40	45.35	362.80		
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65	47.95	383.60		
Stpi	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05	46.35	370.80		
Ston	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60		
Sswk	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20		
Tilf	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20	37.25	298.00		
Tilh	Tile Layers Helpers	20.30	162.40	11.0		11.0		48.8	9.90	30.20	241.60		
Trlt	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15	31.50	252.00		
Trhv	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35	32.05	256.40		
Sswl	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20		
Wrck	*Wrecking	19.80	158.40	44.8		11.0		82.6	16.35	36.15	289.20		

not included in Averages.

City Cost Indexes

DIVISION			FLORIDA																	
			MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE		
			MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK			110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6
031	CONCRETE FORMWORK		94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7
032	CONCRETE REINFORCEMENT		95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3
033	CAST IN PLACE CONCRETE		91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5
3	CONCRETE		87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3
4	MASONRY		76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4
5	METALS		98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0
6	WOOD & PLASTICS		88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0
7	THERMAL & MOISTURE PROTECTION		99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1
8	DOORS & WINDOWS		95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4
092	LATH, PLASTER & GYPSUM BOARD		101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6
095	ACOUSTICAL TREATMENT & WOOD FLOORING		102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9
096	FLOORING & CARPET		121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8
099	PAINTING & WALL COVERINGS		100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0
9	FINISHES		108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3
10-14	TOTAL DIV. 10-14		100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5
15	MECHANICAL		100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0
16	ELECTRICAL		98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5
1-16	WEIGHTED AVERAGE		97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9

DIVISION			GEORGIA																	
			TAMPA			ALBANY			ATLANTA			AUGUSTA			COLUMBUS			MACON		
			MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK			126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8	110.4	74.3	82.6	111.6	91.9	96.5
031	CONCRETE FORMWORK		97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7	96.9	50.4	57.4	95.9	65.9	70.5
032	CONCRETE REINFORCEMENT		95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4	95.1	76.4	84.6	97.4	76.7	85.8
033	CAST IN PLACE CONCRETE		101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5	95.5	49.5	75.8	95.5	53.3	77.5
3	CONCRETE		92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2	89.4	57.0	73.0	89.7	65.1	77.3
4	MASONRY		82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4	83.4	39.3	56.0	98.6	46.7	66.4
5	METALS		102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7	96.7	89.3	93.9	91.7	90.1	91.1
6	WOOD & PLASTICS		94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3	93.7	51.3	72.5	97.4	69.9	83.6
7	THERMAL & MOISTURE PROTECTION		96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9	96.1	55.7	77.5	95.1	62.9	80.2
8	DOORS & WINDOWS		98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1	95.9	53.8	85.7	94.2	64.8	87.1
092	LATH, PLASTER & GYPSUM BOARD		101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7	101.6	50.4	68.4	108.3	69.5	83.2
095	ACOUSTICAL TREATMENT & WOOD FLOORING		102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8	102.4	50.4	68.7	95.9	69.5	78.8
096	FLOORING & CARPET		113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2	113.0	41.0	95.7	87.8	47.5	78.2
099	PAINTING & WALL COVERINGS		104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3	100.9	48.3	70.3	102.4	59.0	77.2
9	FINISHES		107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1	105.7	47.8	76.2	91.5	62.0	76.5
10-14	TOTAL DIV. 10-14		100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8	100.0	69.4	93.5	100.0	73.6	94.4
15	MECHANICAL		100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7	100.0	46.2	76.2	100.0	52.1	78.8
16	ELECTRICAL		97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2	93.3	49.4	64.0	91.4	63.3	72.7
1-16	WEIGHTED AVERAGE		99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5	97.1	55.7	77.1	95.4	65.4	80.9

DIVISION			IDAHO																	
			SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON			POCATELLO		
			MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK			110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2	89.1	99.3	96.9
031	CONCRETE FORMWORK		97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0	97.4	89.3	90.5
032	CONCRETE REINFORCEMENT		100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6	96.3	78.5	86.3
033	CAST IN PLACE CONCRETE		91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8	99.6	93.8	97.1
3	CONCRETE		88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1	103.7	88.6	96.1
4	MASONRY		86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8	136.3	82.7	103.0
5	METALS		97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1	112.5	82.2	101.1
6	WOOD & PLASTICS		93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2	95.1	88.5	91.8
7	THERMAL & MOISTURE PROTECTION		96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7	98.0	83.8	91.5
8	DOORS & WINDOWS		95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7	94.9	78.5	91.0
092	LATH, PLASTER & GYPSUM BOARD		101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4	89.0	87.9	88.3
095	ACOUSTICAL TREATMENT & WOOD FLOORING		102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8	96.2	87.9	90.8
096	FLOORING & CARPET		113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2	97.5	74.8	92.1
099	PAINTING & WALL COVERINGS		100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3			

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-08

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-8 REPAIR LEAKS IN UNDERGROUND HTW PIPING

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 04-16-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	53511.	
B. SIOH	\$	3211.	
C. DESIGN COST	\$	3211.	
D. TOTAL COST (1A+1B+1C)	\$	59933.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	59933.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	4.	\$ 59.	15.08	\$ 897.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	3319.	\$ 4448.	14.88	\$ 66184.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		3324.	\$ 4507.		\$ 67081.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 485.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 7217.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 7217.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 4992.

5. SIMPLE PAYBACK PERIOD (1G/4) 12.00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 74298.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.24
(IF < 1 PROJECT DOES NOT QUALIFY)

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Piping Leaks
 Location: Fort Stewart, GA
 Basis: Schematic Design
 ECO Number: 8

RS&H No.: 694-1331-002
 Date: 04/15/96
 Estimator: W.T.Todd
 Filename: EST-8.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Shut off HTW zone	4	MH	0	0	30.30	121	121		MMp475
Perform leak locator test	1	Ea	0	0	300	300	300		Vendor
Excavation, backhoe to 6'	30	CY	1.43	43	1.82	55	98	MMp28	MMp28
Excavation, by hand to 6'	20	CY	0	0	29.65	593	593	MMp28	MMp28
Remove conduit, torch	6	LF	1.06	6	4.95	30	36	MMp22	MMp22
Remove pipe insulation	2	LF	0	0	4.84	10	10		MMp236
Valve off and drain pipe	0.50	MH	0	0	30.30	15	15		MMp475
Repair HTW leak - Weld	1	Ea	1.95	2	16.05	16	18	MMp144	MMp144
Open valves - fill pipe	0.50	Ea	0	0	30.30	15	15		MMp475
Replace pipe insulation	2	LF	0	0	4.84	10	10		MMp236
Weld conduit, 24" Sch 40	1	Ea	35	35	289	289	324	MMp144	MMp144
Backfill trench, by hand	20	CY		0	12.85	257	257	MMp28	MMp28
Compact backfill, by hand	20	CY		0	4.66	93	93	MMp28	MMp28
Backfill trench, dozer	30	CY	0.95	29	0.32	10	39	MMp28	MMp28
Compact backfill, dozer	30	CY	1.37	41	0.41	12	53	MMp28	MMp28
Total Cost per Leak				156		1826	1,982		
Total Cost for All Leaks	28	Ea	156	4368	1826	51128	55,496		
Subtotal Bare Costs				4368		51128	\$55,496		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				4368		51128	55,496		
City Cost Index (Sav. GA)			0%	0	-44%	-22599	(22,599)	MMp533	MMp533
Subtotal				4368		28529	32,897		
OH & Profit Markups			10%	437	53%	15120	15,557	MMp7	MMp475
Subtotal				4805		43649	48,454		
Sales Taxes			4.0%	192		NA	192	MMp476	
Subtotal				4997		43649	48,646		
Contingency			10%	500	10%	4365	4,865	MEp6	MEp6
Total Construction Cost				5497		48014	53,511		
Design Fee				NA	6.0%	3211	3,211		
SIOH				NA	6.0%	3211	3,211		
Total Project Cost				5497		54436	\$59,933		

LEGEND:

MEp### 1996 Means Electrical Cost Data, page ###.
 MMp### 1996 Means Mechanical Cost Data, page ###.

ECO NUMBER 9

REDUCE OR ELIMINATE HTW DISCHARGE DURING SEP START-UP

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-9

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-9 REDUCE HTW LOSSES DURING SEP START-UP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	0.
B. SIOH	\$	0.
C. DESIGN COST	\$	0.
D. TOTAL COST (1A+1B+1C)	\$	0.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.
F. PUBLIC UTILITY COMPANY REBATE	\$	0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	0.

***** No investment costs; Other items should be checked. *****

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 4.	15.08	\$ 62.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	111.	\$ 149.	14.88	\$ 2213.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		111.	\$ 153.		\$ 2275.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 1067.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 15877.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 15877.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1220.

5. SIMPLE PAYBACK PERIOD (1G/4) .00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 18152.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= *****
 (IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-9

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-9 REDUCE HTW LOSSES DURING SEP START-UP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION B

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	28652.	
B. SIOH	\$	1720.	
C. DESIGN COST	\$	1720.	
D. TOTAL COST (1A+1B+1C)	\$	32092.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		32092.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	111.	\$ 149.	14.88	\$ 2213.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		111.	\$ 149.		\$ 2213.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 9032.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 134396.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 134396.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 9181.

5. SIMPLE PAYBACK PERIOD (1G/4) 3.50 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 136609.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 4.26
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-09X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-9 REDUCE HTW LOSSES DURING SEP START-UP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	0.
B. SIOH	\$	0.
C. DESIGN COST	\$	0.
D. TOTAL COST (1A+1B+1C)	\$	0.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.
F. PUBLIC UTILITY COMPANY REBATE	\$	0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	0.

***** No investment costs; Other items should be checked. *****

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 4.	15.08	\$ 62.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	96.	\$ 129.	14.88	\$ 1914.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		96.	\$ 133.		\$ 1976.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 1067.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 15877.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 15877.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 1200.

5. SIMPLE PAYBACK PERIOD (1G/4) .00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 17853.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= *****
 (IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-09Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-9 REDUCE HTW LOSSES DURING SEP START-UP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	0.
B. SIOH	\$	0.
C. DESIGN COST	\$	0.
D. TOTAL COST (1A+1B+1C)	\$	0.
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.
F. PUBLIC UTILITY COMPANY REBATE	\$	0.
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	0.

***** No investment costs; Other items should be checked. *****

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 4.	15.08	\$ 62.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	85.	\$ 114.	14.88	\$ 1695.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		85.	\$ 118.		\$ 1757.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 1067.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 15877.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 15877.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 1185.

5. SIMPLE PAYBACK PERIOD (1G/4) .00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 17634.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= *****
 (IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
IMPROVE SEP START-UP
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-1-96
DATE _____

ECO-9 OPTION A

The SEP was started up from 13 Nov 95 - 23 Nov 95

The HTW system make-up water for those 11 days:

Actual HTW Make-up = 138,350 Gal.

Average HTW make-up for the previous 6 months:

$$\frac{(4.6 + 5.2 + 5.7 + 5.3 + 5.0 + 4.6) \text{ GPM}}{6} = 5.067 \text{ GPM}$$

$$\text{Average HTW Make-up} = 5.067 \frac{\text{GAL}}{\text{min}} \times 1440 \frac{\text{min}}{\text{day}} \times 11 \text{ days} = \underline{80256 \text{ Gal}}$$

Assuming the SEP start-up losses = Actual - Average:

$$\text{SEP Startup losses} = 138350 \text{ GAL} - 80256 \text{ GAL} = \underline{58094 \frac{\text{GAL}}{\text{YR}}}$$

O&M Cost (Assume start-up takes 4 hr/day & 10 days)

$$\text{Current startup costs} = 10 \text{ days} \times 8 \frac{\text{hr}}{\text{day}} \times \$25.86/\text{hr} = \$2069/\text{YR}$$

$$\text{Proposed startup costs} = 10 \text{ days} \times 4 \frac{\text{hr}}{\text{day}} \times \$25.86/\text{hr} = \$1034/\text{YR}$$

$$\text{O&M Savings} = \$2069 - \$1035 = \boxed{\$1035/\text{YR}}$$

$$\text{Proposed Operating Cost} = \$13163 - \$1035 = \underline{\$12128/\text{YR}}$$



SUBJECT FORT STEWART
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-1-96
DATE _____

ECO-9

Satellite Energy Plant, Operating Costs - Labor

Assumptions:

- 1) SEP operates for $4\frac{1}{2}$ months / year
- 2) SEP startup takes 10 days / year
- 3) SEP shut down takes 3 days / yr
- 4) Normal operation requires one visit per shift that takes about 1 hour / visit.
- 5) Start-up and shut-down requires one operator full time for one shift each day.

Pipefitters hourly rate w/ benefits = \$46.35 mmp 475

Adjusted for Savannah GA = $\$46.35 \times 0.558 = \25.86 mmp 533

Labor Costs:

$$\text{Startup} = 10 \frac{\text{days}}{\text{yr}} \times 8 \frac{\text{hrs}}{\text{day}} \times \$25.86 / \text{hr} = \$2069 / \text{YR}$$

$$\text{Operation} = 4.5 \frac{\text{mo}}{\text{YR}} \times 30 \frac{\text{day}}{\text{mo}} \times 3 \frac{\text{hr}}{\text{day}} \times \$25.86 / \text{hr} = \$10,473 / \text{YR}$$

$$\text{Shut down} = 3 \frac{\text{day}}{\text{YR}} \times 8 \frac{\text{hr}}{\text{day}} \times \$25.86 / \text{hr} = \$621 / \text{YR}$$

$$\text{Total Labor Cost} = \$1034 / \text{YR} + \$9310 / \text{YR} + \$621 / \text{YR} = \underline{\underline{\$13,163 / \text{YR}}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Improve SEP Start-up Procedure
ECO Number: 9

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/12/96

Assumptions:	1. HTW temperature	380 °F
	2. Make-up water temperature	70 °F
	3. Boiler efficiency	68%
	4. Pump head (from record drawings)	300 Ft H2O
	5. Pump efficiency (from record drawings)	72%
	6. Motor efficiency	90%
	7. Average heating fuel cost	\$1.34 /MBtu
	8. Electricity cost	\$0.0469 /kWh
	9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x average temperature difference

$$58094 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 155 \text{ }^\circ\text{F} = 75.1 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 75.1 \text{ MBtu/yr} / 0.68 = 110.5 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 110.5 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$148 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{3.67 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.39 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x Hr/Yr

$$\text{Electric Demand} = 0.39 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.32 \text{ kW}$$

$$\text{Electricity Use} = 0.32 \text{ kW} \times 264 \text{ Hr/Yr} = 84 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 84 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 0.3 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 84 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$4 \text{ /Year}$$

Water Cost:

$$58094 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$32 \text{ /Year}$$

Total Utility Cost:

Heating Fuel Cost	\$148 /Year
Pumping (Elec) Cost	\$4 /Year
Water Cost	\$32 /Year
Total Utility Cost	\$184 /Year



SUBJECT FIRST STEWART
SEP Condensate Return
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-5-96
DATE _____

ECO NO. 9 - OPTION B

INSTALL NEW "CONDENSATE" RETURN PUMP IN SEP.

PUMP VOLUME (1)

PUMP WILL MOVE WATER THROUGH EXISTING 4 IN CONDENSATE RETURN LINE FROM SEP TO CEP.

ASSUME 8 FT/SEC LINE VELOCITY

$$\text{VOL. RATE} = \text{AREA} \times \text{VELOCITY} = \frac{\pi D^2}{4} \times V$$
$$= 3.14/4 \times (4 \text{ IN} / 12 \text{ IN/FT})^2 \times 8 \text{ FT/SEC} = 0.698 \text{ CF/SEC.}$$

$$0.698 \text{ CF/SEC} \times 8.34 \text{ #/CF} \times 60 \text{ SEC/MIN} = \boxed{349 \text{ gpm.}}$$

PUMP HEAD (1)

ACTUAL PIPE DISTANCE IS APPROXIMATELY 1 MILE WITH NO SIGNIFICANT ELEVATION CHANGE.

HEAD LOSS PER 100 FT PIPE = 6 FT/100 FT PIPE.

$$1 \text{ MILE} \times 5280 \text{ FT/MI} \times \frac{6 \text{ FT HEAD}^*}{100 \text{ FT PIPE}} = \boxed{316 \text{ FT.}}$$

* ASHRAE FUNDAMENTALS HAND BOOK, CHAPTER 34, TABLE 1.

PUMP POWER (1)

$$\text{HP} = \frac{\text{gpm} \times \text{TDH}}{3960 \times \eta} = 349 \times 316 / 3960 / 0.7 = \boxed{40 \text{ HP}}$$

PUMP VOLUME (2)

ABOVE PUMP VOLUME IMPLIES A SEP STEAM CONSUMPTION OF $350 \text{ gpm} \times 500 \text{ PPH/gpm} = 175000 \text{ #/HR}$ WHICH IS 2 TIMES THE BOILER CAPACITY, AND IS THEREFORE TOO CONSERVATIVE.

A LESS CONSERVATIVE ESTIMATE WOULD BE BASED ON THE ASSUMPTION THAT THE EXISTING HEAT REQUIREMENT FOR THE TWO CASCADES IS APPROXIMATELY EQUAL TO 146,000 #/HR STEAM^①

① SYSTEMS CORP REPORT, PG A-1, FIG A-1

A.3.9-9

RS&H

SUBJECT FORT STEWART
SEP Condensate Return
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-5-96
DATE _____

ECO-9B

Pump Volume (2) (CONT.)

$$146,000 \text{ #/HR} / 500 \text{ PPH/gpm} = \boxed{292 \text{ gpm}}$$

Pump Power (2)

$$\text{H.P.} = \frac{\text{gpm} \times \text{TDH}}{3960 \times \eta} = \frac{292 \times 316}{3960 \times 0.7} = \boxed{33 \text{ H.P.}}$$

SEP SYSTEM HEAT LOSSES WITH NO HEATING LOAD.

TEST DATA SHOWED A 45°F TEMPERATURE LOSS OVER A 2 HOUR PERIOD WHEN THE AMBIENT TEMPERATURE WAS 60°F (ASSUME NO HEAT LOAD)

ESTIMATED WATER IN SEP DISTRIBUTION PIPING IS 13,500 gal
ESTIMATED WATER IN SEP INTERNAL PIPING IS 1000 gal
CASCADE HEATER VOLUME @ NORMAL OPERATING LEVEL IS
2500 gal X 2 HEATERS = 5000 gal

$$\text{TOTAL SEP CAPACITY} = 13500 + 1000 + 5000 = 19500 \text{ gal}$$

$$\begin{aligned} \text{HEAT LOSS RATE} &= \frac{\text{HEAT LOSS}}{\text{TIME}} = \frac{19500 \text{ gal} \times 8.34 \text{ #/gal} \times (45^{\circ}\text{F})}{2 \text{ HRS.}} \\ &= 3.66 \text{ MBTU/HR} \end{aligned}$$

SEP BUILDING LOSSES

BLDG. 2" pipe = 529 gpm
 $529 \text{ gpm} \times 500 \text{ PPH/gpm} \times (375 - 100) = 7.15 \text{ MBTU/HR}$

BLDG. 1 1/2" pipe = 289 gpm
 $289 \text{ gpm} \times 500 \text{ PPH/gpm} \times (375 - 100) = 3.85 \text{ MBTU/HR}$

BLDG. 1 1/4" pipe = 189 gpm
 $189 \text{ gpm} \times 500 \text{ PPH/gpm} \times (375 - 100) = 2.475 \text{ MBTU/HR}$

BLDG. 1" pipe = 8.5 gpm
 $8.5 \times 500 \times (375 - 100) = \boxed{A.3.9-10} \quad 1.17 \text{ MBTU/HR}$

RS&H

SUBJECT FORT STEWART
SEP condensate Return
 DESIGNER G. Fallon
 CHECKER _____

AEP NO 6941331 002
 SHEET _____ OF _____
 DATE 2-5-96
 DATE _____

ECO-9B

TOTAL MAX SEP LOAD

$$7.15 \times 2 + 3.85 + 2.48 + 1.17 + 3.66 = \boxed{25.46 \text{ MBTU/HR}}$$

MAX ACTUAL PUMP FLOW

$$25.46 \text{ MBTU/HR} / (1199 - 360) \text{ BTU/lb} / 500 \text{ PPH/gpm} \times 1 \text{ lb} = \boxed{60.79 \text{ gpm}}$$

ACTUAL Pump Power

$$\text{H.P.} = \frac{60.79 \text{ gpm} \times 316 \text{ ft}}{3960 \times 0.7} = \boxed{6.92 \text{ HP}} \quad \times 0.746 = \boxed{5.16 \text{ kW}}$$

ENERGY LOST (Assume actual losses are 50% less since water is cold at first)

$$138,350 \text{ Gallons} - 80,256 \text{ Gallons} \approx 58,100 \text{ gal (see ECO-9 calc.)}$$

$$58,100 \text{ gal} \times 8.34 \text{ #/gal} \times (348.6 - (68 - 32)) \text{ BTU/#} / 1 \text{ lb} \times 0.5 = 75.7 \text{ MBTU/yr}$$

ENERGY LOSS VALUE (Assume 0.68 boiler eff.)

$$75.7 \text{ MBTU/yr} \div 0.68 = \boxed{111.4 \frac{\text{MBTU}}{\text{yr}}} \times \$1.34 / \text{MBTU} = \boxed{\$149/\text{yr}}$$

WATER LOSS VALUE

$$58,100 \text{ gal} \times 0.5562 \text{ #/1000 gal} = \boxed{\$32/\text{yr}}$$

Pumping Cost (Assume RETURN PUMPING ENERGY IS THE SAME)

$$58,100 / (11 \text{ days} \times 60 \text{ m/H} \times 24 \text{ H/d}) = \boxed{3.67 \text{ gpm}}$$

$$\text{HP} = \frac{3.67 \text{ gpm} \times 310 \text{ ft}}{3960 \times 0.7} = \boxed{0.41 \text{ HP}} \quad \times 0.746 = \boxed{0.306 \text{ kW}}$$

$$0.306 \text{ kW} \times 11 \text{ DAY} \times 24 \text{ HR/DAY} =$$

$$4.847 \text{ kWh} \times 0.0469 \text{ #/kWh} =$$

$$\boxed{81 \text{ kWh/yr}} = 0.3 \frac{\text{MBTU}}{\text{yr}}$$

$$\boxed{\$4/\text{yr}}$$

A.3.9-11

SUBJECT FORT STEWARTAEP NO 694 1331 002DESIGNER G. FALLONSHEET OF CHECKER DATE 2-9-96DATE

ECO-9B

UTILITY COST SAVINGS

$$\begin{aligned}\text{COST} &= \text{ENERGY COST} + \text{WATER COST} + \text{PUMPING COST} \\ &= 149 + 32 + 4 \\ &= \boxed{\$185}\end{aligned}$$

O & M COSTS:

$$\text{SEP startup: } 10 \text{ days} \times 2 \frac{\text{hour}}{\text{day}} \times \$25.86/\text{HR} = \$517/\text{YR}$$

$$\text{Operation: } 4.5 \frac{\text{mo}}{\text{YR}} \times 30 \frac{\text{day}}{\text{mo}} \times 1 \frac{\text{hr}}{\text{day}} \times \$25.86/\text{HR} = \$3,491/\text{YR}$$

$$\text{Shut down: } 3 \text{ days} \times 2 \frac{\text{hours}}{\text{day}} \times \$25.86/\text{HR} = \$155/\text{YR}$$

$$\text{Total Operating Costs} = \underline{\underline{\$4163/\text{YR}}}$$

ANNUAL SAVINGS

$$\text{HEATING FUELS} = \boxed{111 \text{ MBtu/YR}} \quad \text{SAME AS OPTION A}$$

$$\text{ELECTRICITY} = 0.3 - 0.3 = \boxed{0 \text{ MBtu/YR}}$$

$$\text{WATER} = \boxed{\$32/\text{YR}}$$


$$\text{O \& M} = \$13163 - \$4163 = \boxed{\$9000/\text{YR}}$$

RS&H

SUBJECT FORT STEWART
Pump for SEP to CEP
 DESIGNER G. Fallon
 CHECKER _____

AEP NO 694 1331 002
 SHEET _____ OF _____
 DATE 2-9-96
 DATE _____

ECO-9B



A.3.9-13

0441
912-767-8931

CONSTRUCTION COST ESTIMATE

Project: Install new Return Pump in the SEP
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 9B

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: G. W. Fallon
Filename: EST-9B.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Pump, 300 gpm, 310' hd	2	Ea	2325	4650	480	960	5,610	MMp202	MMp202
Iso. Valves, 4", 300 lb	4	Ea	1300	5200	155	620	5,820	MMp197	MMp197
Elbows, 4", Weld Joint	4	Ea	17.50	70	97.05	388	458	MMp158	MMp158
Flange, 4", 400 lb, W.N.	8	Ea	44.00	352	60.60	485	837	MMp165	MMp165
Pipe, 4", Sch. 80, W.E.	40	LF	16.05	642	14.70	588	1,230	MMp142	MMp142
Welding Labor/Joint	36	Ea	0	0	60.60	2182	2,182	MMp144	MMp144
Level Control Valve	1	Ea	5000	5000	2000	2000	7,000	Estimate	Estimate
Elec. Conn. 480V, 30 hp	2	Ea	1125	2250	1000	2000	4,250	MEp320	MEp320
Subtotal Bare Costs				18164		9223	\$27,387		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				18164		9223	27,387		
City Cost Index (Sav. GA)			0%	0	-44%	-4077	(4,077)	MMp533	MMp533
Subtotal				18164		5146	23,310		
OH & Profit Markups			10%	1816	53%	2727	4,543	MMp7	MMp475
Subtotal				19980		7873	27,853		
Sales Taxes			4.0%	799		NA	799	MMp476	
Total Construction Cost				20779		7873	28,652		
Design Fee				NA	6.0%	1719	1,719		
SIOH				NA	6.0%	1719	1,719		
Subtotal				20779		11311	32,090		
Contingency			0%	0	0%	0	0	MEp6	MEp6
Total Project Cost				20779		11311	\$32,090		

LEGEND:

MEp### 1996 Means Electrical Cost Data, page ###.
MMp### 1996 Means Mechanical Cost Data, page ###.

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	4020			2.8	
	2	5090			3.5	
	3	3730			2.6	
	4	7330			5.1	
	5	2280			1.6	
	6	7650			5.3	
	7	2440			1.7	
	8	3700			2.6	
	9	9110			6.3	
	10	10140			7.0	
	11	5410			3.8	
	12	6830			4.7	
	13	10080			7.0	
	14	9320			6.5	
NOV	15	12200		8708	8.5	6.0
	16	13450			9.3	
	17	16220			11.3	
	18	14560	Total=138,350		10.1	
	19	10130			7.0	
	20	13380			9.3	
	21	14530			10.1	
	22	14460			10.0	
	23	10020			7.0	
	24	7950			5.5	
	25	11720			8.1	
	26	4100			2.8	
	27	4450			3.1	
	28	10070			7.0	
	29	9450			6.6	
	30	7410	261230		5.1	
	1	7430			5.2	
	2	9300			6.5	
	3	10090			7.0	
	4	8930			6.2	
	5	9170			6.4	
	6	6500			4.5	
	7	9930			6.9	
	8	7770			5.4	
	9	7430			5.2	
	10	9410			6.5	
	11	9100			6.3	
	12	8010			5.6	
	13	9780			6.8	
	14	9470			6.6	
DEC	15	10930		8371	7.6	5.8
	16	8650			6.0	
	17	9770			6.8	
	18	8500			5.9	
	19	6790			4.7	
	20	7300			5.1	
	21	7620			5.3	
	22	4110			2.9	
	23	6220			4.3	
	24	7180			5.0	
	25	4420			3.1	
	26	5050			3.5	
	27	7010			4.9	
	28	9310			6.5	
	29	10690			7.4	
	30	11030			7.7	
	31	12610	259510		8.8	

OPERATING INSTRUCTIONS

CASCADE WATER HEATER

I. DESCRIPTION

The Chicago Heater Company cascade hot water heater has been specifically designed to handle all of the system returns outlined in the contract specifications. In order to insure the most efficient use of steam pressure and energy level in the cycle and the lowest operating cost, these specified design rates of flow should not be exceeded.

The cascade heater is a direct contact heat exchanger, heating in such a machine is achieved by passing carefully controlled streams of water through a steam atmosphere.

II. OPERATION

System returns enter the cascade heater through the water inlet nozzle provided on the shell. These returns are conveyed upward through ducting within the unit to a distributor weir over which they cascade downward on to specially designed water distributing trays. These trays break up the water into thin streams to expose the greatest surface area to the steam which fills the heating section. In the steam space the water is heated to within 10° of the steam temperature. The hot water leaving the heating element falls into the storage compartment and is ready for service.

III. BEFORE START UP

This equipment should not be started until all operating personnel are familiar with the start up procedures herein outlined. Particular attention should be paid to the operation of the various controls furnished with the cascade heater.

Prior to admitting water and steam to the unit, the following equipment should be checked.

- A. The atmospheric vent should be wide open. Note: At low starting loads it may be necessary to throttle this valve slightly to bring the unit up to pressure, but in no case is the valve to be fully closed.

- B. The relief valve should be checked to be certain that gags and shipping stops have been removed.
- C. Manually operate all controls. Control valves should be checked for correct travel, freedom from friction, and correct action to match their controlling instrument. For successful operation, the actuator stem and valve plug stem must move freely in response to loading pressure changes on the diaphragm.
- D. Alarm switches should be checked to be certain that the switches are installed for proper function and alarm devices are operational.
- E. Thermometer, pressure gauges, and all recording instruments should be properly calibrated.

IV. START UP

The following procedures should be followed when commencing operation of the cascade heater after all equipment has been tested and checked.

1. Flush out all lines and tanks with water until there is no apparent indication of foreign matter or rust.
2. Close outlet valve from heater to feed pumps.
3. Start flow of inlet water and slowly increase from 50 to 60 per cent of design rate.
4. Open valve admitting steam into tank slowly. Possibly some rumbling may occur but this may be disregarded with the cold tank. Check steam gauge in the heater and make absolutely certain that positive steam pressure is maintained in the heater; if steam supply is insufficient, utilize other sources such as live steam through a reducing valve or any other auxiliary steam supply.
5. Filling the vessel with water will purge most of the air from the tank. As the water approaches operating level, increase the steam flow. Caution: Filling the tank with steam and then flooding with cold water subjects the tank to undue stresses caused by vacuum created by rapid condensation. Never fill the vessel with steam and admit cold water.

6. As the water reaches the operating level, check the operation of inlet controllers. Make adjustments at all controllers. Manually continue the flow of water until high level controls operate. Check operating level of controllers and alarms at this point.
7. When a considerable volume of steam is issuing from the vent valve, commence throttling back vent valve until only a plume of vapor can be seen issuing from it. At this point the water temperature within the unit should be within 10° of saturation temperature of steam at heater pressure. A lower water temperature indicates that pockets of air have left and completely purged. If this occurs, open steam valve wide, then open vent valve wide for a few seconds, then throttle back to force pockets to the vent.
8. Open steam valve wide.
9. The unit is now ready for service and the outlet valve may be opened and admit water to the feed pumps. When the unit is operating correctly, the storage water temperature should be within 10° of the saturated temperature of the steam at heater pressure.
10. For any special equipment that has been supplied with this unit, check the descriptive literature and operating instructions for that equipment.

R010-070 Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of rate rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with sma annual billing. The overhead percentages for any given contract vary greatly and depend on a number of factors, such as the co annual volume, engineering and logistical support costs, and si requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevaili economic conditions. All factors should be examined very carefu each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

Abbr.	Trade	A		B	C	D	E	F		G	H		I
		Base Rate Incl. Fringes		Work- ers' Comp. Ins.	Average Fixed Over- head	Over- head	Profit	Total Overhead & Profit			Rate with O & P		
		Hourly	Daily					%	Amount		Hourly	Daily	
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10.0%	60.0%	\$15.55		\$41.50	\$332.00	
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40		30.65	245.20	
	Foreman Average, Inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85		42.30	338.40	
	Foreman Average, Outside (\$2.00 over trade)	27.95	223.60	20.2		13.0		60.0	16.75		44.70	357.60	
Clab	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80		31.60	252.80	
Asbe	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85		46.40	371.20	
Boil	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20		48.25	386.00	
Bric	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80		40.70	325.60	
Brhe	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45		31.45	251.60	
Carp	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05		40.25	322.00	
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30		36.65	293.20	
Elec	Electricians	29.30	234.40	8.0		16.0		50.8	14.90		44.20	353.60	
Elev	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75		45.80	366.40	
Eqhv	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35		41.10	328.80	
Eqmd	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80		39.50	316.00	
Eqlt	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25		37.95	303.60	
Eqol	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75		33.65	269.20	
Eqmm	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80		42.35	338.80	
Glaz	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40		38.30	306.40	
Lath	Lathers	24.95	199.60	13.5		11.0		51.3	12.80		37.75	302.00	
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65		40.30	322.40	
Mill	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55		40.10	320.80	
Mstz	Mosaic and Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30		37.55	300.40	
Pord	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55		35.50	284.00	
Psst	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00		47.95	383.60	
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70		36.00	288.00	
Pile	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35		44.70	357.60	
Plas	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35		37.55	300.40	
Plah	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10		31.25	250.00	
Plum	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95		46.00	368.00	
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40		49.15	393.20	
Rofc	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95		39.50	316.00	
Rots	Roofers, Tile and Slate	22.60	180.80	37.4		11.0		75.2	17.00		39.60	316.80	
Rohe	Roofing Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00		27.95	223.60	
Shee	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40		45.35	362.80	
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65		47.95	383.60	
Stpi	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05		46.35	370.80	
Ston	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80		40.70	325.60	
Sswk	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30		52.15	417.20	
Tilf	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20		37.25	298.00	
Tilh	Tile Layer Helpers	20.30	162.40	11.0		11.0		48.8	9.90		30.20	241.60	
Trlt	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15		31.50	252.00	
Trhv	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35		32.05	256.40	
Sswl	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30		52.15	417.20	
Wrck	*Wrecking	19.80	158.40	44.8		11.0		82.6	16.35		36.15	289.20	

*Not included in Averages.

A.3.9-19

GENERAL REQUIREMENTS

REFERENCE NOS.

City Cost Indexes

DIVISION	FLORIDA																				
	MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE					
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6			
031 CONCRETE FORMWORK	94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7			
032 CONCRETE REINFORCEMENT	95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3			
033 CAST IN PLACE CONCRETE	91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5			
3 CONCRETE	87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3			
4 MASONRY	76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4			
5 METALS	98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0			
6 WOOD & PLASTICS	88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0			
7 THERMAL & MOISTURE PROTECTION	99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1			
8 DOORS & WINDOWS	95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4			
092 LATH, PLASTER & GYPSUM BOARD	101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6			
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9			
096 FLOORING & CARPET	121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8			
099 PAINTING & WALL COVERINGS	100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0			
9 FINISHES	108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3			
10-14 TOTAL DIV. 10-14	100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5			
15 MECHANICAL	100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0			
16 ELECTRICAL	98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5			
1-16 WEIGHTED AVERAGE	97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9			

DIVISION	FLORIDA						GEORGIA					
	TAMPA			ALBANY			ATLANTA			AUGUSTA		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8
031 CONCRETE FORMWORK	97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7
032 CONCRETE REINFORCEMENT	95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4
033 CAST IN PLACE CONCRETE	101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5
3 CONCRETE	92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2
4 MASONRY	82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4
5 METALS	102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7
6 WOOD & PLASTICS	94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3
7 THERMAL & MOISTURE PROTECTION	96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9
8 DOORS & WINDOWS	98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1
092 LATH, PLASTER & GYPSUM BOARD	101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8
096 FLOORING & CARPET	113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2
099 PAINTING & WALL COVERINGS	104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3
9 FINISHES	107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1
10-14 TOTAL DIV. 10-14	100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8
15 MECHANICAL	100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7
16 ELECTRICAL	97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2
1-16 WEIGHTED AVERAGE	99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5

DIVISION	GEORGIA						HAWAII			IDAHO					
	SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2
031 CONCRETE FORMWORK	97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0
032 CONCRETE REINFORCEMENT	100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6
033 CAST IN PLACE CONCRETE	91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8
3 CONCRETE	88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1
4 MASONRY	86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8
5 METALS	97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1
6 WOOD & PLASTICS	93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2
7 THERMAL & MOISTURE PROTECTION	96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7
8 DOORS & WINDOWS	95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7
092 LATH, PLASTER & GYPSUM BOARD	101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8
096 FLOORING & CARPET	113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2
099 PAINTING & WALL COVERINGS	100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3
9 FINISHES	105.8	60.5	82.8	101.9	50.0	75.5	124.5	153.9	139.5	93.2	84.6	88.8	156.4	89.0	122.1
10-14 TOTAL DIV. 10-14	100.0	71.7	94.0	100.0	70.1	93.7	100.0	129.2	106.2	100.0	86.1	97.0	100.0	100.6	100.1
15 MECHANICAL	100.0	55.8	80.5	100.0	48.7	77.3	100.1	119.4	108.6	99.8	85.6	93.5	100.6	94.1	97.7
16 ELECTRICAL	93.3	65.4	74.7	90.2	40.8	57.2	109.7	128.8	122.5	85.2	78.7	80.9	87.5	92.2	90.6
1-16 WEIGHTED AVERAGE	97.2	64.6	81.4	96.8	55.0	76.6	115.9	129.5	122.5	101.0	85.2	93.4	111.9	92.1	102.3

A.3.9-20

ECO NUMBER 10

**USE AN ALTERNATIVE HEATING METHOD TO REDUCE SEP
OPERATING COST**

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-10

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-10 ALTERNATIVE HEATING METHODS FOR THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	6043.		
B. SIOH	\$	363.		
C. DESIGN COST	\$	363.		
D. TOTAL COST (1A+1B+1C)	\$	6769.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.		
F. PUBLIC UTILITY COMPANY REBATE	\$	0.		
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		6769.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 4.	15.08	\$ 62.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	111.	\$ 149.	14.88	\$ 2213.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		111.	\$ 153.		\$ 2275.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 10102.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 150318.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
------	------------------------------	-----------------	------------------------	---

d. TOTAL	\$ 0.			0.
----------	-------	--	--	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)	\$ 150318.
---	------------

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$	\$ 10255.
--	-----------

5. SIMPLE PAYBACK PERIOD (1G/4)	.66 YEARS
---------------------------------	-----------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$ 152593.
--	------------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)=	22.54
(IF < 1 PROJECT DOES NOT QUALIFY)	

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-10

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP) LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-10 ALTERNATIVE HEATING METHODS FOR THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION B

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	334231.	
B. SIOH	\$	20054.	
C. DESIGN COST	\$	20054.	
D. TOTAL COST (1A+1B+1C)	\$	374339.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$		374339.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ -5.	15.08	\$ -83.
B. DIST	\$ 4.40	-9218.	\$ -40559.	18.57	\$ -753184.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	24711.	\$ 33113.	14.88	\$ 492718.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		15493.	\$ -7452.		\$ -260550.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 12672.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 188559.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 188559.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 5220.

5. SIMPLE PAYBACK PERIOD (1G/4) 71.71 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ -71990.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= -.19
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-10XY

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-10 ALTERNATIVE HEATING METHODS FOR THE SEP

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	6043.	
B. SIOH	\$	363.	
C. DESIGN COST	\$	363.	
D. TOTAL COST (1A+1B+1C)	\$	6769.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	6769.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		0.	\$ 0.		\$ 0.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 10070.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 149842.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 149842.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 10070.

5. SIMPLE PAYBACK PERIOD (1G/4) .67 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 149842.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 22.14
 (IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.



SUBJECT Fort Stewart
Send HTW from CEP to SEP
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-7-96
DATE _____

ECO No. 10 - A

DISTRIBUTE HTW FROM CEP TO SEP INSTEAD OF STEAM.

THE HTW SYSTEM OPERATES AT THE SAME TEMPERATURE AS THE STEAM LINE, 375 °F. IF THE STEAM LINE WERE USED TO CONVEY HTW TO THE SEP THE HEAT LOSS FROM THE LINE WOULDN'T CHANGE. THEREFORE THERE WOULD BE NO ENERGY SAVINGS, BUT THERE WOULD BE A SIGNIFICANT DECREASE IN HEATING SEASON OPERATING LABOR.

ENERGY LOSS IN STEAM LINE

ENERGY LOSS DATA FROM SEP TEST SHOWS 3.66 MBTU/HR IN 8750 FT OF PIPE. See calculation in ECO-12.

$$\text{STEAM LINE LOSS} = 3.66 \text{ MBTU/HR} \times \frac{5280 \text{ FT}}{8760 \text{ FT}} = 2.2 \text{ MBTU/HR.}$$

MAX ENERGY REQT. TO SEP

$$\begin{aligned} \text{SEP LOAD} &= 25.46 \text{ MBTU/HR} \\ \text{LINE LOSS TO SEP} &= 2.2 \text{ MBTU/HR} \\ \text{TOTAL ENERGY REQT.} &= 27.66 \text{ MBTU/HR.} \end{aligned}$$

JUMPER LINE SIZE IN CEP

$$\frac{27.66 \text{ MBTU/HR}}{500 \frac{\text{PPH}}{\text{gpm}} \times (375 - 230)} = 382 \text{ gpm} \Rightarrow 4" \phi \text{ PIPE.}$$

RETURN LINE ΔP

$$\textcircled{a} \quad 382 \text{ gpm} \quad \Delta P \text{ IN } 4" \text{ LINE} = 8 \text{ FT/100 FT PIPE. (WORST CASE)}$$

$$\frac{8 \text{ FT}}{100 \text{ FT}} \times 5280 \text{ FT} = 422 \text{ FT}$$


RS&H

ECO-10-A

SUBJECT Fort Stewart
HTW from CEP to SEP
 DESIGNER G. Fallon
 CHECKER _____

AEP NO 694 1331 002
 SHEET _____ OF _____
 DATE 2-7-96
 DATE _____

Schematic Diagram



- ① DISCONNECT STEAM TRAPS; OR, HEAVILY THROTTLE TRAP ISOLATION VALVES TO MINIMIZE, BUT NOT STOP, FLOW THROUGH TRAPS. MINIMAL TRAP FLOW WILL PROTECT DRIP LINE FROM FREEZING.
- ② BREAK & BLANK EXISTING STEAM LINE AT HEADER.
- ③ OPERATE HEATERS FULL

Proposed Labor Costs:

Start-up & shut down: assume 50%; $(\$2069 + \$621) / \text{YR} \times 0.5 = \$1345 / \text{YR}$ (see next page)

Operating Labor Costs = $1 \frac{\text{trip}}{\text{day}} \times \frac{1}{2} \frac{\text{hr}}{\text{trip}} \times \$25.86 / \text{hr} \times 135 \frac{\text{day}}{\text{yr}} = \$1746 / \text{YR}$

O&M Savings = $\$1047.3 / \text{YR} - \$1746 / \text{YR} + \$1345 / \text{YR} = \boxed{\$10,072 / \text{YR}}$

A.3.10-6



SUBJECT FORT STEWART
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-1-96
DATE _____

ECO-10

Satellite Energy Plant, Operating Costs - Labor

Assumptions:

- 1) SEP operates for $4\frac{1}{2}$ months / year
- 2) SEP startup takes 10 days / year
- 3) SEP shut down takes 3 days / yr
- 4) Normal operation requires one visit per shift that takes about 1 hour / visit.
- 5) Start-up and shut-down requires one operator Full time for one shift each day.

Pipefitters hourly rate w/ benefits = \$46.35 mmp 475

Adjusted for Savannah GA = $\$46.35 \times 0.558 = \25.86 mmp 533

Labor Costs:

$$\text{Startup} : 10 \frac{\text{days}}{\text{yr}} \times 8 \frac{\text{hrs}}{\text{day}} \times \$25.86 / \text{hr} = \underline{\$2069 / \text{yr}}$$

$$\text{Operation} : 4.5 \frac{\text{mo}}{\text{yr}} \times 30 \frac{\text{day}}{\text{mo}} \times 3 \frac{\text{hr}}{\text{day}} \times \$25.86 / \text{hr} = \underline{\$10473 / \text{yr}}$$

$$\text{Shut down} : 3 \frac{\text{day}}{\text{yr}} \times 8 \frac{\text{hr}}{\text{day}} \times \$25.86 / \text{hr} = \underline{\$621 / \text{yr}}$$

$$\text{Total Labor Cost} = \$1034 / \text{yr} + \$9310 / \text{yr} + \$621 / \text{yr} = \underline{\underline{\$13163 / \text{yr}}}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Distribute HTW from the CEP to the SEP
ECO Number: 10

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/12/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Use Calculations:

Energy Use = flow rate x specific heat x average temperature difference

$$58094 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 155 \text{ }^\circ\text{F} = 75.1 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 75.1 \text{ MBtu/yr} / 0.68 = 110.5 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 110.5 \text{ MBtu/yr} \times \$1.34 / \text{MBtu} = \$148 / \text{Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{3.67 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.39 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x Hr/Yr

$$\text{Electric Demand} = 0.39 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.32 \text{ kW}$$

$$\text{Electricity Use} = 0.32 \text{ kW} \times 264 \text{ Hr/Yr} = 84 \text{ kWh/Yr}$$

$$\text{Electricity Use} = 84 \text{ kWh/Yr} \times 0.003413 \text{ MBtu/kWh} = 0.3 \text{ MBtu/Yr}$$

$$\text{Electricity Cost} = 84 \text{ kWh/Yr} \times \$0.0469 / \text{kWh} = \$4 / \text{Year}$$

Water Cost:

$$58094 \text{ Gal/Yr} \times \$0.5562 / \text{kGal} = \$32 / \text{Year}$$

Total Utility Cost:

Heating Fuel Cost	\$148 /Year
Pumping (Elec) Cost	\$4 /Year
Water Cost	\$32 /Year
<hr/>	
Total Utility Cost	\$184 /Year



SUBJECT FORT STEWART
SHUT DOWN THE SEP
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF _____
DATE 2-7-96
DATE _____

ECO-10-B SHUT DOWN THE SEP

SEP - Estimated Building Loads

Assumptions :

- 1) 2" diameter HTW supply pipe to building
- 2) Flow based on pipe friction pressure drop of 3 ft/100 ft which is in the upper end of general design range.
- 3) The HTW temperature difference across the heat exchanger is $\sim 180^{\circ} - 60^{\circ} = 120^{\circ}\text{F}$

Heating Load:

$$\text{Load} = \text{Flow} \times \text{specific heat} \times \text{temp. diff.}$$

Flow \approx 40 gal/min from ASHRAE Friction Loss chart

$$40 \frac{\text{gal}}{\text{min}} \times 8.34 \frac{\text{lb}}{\text{gal}} \times 60 \frac{\text{min}}{\text{hr}} \times 1 \frac{\text{Btu}}{\text{lb}^{\circ}\text{F}} \times 120^{\circ}\text{F} = 2401920 \frac{\text{Btu}}{\text{hr}}$$

$$2401920 \frac{\text{Btu}}{\text{hr}} \times 1 \text{ MBtu} / 10^6 \text{ Btu} = 2.4 \text{ MBtu/hr per bldg.}$$

The cost estimate is based on 5 boilers of this size.

Heat Loss from HTW Piping

Assumptions :

- 1) Average HTW and steam pipe size is 6" dia.
- 2) Heat loss from dry insulated pipes is $\sim 55 \text{ Btu/hr.ft}$
- 3) Heat loss from pipes with deteriorated and moist insulation is 275 Btu/hr.ft
- 4) Source is Ft. McClellan study (see attached pages)
- 5) Length of SEP piping is 17500 feet.
- 6) 50% of the sep piping is dry w/good insulation.



SUBJECT FORT STEWART
SHUT DOWN THE SEP
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF _____
DATE 2-7-96
DATE _____

ECO-10-B

Heat Loss from HTW/steam piping (continued)

Current Heat Loss:

$$17500 \text{ LF} \times 0.5 \times 55 \text{ Btu/HR-LF} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 0.481 \text{ MBtu/HR}$$

$$17500 \text{ LF} \times 0.5 \times 275 \text{ Btu/HR-LF} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = 2.406 \text{ MBtu/HR}$$

$$\text{Annual heat loss} = (0.481 + 2.406) \frac{\text{MBtu}}{\text{HR}} \times 135 \frac{\text{day}}{\text{YR}} \times 24 \frac{\text{hr}}{\text{day}} = 9354 \frac{\text{MBtu}}{\text{YR}}$$

$$\text{Annual Fuel Use} = 9354 \frac{\text{MBtu}}{\text{YR}} \div 0.68 = \underline{13756 \frac{\text{MBtu}}{\text{YR}}}$$

Operating Energy Costs:

The operating energy use will be the same for both systems, however, the cost of fuel oil is \$4.40/MBtu and the cost of CEP fuels (average) is \$1.34/MBtu.

Bin temperature data was used to estimate the heating energy used in the 5 buildings (see attached table)

Current Energy Cost (CEP HEATING FUELS):

$$7374 \frac{\text{MBtu}}{\text{YR}} \div 0.68 = \underline{10844 \frac{\text{MBtu}}{\text{YR}}} \times \$1.34/\text{MBtu} = \$14531/\text{YR}$$

Proposed Energy Cost (FUEL OIL NO. 2):

$$7374 \frac{\text{MBtu}}{\text{YR}} \div 0.80 = \underline{9218 \frac{\text{MBtu}}{\text{YR}}} \times \$4.40/\text{MBtu} = \$40,557/\text{YR}$$



SUBJECT FORT STEWART
SHUT DOWN THE SEP
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1268 002
SHEET 3 OF _____
DATE 2-7-96
DATE _____

ECO-10 - B

O&M Costs for new boilers

Assume 1 hour per month per boiler for maintenance.

$$1 \frac{\text{HR}}{\text{mo}} \times 4 \frac{\text{mo}}{\text{YR}} \times 5 \text{ BOILERS} \times \$25.86/\text{HR} = \underline{\$517/\text{YR}}$$

Pumping Energy

Assume the new circulating pumps will be the same size as the existing HTW circ. pumps in the buildings.

SEP Zone HTW Pump :

$$\text{Heating energy} = 7374 \frac{\text{MBtu}}{\text{YR}} \times \frac{1 \text{ YR}}{135 \text{ day}} \times \frac{1 \text{ day}}{24 \text{ HR}} \times \frac{1 \text{ HR}}{60 \text{ min}} = 37932 \frac{\text{Btu}}{\text{HR}}$$

$$\text{lb/HR} = \frac{37932 \frac{\text{Btu}}{\text{HR}}}{1 \frac{\text{Btu}}{\text{lb}^\circ\text{F}} \times 120^\circ\text{F}} = 316 \frac{\text{lb}}{\text{HR}} \times \frac{1 \text{ GAL}}{8.34 \text{ lb}} \times \frac{1 \text{ HR}}{60 \text{ min}} = 0.63 \text{ GPM}$$

$$\text{BHP} = \frac{0.63 \times 300' \text{ HD}}{3960 \times 0.72} = 0.07 \text{ BHP} \div 0.9 \times 0.746 \frac{\text{KW}}{\text{BHP}} = 0.06 \text{ KW}$$

$$0.06 \text{ KW} \times 135 \frac{\text{day}}{\text{YR}} \times 24 \frac{\text{HR}}{\text{day}} \times 3413 \frac{\text{Btu}}{\text{KW}^\circ\text{H}} \times \frac{1 \text{ MBtu}}{10^6 \text{ Btu}} = \underline{0.7 \text{ MBtu/YR}}$$



SUBJECT FORT STEWART
SHUT DOWN SEP
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 2-7-96
DATE _____

ECO-10 B

ANNUAL SAVINGS (INCREASE)

$$\text{HEATING FUELS} = 111 + 13756 + 10844 = \boxed{24711 \frac{\text{MBtu}}{\text{YR}}}$$

$$\text{ELECTRICITY} = 0.3 - 0.7 = \boxed{(0.4) \text{ MBtu/YR}}$$


$$\text{FUEL OIL} = \boxed{(9218) \text{ MBtu/YR}}$$

$$\text{WATER} = \boxed{\$32 / \text{YR}}$$

$$\text{O\&M} = 13163 - 517 = \boxed{\$12,646 / \text{YR}}$$

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-10B.WB2

LEGEND:
 Mmp### 1996 Means Mechanical Cost Data, page ###.



Unit Heater

Fossil Fuel Boiler System Considerations:

1. Terminal units are horizontal unit heaters. Quantities are varied to accommodate total heat loss per building.
2. Unit heater selection was determined by their capacity to circulate the building volume a minimum of three times per hour in addition to the BTU output.
3. Systems shown are forced hot water. Steam boilers cost slightly more than hot water boilers. However, this is compensated for by the smaller size or fewer terminal units required with steam.
4. Floor levels are based on 10' story heights.
5. MBH requirements are gross boiler output.

System Components

System Components	QUANTITY	UNIT	COST EACH		
			MAT.	INST.	TOTAL
SYSTEM 8.3-141-1280					
HEATING SYSTEM, HYDRONIC, FOSSIL FUEL, TERMINAL UNIT HEATERS					
CAST IRON BOILER, GAS, 80 MBH, 1,070 S.F. BUILDING					
Boiler, gas, hot water, CI, burner, controls & insulation 80 MBH	1.000	Ea.	1,300	970	2,270
Pipe, steel, black, schedule 40, threaded, cplg & hngr 10'OC, 2" diam	50 200.000	L.F.	247 988	5182,070	3,058
Unit heater, 1 speed propeller, horizontal, 200° EWT, 72.7 MBH	2.000	Ea.	0 1,900	0 191	2,091
Unit heater piping hookup with controls	2.000	Set	0 640	0 1,580	2,220
Boiler breeching	1.000	System	65	48.50	113.50
Expansion tank, painted steel, ASME, 18 Gal capacity	1.000	Ea.	1,250	55.50	1,305.50
Circulating pump, CI, flange connection, 1/12 HP	1.000	Ea.	198	110	308
Pipe covering, calcium silicate w/cover, 1" wall, 2" diam	50 200.000	L.F.	145 580	209 836	1,416
TOTAL			3205	1911	5116
COST PER S.F.			6.921	5.861	12,782
			0.467	0.326	11.95
			0.463	0.326	

8.3-141

Heating Systems, Unit Heaters

		COST PER S.F.		
		MAT.	INST.	TOTAL
1260	Heating systems, hydronic, fossil fuel, terminal unit heaters,			
1280	Cast iron boiler, gas, 80 M.B.H., 1,070 S.F. bldg.	6.45	5.50	11.95
1320	163 M.B.H., 2,140 S.F. bldg.	4.41	3.72	8.13
1360	544 M.B.H., 7,250 S.F. bldg.	3.04	2.58	5.62
1400	1,088 M.B.H., 14,500 S.F. bldg.	2.71	2.46	5.17
1440	3,264 M.B.H., 43,500 S.F. bldg.	2.29	1.84	4.13
1480	5,032 M.B.H., 67,100 S.F. bldg.	2.48	1.91	4.39
1520	Oil, 109 M.B.H., 1,420 S.F. bldg.	6.40	4.87	11.27
1560	235 M.B.H., 3,150 S.F. bldg.	4.24	3.52	7.76
1600	940 M.B.H., 12,500 S.F. bldg.	3.20	2.25	5.45
1640	1,600 M.B.H., 21,300 S.F. bldg.	3.10	2.14	5.24
1680	2,480 M.B.H., 33,100 S.F. bldg.	3.10	2.14	5.24
1720	3,350 M.B.H., 44,500 S.F. bldg.	2.74	1.99	4.73
1760	Coal, 148 M.B.H., 1,975 S.F. bldg.	4.70	3.20	7.90
1800	300 M.B.H., 4,000 S.F. bldg.	3.68	2.50	6.18
1840	2,360 M.B.H., 31,500 S.F. bldg.	2.69	2.01	4.70
1880	Steel boiler, gas, 72 M.B.H., 1,020 S.F. bldg.	5.85	4.06	9.91
1920	240 M.B.H., 3,200 S.F. bldg.	4.18	3.22	7.40
1960	480 M.B.H., 6,400 S.F. bldg.	3.39	2.38	5.77
2000	800 M.B.H., 10,700 S.F. bldg.	2.99	2.13	5.12
2040	1,960 M.B.H., 26,100 S.F. bldg.	2.69	1.91	4.60
2080	3,000 M.B.H., 40,000 S.F. bldg.	2.66	1.95	4.61

To → / From ↓	ΔP				ΔP/L			ΔP/ρ			ΔP/ρL		
	psi	psf	Pa	kPa	(psi/ 100 ft)	(Pa/ m)	(kPa/ m)	ft	(l)	(J/ kg)	(ft/ 100 ft)	(milinch/ ft)	(J/ kg m)
psi	1	144	6890	6.89	—	—	—	—	—	—	—	—	—
psf	0.00694	1	4.79	0.00479	—	—	—	—	—	—	—	—	—
Pa	0.000145	0.209	1	0.001	—	—	—	—	—	—	—	—	—
kPa	0.145	209	1000	1	—	—	—	—	—	—	—	—	—
(psi/ 100 ft)	—	—	—	—	1	226	0.226	—	—	—	—	—	—
(Pa/ m)	—	—	—	—	0.00442	1	0.001	—	—	—	—	—	—
(kPa/ m)	—	—	—	—	4.42	1000	1	—	—	—	—	—	—
ft (l)	—	—	—	—	—	—	—	1	3.00	—	—	—	—
(J/ kg)	—	—	—	—	—	—	—	0.344	1	—	—	—	—
(ft/ 100 ft)	—	—	—	—	—	—	—	—	—	—	1	120	0.0983
(milinch/ ft)	—	—	—	—	—	—	—	—	—	—	0.00833	1	0.000819
(J/ kg m)	—	—	—	—	—	—	—	—	—	—	10.2	1220.7	1

(l) (ft-lb/lb) = ft




Fig. 1 Friction Loss for Water in Commercial Steel Pipe (Schedule 40)

system must be equipped with air separation devices to minimize the amount of entrained air in the piping circuit. Air should be vented at the highest point of the system.

In the absence of such venting, air can be entrained in the water and carried to separation units at flow velocities of 1.5 to 2 fps or more in pipe sizes 2 in. and under. Minimum velocities of 2 fps are therefore recommended. For pipe sizes 2 in. and over, minimum velocities corresponding to .75 ft/100 ft (.75 m/100 m) are normally used. Particular attention to maintenance of minimum velocities should be observed in the upper floors of high rise buildings when the air may tend to come out of solution because of the reduced pressures. Higher velocities should be used in down-comer return mains feeding into air separation units located in the basement.

Example 1: Determine pipe size for circuit requiring 20 gpm flow.

Solution: Enter Fig. 1 at 20 gpm, read up to pipe size within normal design range, select 1 1/2 in. Velocity is 3.1 fps which is between 2-4. Pressure loss is 2.9 ft/100 ft which is between 1-4 ft/100 ft.

Valve and Fitting Pressure Drop

Valve and fitting pressure drop is usually listed in elbow equivalents. The elbow equivalent simply relates pressure

drop through a valve or fitting to an equivalent pipe length. The pressure drop of one elbow is approximately the same as that of a length of straight pipe 25 times the pipe diameter. The following simple rule-of-thumb is often used: the equivalent length of pipe in feet for an elbow equals 2 times nominal pipe diameter (inches). Thus, a 1-in. elbow = 2 equivalent ft of 1-in. pipe, a 4-in. elbow = 8 equivalent ft of 4-in. pipe, etc.

A more accurate determination, related to water flow velocity, is listed in Table 2.

Elbow equivalents for valves and fittings for iron and copper are shown in Table 3.

Example 2: Determine equivalent feet of pipe for a 4-in. open gate valve at a flow velocity of approximately 4 fps.

Solution: From Table 2, at 4 fps, each equivalent elbow is equal to 10.6 ft of 4-in. pipe. From Table 3, the 4-in. gate valve is equal to 0.5 elbows. The actual equivalent pipe length (added to measure circuit length for pressure drop determination) will be 10.6×0.5 , or 5.3 equivalent feet of 4-in. pipe.

Tee Fitting Pressure Drop. Pressure drop through pipe tees varies with flow through the branch. Pressure drops are illustrated in Fig. 3 for tees of equal inlet and outlet sizes, and for the flow patterns illustrated.

CONF-8406132--2

NOTICE

PORTIONS OF THIS REPORT ARE ILLEGIBLE. It
has been reproduced from the best available
copy to permit the broadest possible avail-
ability.

ANALYSIS OF A SMALL DISTRICT STEAM SYSTEM AT
FT. McCLELLAN, ALABAMA

Gerald D. Pine and Michael A. Karnitz

CONF-8406132

DE84 014051

Energy Division
Oak Ridge National Laboratory*
Oak Ridge, Tennessee 37831

615 576-5454
574-5150

For presentation at the
75th Annual Conference of the International
District Heating Association
Mount Washington, New Hampshire

June 17-20, 1984

MASTER

By acceptance of this article, the
publisher or recipient acknowledges
the U.S. Government's right to
retain a nonexclusive, royalty-free
license in and to any copyright
covering the article.

* Research sponsored by the U. S. Army, Construction Engineering
Research Laboratory, under Interagency Agreement Number 40-1361-83, Army
Number CERL-83-080, operated by Martin Marietta Energy Systems, Inc.,
under Contract No. DE-AC05-84OR21400 with the U.S. Department of Energy.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

A.3.10-17

ps

Of the total steam produced, we estimate that approximately 95% enters the steam distribution system. The remaining 5% is used within the boiler plants to power auxiliaries. This amounts to some 570 lb/hr on the average or 5.0 million lb/yr. Then approximately 96 million lb/yr enters the distribution system.

5. CAUSES FOR HEAT LOSS FROM BURIED PIPE

In order to minimize heat losses from steam and condensate pipe lines, the lines are usually insulated. Sometimes the pipes may run above ground but more commonly, the pipes are buried from two to six feet below the surface. If the insulation is intact and dry, the ground helps to insulate the pipe from cold temperatures in the winter and to reduce the heat losses. In this section, we present estimates of the heat losses for well insulated pipes as well as for pipes with deteriorated insulation and under various failure conditions.

Heat Loss From Dry, Insulated, Buried Pipes. Heat losses have been calculated for varied soil conditions and various types of insulation by King et al. [3]. For the example of a six-inch steam line at 325°F with four inches of calcium silicate insulation in clay of average moisture and a soil temperature of 50°F, the rate of heat loss would be approximately 55 Btu/hour per linear foot of pipe. For the Ft. McClellan system with a steam temperature of 338°F and a ground temperature of 80°F, the loss rate would be about 52 Btu/hr-ft. ←

Heat Loss From Bare Pipes in Air. The simplest case to consider is a bare pipe exposed to ambient air on a dry, still day. For this case, the two major heat loss mechanisms are natural convection and radiation. We consider the case of a six-inch pipe with 338°F steam and ambient air at 150°F (a typical temperature inside a dry vault, where much of the bare pipe is found). The estimated loss due to natural convection under these conditions is about 350 Btu/hour per foot of pipe. Kreith [4] in Table 5.1 gives a value of emissivity of 0.8 for oxidized steel pipe. For the same pipe, the estimated radiation loss is approximately 370 Btu/hr-ft. The total loss per foot of bare pipe under these circumstances is then 920 Btu/hr-ft.

Buried Pipes With Entrapped Moisture and Deteriorated Insulation. Observations of actual buried steam lines indicates that the heat losses are substantially higher than the theoretical losses. Consideration of the magnitudes of the observed losses suggests that the pipe is behaving as though there were no insulation, and that the pipe is in direct contact with the surrounding soil. The most likely physical explanation is that the conductivity has been greatly enhanced by the deterioration of the insulation from the combined effects of heat and moisture that gets into the system by steam leaks or the intrusion of ground water. Entrapped moisture could be boiling near the surface of the pipe and condensing on the jacket, or subcooled boiling and the formation of a thermal convection loop in water filling the space between the pipe and jacket could be occurring. Both these processes produce extremely high heat transfer rates compared to the rate through dry insulation. If it is assumed that the conductivity of the insulation is infinite, the model of King et al. yields a heat transfer factor of about 1.8 Btu/hr-°F per foot of six-inch diameter pipe. For the six-inch pipe at 330°F and a 80°F ground temperature, the rate of heat loss per foot of pipe would be 460 Btu/hr-ft. This compares with the observed value of about 275 Btu/hr-ft. ←

Heat Loss From Flooding of Vaults. A commonly observed failure of steam lines is the failure of sump pumps in valve pits and the subsequent covering of the steam pipe with water. The source of the water can be either condensate from steam traps, which collects in the vault and causes flooding when sump pumps fail, or intrusion of ground water into the pits through cracks in the pit wall or around pipes that penetrate the pit walls. Water in the vaults is commonly heated to temperatures that are rather hot; we assume here that the water in the vault is heated to 150°F. The estimated rate of heat loss from a bare, six-inch steam pipe carrying 338°F steam and covered by 150°F water is 50,000 Btu/hr-ft. (This estimate could be higher, perhaps as high as 150,000 Btu/hr-ft depending on the assumed heat transfer mechanism.) Notice that the loss is nearly sixty times as large as the loss from dry, bare pipe. Perhaps even more interesting, the rate of heat loss would be 190 times greater than the

Fort Stewart - Central Energy Plant
 Filename: FS-VPDIS.WQ1
 12/15/95

Approximate Distance Between Valve Pits (1)

ZONE 1		ZONE 2N		ZONE 2S		ZONE 3		SEP ZONE		
PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	
CP-B1	200	CP-V1	150	V1-B1	700	CP-?	700	C1-V1	1500	(2)
B1-V4	1000	V1-V2	200	B1-V1	1500	?-1	800	V1-V2	100	(2)
V1-V2	600	V2-V3	350	V1-B2	300	?-2	400	V2-V3	1700	(2)
V2-V3	200	V3-V4	650	B2-B3	550	2-2A	400	V3-V4	450	(2)
V3-V4	350	V4-V5	600	B3-V1	250	2A-3	500	V4-V5	600	(2)
V4-V5	300	V5-V6	800	V1-V2	250	3-3A	400	V5-V6	500	(2)
V5-V6	550	V6-V7	800	V1-V3	350	3A-6	550	V6-SP	100	(2)
V6-V7	400	V2-V8	750	V3-V4	250	4-5	900	SP-V7	200	
V7-V8	600	V8-V9	300	V3-V6	300	5-6	650	V7-V8	150	
V8-V9	350			V4-V5	200	6-7	850	V8-V9	550	
V9-V10	350			V3-V7	650	7-8	950	V9-V10	650	
V10-V11	250			V7-V8	250	8-9	1000	V10-V11	800	
V11-V12	500			V8-V9	500	9-10	1000	V11-V12	650	
V12-V13	1000			V9-V10	200	10-11	900	V12-V13	800	
V13-V14	350			V9-V11	450	11-12	500			
V14-V15	400					12-13	950			
V15-V16	400					13-13A	750			
V16-V17	500					12-14	950			
V17-V18	800					14-15	200			
						15-16	250			
						16-16A	300			
						16A-17	200			
						17-18	200			
						18-19	100			
						19-20	150			
						20-22	200			
						21-22	100			
						22-23	350			
						15-24C	350			
						24C-24B	200			
						24B-24	200			
						24-24A	200			
						24A-25	150			
						24A-25A	300			
						25A-26	100			
						26-26A	200			
						26A-27	250			
						27-28	250			
TOTAL LN.FT.		9100	4600	6700		17400		8750		
MILES		1.7	0.9	1.3		3.3		1.7		8.8
MAX LNFT/VP	1000	800	1500	1000	1700					
AVG LNFT/VP	479	511	447	458	625					490
MIN LNFT/VP	200	150	200	100	100					
NO. OF PITS (1)	19	9	15	38	14					95

- (1) There are other valve boxes and drain pits that are not shown on our HTW system map.
 (2) These pipes carry steam.

HEATING SEASON ENERGY CONSUMPTION FOR SEP BUILDINGS

SEP Building Number													
Pipe size feeding building													
GPM flow rate at 3 ft/100 ft													
Max Heat delivery (MBtu/Hr)													
4502													
2" dia													
40													
2.4													
4577													
2" dia													
40													
2.4													
4528													
1.25" dia.													
13													
0.8													
3002													
1" dia.													
7													
7.21													
Total													
Temp.													
Hours in Temperature Range													
Range													
Nov													
Dec													
Jan													
Feb													
Mar													
Total													
Load (%)													
Time (%)													
MBTU													
130													
130													
260													
388													
458													
467													
356													
232													
115													
41													
10													
2,458													
2,458													
1,229													
799													
430													
7,374													

A.3.10-21

3-109

Installing Contractor's Overhead & Profit

Below are the average installing contractor's percentage mark-ups applied to base labor rates to arrive at typical billing rates.

Column A: Labor rates are based on union wages averaged for 30 major U.S. cities. Base rates including fringe benefits are listed hourly and daily. These figures are the sum of the wage rate and employer-paid fringe benefits such as vacation pay, employer-paid health and welfare costs, pension costs, plus appropriate training and industry advancement funds costs.

Column B: Workers' Compensation rates are the national average of state rates established for each trade.

Column C: Column C lists average fixed overhead figures for all trades. Included are Federal and State Unemployment costs set at 7.3%; Social Security Taxes (FICA) set at 7.65%; Builder's Risk Insurance costs set at 0.34%; and Public Liability costs set at 1.55%. All the percentages except those for Social Security Taxes vary from state to state as well as from company to company.

Columns D and E: Percentages in Columns D and E are based on the presumption that the installing contractor has annual billing of \$500,000 and up. Overhead percentages may increase with smaller annual billing. The overhead percentages for any given contractor may vary greatly and depend on a number of factors, such as the contractor's annual volume, engineering and logistical support costs, and staff requirements. The figures for overhead and profit will also vary depending on the type of job, the job location, and the prevailing economic conditions. All factors should be examined very carefully for each job.

Column F: Column F lists the total of Columns B, C, D, and E.

Column G: Column G is Column A (hourly base labor rate) multiplied by the percentage in Column F (O&P percentage).

Column H: Column H is the total of Column A (hourly base labor rate) plus Column G (Total O&P).

Column I: Column I is Column H multiplied by eight hours.

		A		B	C	D	E	F	G	H	I
Abbr.	Trade	Base Rate Incl. Fringes		Work-ers' Comp. Ins.	Average Fixed Over-head	Over-head	Profit	Total Overhead & Profit		Rate with O & P	
		Hourly	Daily					%	Amount	Hourly	Daily
Skwk	Skilled Workers Average (35 trades)	\$25.95	\$207.60	20.2%	16.8%	13.0%	10%	60.0%	\$15.55	\$41.50	\$332.00
	Helpers Average (5 trades)	19.25	154.00	21.4		11.0		59.2	11.40	30.65	245.20
	Foreman Average, Inside (\$.50 over trade)	26.45	211.60	20.2		13.0		60.0	15.85	42.30	338.40
	Foreman Average, Outside (\$2.00 over trade)	27.95	223.60	20.2		13.0		60.0	16.75	44.70	357.60
	Common Building Laborers	19.80	158.40	21.9		11.0		59.7	11.80	31.60	252.80
Clab	Asbestos Workers	28.55	228.40	19.7		16.0		62.5	17.85	46.40	371.20
	Boilermakers	30.05	240.40	17.7		16.0		60.5	18.20	48.25	386.00
	Bricklayers	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
	Bricklayer Helpers	20.00	160.00	19.4		11.0		57.2	11.45	31.45	251.60
	Carpenters	25.20	201.60	21.9		11.0		59.7	15.05	40.25	322.00
Cefi	Cement Finishers	24.35	194.80	12.8		11.0		50.6	12.30	36.65	293.20
	Electricians	29.30	234.40	8.0		16.0		50.8	14.90	44.20	353.60
	Elevator Constructors	30.05	240.40	9.6		16.0		52.4	15.75	45.80	366.40
	Equipment Operators, Crane or Shovel	26.75	214.00	12.9		14.0		53.7	14.35	41.10	328.80
	Equipment Operators, Medium Equipment	25.70	205.60	12.9		14.0		53.7	13.80	39.50	316.00
Eqht	Equipment Operators, Light Equipment	24.70	197.60	12.9		14.0		53.7	13.25	37.95	303.60
	Equipment Operators, Oilers	21.90	175.20	12.9		14.0		53.7	11.75	33.65	269.20
	Equipment Operators, Master Mechanics	27.55	220.40	12.9		14.0		53.7	14.80	42.35	338.80
	Glaziers	24.90	199.20	16.0		11.0		53.8	13.40	38.30	306.40
	Lathers	24.95	199.60	13.5		11.0		51.3	12.80	37.75	302.00
Marb	Marble Setters	25.65	205.20	19.4		11.0		57.2	14.65	40.30	322.40
	Millwrights	26.55	212.40	13.2		11.0		51.0	13.55	40.10	320.80
	Mosaic & Terrazzo Workers	25.25	202.00	11.0		11.0		48.8	12.30	37.55	300.40
	Painters, Ordinary	22.95	183.60	16.8		11.0		54.6	12.55	35.50	284.00
	Painters, Structural Steel	23.95	191.60	62.5		11.0		100.3	24.00	47.95	383.60
Pape	Paper Hangers	23.30	186.40	16.8		11.0		54.6	12.70	36.00	288.00
	Pile Drivers	25.35	202.80	33.6		16.0		76.4	19.35	44.70	357.60
	Plasterers	24.20	193.60	17.4		11.0		55.2	13.35	37.55	300.40
	Plasterer Helpers	20.15	161.20	17.4		11.0		55.2	11.10	31.25	250.00
	Plumbers	30.05	240.40	10.2		16.0		53.0	15.95	46.00	368.00
Rodm	Rodmen (Reinforcing)	27.75	222.00	36.3		14.0		77.1	21.40	49.15	393.20
	Roofers, Composition	22.55	180.40	37.4		11.0		75.2	16.95	39.50	316.00
	Roofers, Tile & Slate	22.60	180.80	37.4		11.0		75.2	17.00	39.60	316.80
	Roofers, Helpers (Composition)	15.95	127.60	37.4		11.0		75.2	12.00	27.95	223.60
	Sheet Metal Workers	28.95	231.60	13.8		16.0		56.6	16.40	45.35	362.80
Spri	Sprinkler Installers	31.30	250.40	10.4		16.0		53.2	16.65	47.95	383.60
	Steamfitters or Pipefitters	30.30	242.40	10.2		16.0		53.0	16.05	46.35	370.80
	Stone Masons	25.90	207.20	19.4		11.0		57.2	14.80	40.70	325.60
	Structural Steel Workers	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
	Tile Layers	25.05	200.40	11.0		11.0		48.8	12.20	37.25	298.00
Tilh	Tile Layers Helpers	20.30	162.40	11.0		11.0		48.8	9.90	30.20	241.60
	Truck Drivers, Light	20.35	162.80	17.0		11.0		54.8	11.15	31.50	252.00
	Truck Drivers, Heavy	20.70	165.60	17.0		11.0		54.8	11.35	32.05	256.40
	Welders, Structural Steel	27.85	222.80	46.4		14.0		87.2	24.30	52.15	417.20
	*Wrecking	19.80	158.40	44.8	↓	11.0	↓	82.6	16.35	36.15	289.20

*Not included in Averages.

City Cost Indexes

DIVISION	FLORIDA																	
	MIAMI			ORLANDO			PANAMA CITY			PENSACOLA			ST. PETERSBURG			TALLAHASSEE		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.3	72.8	81.5	125.3	85.9	95.0	141.6	83.4	96.9	138.9	85.9	98.1	126.2	85.6	95.0	125.7	85.2	94.6
031 CONCRETE FORMWORK	94.2	71.0	74.5	97.3	71.6	75.5	95.8	37.8	46.6	84.5	69.7	72.0	94.1	64.8	69.3	97.3	53.0	59.7
032 CONCRETE REINFORCEMENT	95.1	72.5	82.4	95.1	79.0	86.0	99.3	64.5	79.7	101.5	64.9	81.0	98.5	74.3	84.9	95.1	65.2	78.3
033 CAST IN PLACE CONCRETE	91.5	75.4	84.6	88.7	78.0	84.1	95.2	43.0	72.9	95.2	69.0	84.0	101.4	70.2	88.1	91.7	58.4	77.5
3 CONCRETE	87.4	74.3	80.8	86.3	76.7	81.4	95.0	46.6	70.5	93.5	70.1	81.7	92.6	70.1	81.2	87.7	59.2	73.3
4 MASONRY	76.9	70.2	72.8	77.4	75.6	76.2	84.9	37.4	55.4	82.6	67.6	73.3	119.2	66.9	86.7	83.6	52.6	64.4
5 METALS	98.8	93.5	96.8	107.9	95.0	103.0	97.2	75.1	88.9	97.1	89.6	94.3	101.0	92.4	97.7	99.2	88.1	95.0
6 WOOD & PLASTICS	88.6	72.7	80.6	94.5	71.1	82.8	92.9	38.3	65.6	80.1	71.1	75.6	90.8	65.2	78.0	94.5	51.6	73.0
7 THERMAL & MOISTURE PROTECTION	99.6	74.6	88.0	96.6	75.6	86.9	96.9	38.3	69.9	96.6	66.9	82.9	96.3	63.1	81.0	96.6	58.8	79.1
8 DOORS & WINDOWS	95.9	69.5	89.5	98.1	68.2	90.9	95.7	35.2	81.2	95.7	66.5	88.7	96.8	60.4	88.0	98.1	53.9	87.4
092 LATH, PLASTER & GYPSUM BOARD	101.0	72.5	82.5	101.6	70.8	81.7	99.7	36.9	59.0	94.5	70.9	79.2	98.9	64.8	76.8	101.6	50.7	68.6
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	72.5	83.0	102.4	70.8	82.0	96.6	36.9	58.0	96.6	70.9	79.9	98.0	64.8	76.5	102.4	50.7	68.9
096 FLOORING & CARPET	121.8	75.3	110.7	113.0	74.9	103.8	112.3	24.6	91.3	106.7	68.0	97.4	111.4	67.8	100.9	113.0	49.7	97.8
099 PAINTING & WALL COVERINGS	100.9	70.1	83.0	104.2	77.6	88.7	104.2	34.5	63.7	104.2	78.5	89.3	104.2	65.4	81.6	104.2	55.7	76.0
9 FINISHES	108.6	71.4	89.7	107.7	72.7	89.9	107.2	34.4	70.2	104.5	70.5	87.2	106.0	65.3	85.3	107.7	51.9	79.3
10-14 TOTAL DIV. 10-14	100.0	81.8	96.1	100.0	83.9	96.6	100.0	65.4	92.6	100.0	73.3	94.3	100.0	76.8	95.1	100.0	74.0	94.5
15 MECHANICAL	100.0	72.9	88.0	100.0	70.8	87.1	100.0	34.6	71.1	100.0	68.8	86.2	100.0	68.7	86.2	100.0	54.8	80.0
16 ELECTRICAL	98.0	84.9	89.3	98.0	63.0	74.6	96.3	47.1	63.5	101.8	63.4	76.2	98.5	68.1	78.2	98.0	58.3	71.5
1-16 WEIGHTED AVERAGE	97.5	76.7	87.4	99.2	75.1	87.6	99.2	48.1	74.5	98.8	71.8	85.7	101.0	71.8	86.9	98.5	62.1	80.9
DIVISION	FLORIDA						GEORGIA											
	TAMPA			ALBANY			ATLANTA			AUGUSTA			COLUMBUS			MACON		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	126.9	85.6	95.1	110.4	74.2	82.5	114.3	92.8	97.8	110.2	91.5	95.8	110.4	74.3	82.6	111.6	91.9	96.5
031 CONCRETE FORMWORK	97.3	64.9	69.8	96.9	50.8	57.8	98.0	70.3	74.5	94.5	61.8	66.7	96.9	50.4	57.4	95.9	65.9	70.5
032 CONCRETE REINFORCEMENT	95.1	74.3	83.4	95.1	76.4	84.6	98.5	77.5	86.7	104.0	69.1	84.4	95.1	76.4	84.6	97.4	76.7	85.8
033 CAST IN PLACE CONCRETE	101.7	70.2	88.2	95.5	48.9	75.6	101.1	71.2	88.3	95.6	57.9	79.5	95.5	49.5	75.8	95.5	53.3	77.5
3 CONCRETE	92.4	70.2	81.2	89.4	57.0	73.0	94.0	72.1	82.9	90.5	62.2	76.2	89.4	57.0	73.0	89.7	65.1	77.3
4 MASONRY	82.8	66.9	72.9	83.4	38.9	55.7	92.1	63.6	74.4	92.2	49.1	65.4	83.4	39.3	56.0	98.6	46.7	66.4
5 METALS	102.2	92.4	98.5	96.8	89.0	93.9	93.7	74.5	86.4	92.4	69.4	83.7	96.7	89.3	93.9	91.7	90.1	91.1
6 WOOD & PLASTICS	94.5	65.2	79.8	93.7	51.6	72.6	99.7	72.2	86.0	95.9	64.6	80.3	93.7	51.3	72.5	97.4	69.9	83.6
7 THERMAL & MOISTURE PROTECTION	96.6	64.3	81.7	96.4	55.7	77.6	94.2	70.0	83.0	93.6	59.5	77.9	96.1	55.7	77.5	95.1	62.9	80.2
8 DOORS & WINDOWS	98.1	60.4	89.0	95.9	53.7	85.7	94.2	67.9	87.9	90.6	59.3	83.1	95.9	53.8	85.7	94.2	64.8	87.1
092 LATH, PLASTER & GYPSUM BOARD	101.6	64.8	77.7	101.6	50.7	68.6	112.5	72.0	86.2	111.3	64.1	80.7	101.6	50.4	68.4	108.3	69.5	83.2
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	64.8	78.1	102.4	50.7	69.0	108.7	72.0	84.9	108.7	64.1	79.8	102.4	50.4	68.7	95.9	69.5	78.8
096 FLOORING & CARPET	113.0	67.8	102.1	113.0	40.4	95.6	87.8	75.0	84.8	86.7	51.5	78.2	113.0	41.0	95.7	87.8	47.5	78.2
099 PAINTING & WALL COVERINGS	104.2	65.4	81.6	100.9	50.4	71.5	99.0	72.1	83.4	99.0	47.9	69.3	100.9	48.3	70.3	102.4	59.0	77.2
9 FINISHES	107.7	65.3	86.1	105.8	48.1	76.4	95.1	71.5	83.1	94.4	58.6	76.1	105.7	47.8	76.2	91.5	62.0	76.5
10-14 TOTAL DIV. 10-14	100.0	76.8	95.1	100.0	69.5	93.5	100.0	75.4	94.8	100.0	71.0	93.8	100.0	69.4	93.5	100.0	73.6	94.4
15 MECHANICAL	100.0	68.7	86.2	100.0	56.8	80.9	100.1	71.7	87.5	100.1	54.0	79.7	100.0	46.2	76.2	100.0	52.1	78.8
16 ELECTRICAL	97.5	68.1	77.9	93.3	68.1	76.5	93.4	82.3	86.0	96.9	61.3	73.2	93.3	49.4	64.0	91.4	63.3	72.7
1-16 WEIGHTED AVERAGE	99.5	71.8	86.1	97.1	60.8	79.5	96.5	75.0	86.1	95.5	62.5	79.5	97.1	55.7	77.1	95.4	65.4	80.9
DIVISION	GEORGIA						HAWAII			IDAHO								
	SAVANNAH			VALDOSTA			HONOLULU			BOISE			LEWISTON			POCATELLO		
	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL	MAT.	INST.	TOTAL
2 SITE WORK	110.6	76.1	84.0	122.0	74.5	85.5	115.0	112.0	112.7	86.4	99.3	96.3	90.4	92.7	92.2	89.1	99.3	96.9
031 CONCRETE FORMWORK	97.0	60.5	66.0	80.8	51.9	56.3	102.1	158.7	150.1	97.4	89.3	90.5	106.3	87.1	90.0	97.4	89.3	90.5
032 CONCRETE REINFORCEMENT	100.7	69.5	83.2	100.8	50.3	72.5	109.9	125.0	118.4	96.0	78.4	86.1	108.6	96.1	101.6	96.3	78.5	86.3
033 CAST IN PLACE CONCRETE	91.5	56.6	76.6	93.0	57.4	77.8	170.2	127.7	152.0	98.6	93.8	96.6	107.8	93.9	101.8	99.6	93.8	97.1
3 CONCRETE	88.3	62.5	75.3	92.8	55.5	74.0	153.0	139.4	146.1	103.2	88.7	95.9	115.5	91.0	103.1	103.7	88.6	96.1
4 MASONRY	86.9	57.6	68.7	89.8	50.6	65.4	131.3	134.3	133.2	131.8	81.0	100.2	128.8	96.6	108.8	136.3	82.7	103.0
5 METALS	97.1	87.6	93.5	96.5	80.7	90.6	117.4	107.6	113.7	112.9	82.2	101.3	96.2	90.7	94.1	112.5	82.2	101.1
6 WOOD & PLASTICS	93.8	60.9	77.3	76.0	50.3	63.1	100.6	165.6	133.1	95.1	88.5	91.8	98.7	83.6	91.2	95.1	88.5	91.8
7 THERMAL & MOISTURE PROTECTION	96.4	59.2	79.3	96.1	60.0	79.5	109.5	133.7	120.6	97.9	84.0	91.5	167.6	89.8	131.7	98.0	83.8	91.5
8 DOORS & WINDOWS	95.9	56.7	86.4	91.4	46.3	80.5	110.6	146.5	119.2	94.9	81.7	91.7	116.3	85.0	108.7	94.9	78.5	91.0
092 LATH, PLASTER & GYPSUM BOARD	101.6	60.4	74.9	93.7	49.4	65.0	95.7	167.7	142.3	89.0	87.9	88.3	135.3	83.0	101.4	89.0	87.9	88.3
095 ACOUSTICAL TREATMENT & WOOD FLOORING	102.4	60.4	75.2	98.0	49.4	66.5	132.8	167.7	155.4	96.2	87.9	90.8	144.9	83.0	104.8	96.2	87.9	90.8
096 FLOORING & CARPET	113.0	60.7	100.4	105.1	48.5	91.5	127.8	128.3	127.9	97.5	74.8	92.1	135.1	97.9	126.2	97.5	74.8	92.1
099 PAINTING & WALL COVERINGS	100.9	59.9	77.0	100.9	43.7	67.6	123.8	148.0	137.9	109.4	67.9	85.2	134.4	91.3	109.3	109.4	78.2	91.3
9 FINISHES	105.8	60.5	82.8	101.9	50.0	75.5	124.5	153.9	139.5	93.2	84.6	88.8	156.4	89.0	122.1	93.2	85.8	89.4
10-14 TOTAL DIV. 10-14	100.0	71.7	94.0	100.0	70.1	93.7	100.0	129.2	106.2	100.0	86.1	97.0	100.0	100.6	100.1	100.0	86.1	97.0
15 MECHANICAL	100.0	55.8	80.5	100.0	48.7	77.3	100.1	119.4	108.6	99.8	85.6	93.5	100.6	94.1	97.7	99.8	85.6	93.5
16 ELECTRICAL	93.3	65.4	74.7	90.2	40.8	57.2	109.7	128.8	122.5	85.2	78.7	80.9	87.5	92.2	90.6	85.7	79.4	81.5
1-16 WEIGHTED AVERAGE	97.2	64.6	81.4	96.8	55.0	76.6	115.9	129.5	122.5	101.0	85.2	93.4	111.9	92.1	102.3	101.3	85.5	93.7

A.3.10-23

ECO NUMBER 11

**CONTRACT WITH A LEAK DETECTION SERVICE OR PURCHASE LEAK
LOCATING EQUIPMENT FOR USE WHEN A MAJOR HTW LEAK OCCURS**

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-11

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-11 PURCHASE LEAK DETECTION EQUIPMENT

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	55500.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	55500.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	55500.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 1.	15.08	\$ 21.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	76.	\$ 102.	14.88	\$ 1511.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		76.	\$ 103.		\$ 1532.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 5658.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 84191.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 84191.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 5761.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.63 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 85723.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.54
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-11X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-11 PURCHASE LEAK DETECTION EQUIPMENT

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	55500.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	55500.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	55500.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 1.	15.08	\$ 21.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	66.	\$ 88.	14.88	\$ 1306.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		66.	\$ 89.		\$ 1327.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	5658.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	84191.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 84191.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 5747.

5. SIMPLE PAYBACK PERIOD (1G/4) 9.66 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 85518.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 1.54
(IF < 1 PROJECT DOES NOT QUALIFY)

**** Project does not qualify for ECIP funding; 4,5,6 for information only.

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-11Y

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-11 PURCHASE LEAK DETECTION EQUIPMENT

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 05-06-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	55500.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	55500.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	55500.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 1.	15.08	\$ 21.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	58.	\$ 78.	14.88	\$ 1156.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		58.	\$ 79.		\$ 1177.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ 5658.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ 84191.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
------	------------------------------	-----------------	------------------------	---

d. TOTAL	\$ 0.			0.
----------	-------	--	--	----

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)	\$ 84191.
---	-----------

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$	\$ 5737.
--	----------

5. SIMPLE PAYBACK PERIOD (1G/4)	9.67 YEARS
---------------------------------	------------

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C)	\$ 85368.
--	-----------

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)=	1.54
(IF < 1 PROJECT DOES NOT QUALIFY)	

**** Project does not qualify for ECIP funding; 4,5,6 for information only.



SUBJECT Fort Stewart
Purchase Leak Correlator
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF _____
DATE 2-7-96
DATE Rev. 4-12-96

ECO-11 PURCHASE LEAK CORRELATOR.


W/o Leak Correlator

Assume 3 dig and cut operations are required to find a typical HTW leak.

Average distance between valve pits:

$$\frac{9100 \text{ LF} + 4600 \text{ LF} + 6700 \text{ LF} + 17400 \text{ LF} + 8750 \text{ LF}}{95 \text{ Valve Pits}} = 490 \text{ LF/pit}$$

Area of excavation: Assume 1 dig is 20' long and:



$$6' \times 11' \times 20' = 1320 \text{ Ft}^3 \div 27 \frac{\text{CF}}{\text{CY}} = 48.9 \Rightarrow \text{say } 50 \frac{\text{CY}}{\text{DIG}} \times 3 \text{ DIGS} = 150 \text{ CY}$$

Using a combination of backhoe and hand excavation and assuming 60% ($150 \times 0.6 = 90 \text{ CY}$) will be done by backhoe and 40% ($150 \times 0.4 = 60 \text{ CY}$) will be done by hand. The time required to find the leak is:

Backhoe : $90 \text{ CY} \times 0.080 \text{ hr/cy} \div 24 \text{ hr/day} \approx 0.3 \text{ day}$ (96MM p28)
By Hand : $60 \text{ CY} \times 1.5 \text{ hr/cy} \div 24 \text{ hr/day} \div 4 \text{ men} \approx 0.94 \text{ day}$ (96MM p28)

HTW Lost: (See graph of 1995 Make-up water use)

Average loss during leak = 25000 GPD
Average 1995 Make-up use = 10000 GPD

$$(25000 \text{ GPD} - 10000 \text{ GPD}) \times 1.24 \text{ Day/leak} \approx 18,560 \text{ Gal/leak}$$



SUBJECT Fort Stewart
Purchase Leak Correlator
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF _____
DATE 2-7-96
DATE Rev. 4-12-96

ECO-11

With Leak Correlator

Assume only have to dig 20 linear feet. Vendor indicated leak could be located within inches (see call confirmation) on the first dig.

Area of excavation :

$$6' \times 11' \times 20' = 1320 \text{ CF} \div 27 \text{ CF/cy} = 49 \Rightarrow 50 \text{ cy}$$

Assume 60 % will be done by backhoe; $50 \times 0.6 = 30 \text{ cy}$

Assume 40 % will be done by hand; $50 \times 0.4 = 20 \text{ cy}$

Time Required:

By hand : $20 \text{ cy} \times 1.5 \frac{\text{hr}}{\text{cy}} \div 4 \text{ men} \div 24 \text{ hr/day} = 0.31 \text{ day} \text{ (96MM p 28)}$

w/ backhoe: $30 \text{ cy} \times 0.080 \frac{\text{hr}}{\text{cy}} \div 24 \text{ hr/day} = 0.1 \text{ day} \text{ (96MM p 28)}$

Assume 4 hours for leak correlator test

$$0.31 \text{ day} + 0.1 \text{ day} + 0.17 \text{ day} = 0.58 \text{ days/leak}$$

HTW Lost :

$$(25000 \text{ GPD} - 10000 \text{ GPD}) \times 0.58 \text{ day} = 8650 \text{ Gal/leak}$$



SUBJECT FORT STEWART
PURCHASE LEAK CORRELATOR
DESIGNER W. TODD
CHECKER _____

AEP NO 694 1331 002
SHEET 3 OF _____
DATE 2-7-96
DATE Rev. 4-12-96

ECO - 11

W/o Leak Correlator :

$$\text{O\&M Costs} = (\text{From estimate EST-11B.WB2} = \underline{\$9133/\text{YR}})$$

$$\text{HTW Losses} = 18,560 \frac{\text{GAL}}{\text{Leak}} \times 2 \frac{\text{Leaks}}{\text{YR}} = \underline{37,120 \frac{\text{GAL}}{\text{YR}}}$$

$$\text{Heating Fuel Use} = \underline{141.2 \text{ MBtu/YR}}$$

$$\text{Electricity Use} = 54 \frac{\text{Kwh}}{\text{YR}} \times 0.003413 \frac{\text{MBtu}}{\text{Kwh}} = \underline{0.2 \frac{\text{MBtu}}{\text{YR}}}$$

$$\text{Water Cost} = 37,120 \frac{\text{GAL}}{\text{YR}} \times \$0.5562/1000 \text{ GAL} = \underline{\$21/\text{YR}}$$

With Leak Correlator :

$$\text{O\&M Costs} = (\text{from estimate EST-11A.WB2} = \underline{\$3486/\text{YR}})$$

$$\text{HTW Losses} = 8650 \frac{\text{GAL}}{\text{Leak}} \times 2 \frac{\text{Leaks}}{\text{YR}} = \underline{17300 \text{ GAL/YR}}$$

$$\text{Heating Fuel Use} = \underline{65.8 \text{ MBtu/YR}}$$

$$\text{Electricity Use} = 25 \frac{\text{Kwh}}{\text{YR}} \times 0.003413 \frac{\text{MBtu}}{\text{Kwh}} = \underline{0.1 \frac{\text{MBtu}}{\text{YR}}}$$

$$\text{Water Cost} = 17,300 \frac{\text{GAL}}{\text{YR}} \times \$0.5562/1000 \text{ GAL} = \underline{\$10/\text{YR}}$$

ANNUAL SAVINGS

$$\text{HEATING FUELS} = 141.2 - 65.8 = 75.8 \text{ MBtu/YR}$$

$$\text{ELECTRICITY} = 0.2 - 0.1 = 0.1 \text{ MBtu/YR}$$

$$\text{WATER} = \$21 - \$10 = \$11/\text{YR}$$

$$\text{O\&M} = \$9133 - \$3486 = \$5647/\text{YR}$$

A.3.11-7

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Piping Leaks
 Location: Fort Stewart, GA
 Basis: Schematic Design
 ECO Number: 11

RS&H No.: 694-1331-002
 Date: 04/12/96
 Estimator: W.T.Todd
 Filename: EST-11A.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Shut off HTW zone	4	MH	0	0	30.30	121	121		MMp475
Perform leak locator test	4	MH	0	0	30.30	121	121		MMp475
Excavation, backhoe to 6'	30	CY	1.43	43	1.82	55	98	MMp28	MMp28
Excavation, by hand to 6'	20	CY	0	0	29.65	593	593	MMp28	MMp28
Remove conduit, torch	6	LF	1.06	6	4.95	30	36	MMp22	MMp22
Remove pipe insulation	2	LF	0	0	4.84	10	10		MMp236
Valve off and drain pipe	0.50	MH	0	0	30.30	15	15		MMp475
Repair HTW leak - Weld	1	Ea	1.95	2	16.05	16	18	MMp144	MMp144
Open valves - fill pipe	0.50	Ea	0	0	30.30	15	15		MMp475
Replace pipe insulation	2	LF	0	0	4.84	10	10		MMp236
Weld conduit, 24" Sch 40	1	Ea	35	35	289	289	324	MMp144	MMp144
Backfill trench, by hand	20	CY		0	12.85	257	257	MMp28	MMp28
Compact backfill, by hand	20	CY		0	4.66	93	93	MMp28	MMp28
Backfill trench, dozer	30	CY	0.95	29	0.32	10	39	MMp28	MMp28
Compact backfill, dozer	30	CY	1.37	41	0.41	12	53	MMp28	MMp28
Total Cost per Leak				156		1647	1,803		
Total Cost for All Leaks	2	Ea	156	312	1647	3294	3,606		
Subtotal Bare Costs				312		3294	\$3,606		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				312		3294	3,606		
City Cost Index (Sav. GA)			0%	0	-44%	-1456	(1,456)	MMp533	MMp533
Subtotal				312		1838	2,150		
OH & Profit Markups			10%	31	53%	974	1,005	MMp7	MMp475
Subtotal				343		2812	3,155		
Sales Taxes			4.0%	14		NA	14	MMp476	
Subtotal				357		2812	3,169		
Contingency			10%	36	10%	281	317	MEp6	MEp6
Total Construction Cost				393		3093	3,486		
Design Fee				NA	0.0%	0	0		
SIOH				NA	0.0%	0	0		
Total Project Cost				393		3093	\$3,486		

LEGEND:

MEp### 1996 Means Electrical Cost Data, page ###.
 MMp### 1996 Means Mechanical Cost Data, page ###.

CONSTRUCTION COST ESTIMATE

Project: Repair HTW Piping Leaks
 Location: Fort Stewart, GA
 Basis: Schematic Design
 ECO Number: 11

RS&H No.: 694-1331-002
 Date: 04/12/96
 Estimator: W.T.Todd
 Filename: EST-11B.WB2

ITEM DESCRIPTION	QUANTITY		MATERIAL/EQUIP		LABOR		TOTAL COST	SOURCE	
	No.	Unit	\$/Unit	Total	\$/Unit	Total		Material	Labor
Shut off HTW zone	4	MH	0	0	30.30	121	121		MMp475
Excavation, backhoe to 6'	90	CY	1.43	129	1.82	164	293	MMp28	MMp28
Excavation, by hand to 6'	60	CY	0	0	29.65	1779	1,779	MMp28	MMp28
Remove conduit, torch	18	LF	1.06	19	4.95	89	108	MMp22	MMp22
Remove pipe insulation	6	LF	0	0	4.84	29	29		MMp236
Valve off and drain pipe	0.50	MH	0	0	30.30	15	15		MMp475
Repair HTW leak - Weld	1	Ea	1.95	2	16.05	16	18	MMp144	MMp144
Open valves - fill pipe	0.50	Ea	0	0	30.30	15	15		MMp475
Replace pipe insulation	6	LF	0	0	4.84	29	29		MMp236
Weld conduit, 24" Sch 40	3	Ea	35	105	289	867	972	MMp144	MMp144
Backfill trench, by hand	60	CY		0	12.85	771	771	MMp28	MMp28
Compact backfill, by hand	60	CY		0	4.66	280	280	MMp28	MMp28
Backfill trench, dozer	90	CY	0.95	86	0.32	29	115	MMp28	MMp28
Compact backfill, dozer	90	CY	1.37	123	0.41	37	160	MMp28	MMp28
Total Cost per Leak				464		4241	4,705		
Total Cost for All Leaks	2	Ea	464	928	4241	8482	9,410		
Subtotal Bare Costs				928		8482	\$9,410		
Retrofit Cost Factors			0%	0	0%	0	0	MMp6	MMp6
Subtotal				928		8482	9,410		
City Cost Index (Sav. GA)			0%	0	-44%	-3749	(3,749)	MMp533	MMp533
Subtotal				928		4733	5,661		
OH & Profit Markups			10%	93	53%	2508	2,601	MMp7	MMp475
Subtotal				1021		7241	8,262		
Sales Taxes			4.0%	41		NA	41	MMp476	
Subtotal				1062		7241	8,303		
Contingency			10%	106	10%	724	830	MEp6	MEp6
Total Construction Cost				1168		7965	9,133		
Design Fee				NA	0.0%	0	0		
SIOH				NA	0.0%	0	0		
Total Project Cost				1168		7965	\$9,133		

LEGEND:

MEp### 1996 Means Electrical Cost Data, page ###.
 MMp### 1996 Means Mechanical Cost Data, page ###.

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Without Leak Locating Equipment
ECO Number: 11

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 05/06/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H ₂ O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Loss Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$37120 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 96.0 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 96.0 \text{ MBtu/yr} / 0.68 = 141.2 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 141.2 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$189 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.07 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.01 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.01 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.01 \text{ kW}$$

$$\text{Electricity Use} = 0.01 \text{ kW} \times 8760 \text{ Hr/Yr} = 54 \text{ kWh/Yr}$$

$$\text{Electricity Cost} = 54 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$3 \text{ /Year}$$

Water Cost:

$$37120 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$21 \text{ /Year}$$

Total Utility Cost Savings:

Heating Fuel Cost	\$189 /Year
Pumping (Elec) Cost	\$3 /Year
Water Cost	\$21 /Year
<hr/> Total Savings	<hr/> \$213 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: With Leak Locating Equipment
ECO Number: 11

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 05/06/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H ₂ O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Loss Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$17300 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} = 44.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 44.8 \text{ MBtu/yr} / 0.68 = 65.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 65.8 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$88 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.03 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.003 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.003 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.003 \text{ kW}$$

$$\text{Electricity Use} = 0.003 \text{ kW} \times 8760 \text{ Hr/Yr} = 25 \text{ kWh/Yr}$$

$$\text{Electricity Cost} = 25 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$1 \text{ /Year}$$

Water Cost:

$$17300 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$10 \text{ /Year}$$

Total Utility Cost Savings:

Heating Fuel Cost	\$88 /Year
Pumping (Elec) Cost	\$1 /Year
Water Cost	\$10 /Year
<hr/>	
Total Savings	\$99 /Year

Fort Stewart - Central Energy Plant
 Filename: FS-VPDIS.WQ1
 12/15/95

Approximate Distance Between Valve Pits (1)

ZONE 1		ZONE 2N		ZONE 2S		ZONE 3		SEP ZONE		
PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	PIT#	LN.FT.	
CP-B1	200	CP-V1	150	V1-B1	700	CP-?	700	C1-V1	1500	(2)
B1-V4	1000	V1-V2	200	B1-V1	1500	?-1	800	V1-V2	100	(2)
V1-V2	600	V2-V3	350	V1-B2	300	?-2	400	V2-V3	1700	(2)
V2-V3	200	V3-V4	650	B2-B3	550	2-2A	400	V3-V4	450	(2)
V3-V4	350	V4-V5	600	B3-V1	250	2A-3	500	V4-V5	600	(2)
V4-V5	300	V5-V6	800	V1-V2	250	3-3A	400	V5-V6	500	(2)
V5-V6	550	V6-V7	800	V1-V3	350	3A-6	550	V6-SP	100	(2)
V6-V7	400	V2-V8	750	V3-V4	250	4-5	900	SP-V7	200	
V7-V8	600	V8-V9	300	V3-V6	300	5-6	650	V7-V8	150	
V8-V9	350			V4-V5	200	6-7	850	V8-V9	550	
V9-V10	350			V3-V7	650	7-8	950	V9-V10	650	
V10-V11	250			V7-V8	250	8-9	1000	V10-V11	800	
V11-V12	500			V8-V9	500	9-10	1000	V11-V12	650	
V12-V13	1000			V9-V10	200	10-11	900	V12-V13	800	
V13-V14	350			V9-V11	450	11-12	500			
V14-V15	400					12-13	950			
V15-V16	400					13-13A	750			
V16-V17	500					12-14	950			
V17-V18	800					14-15	200			
						15-16	250			
						16-16A	300			
						16A-17	200			
						17-18	200			
						18-19	100			
						19-20	150			
						20-22	200			
						21-22	100			
						22-23	350			
						15-24C	350			
						24C-24B	200			
						24B-24	200			
						24-24A	200			
						24A-25	150			
						24A-25A	300			
						25A-26	100			
						26-26A	200			
						26A-27	250			
						27-28	250			
TOTAL LN.FT.		9100	4600	6700		17400		8750		
MILES		1.7	0.9	1.3		3.3		1.7		8.8
MAX LNFT/VP		1000	800	1500		1000		1700		
AVG LNFT/VP		479	511	447		458		625		
MIN LNFT/VP		200	150	200		100		100		
NO. OF PITS (1)		19	9	15		38		14		95

- (1) There are other valve boxes and drain pits that are not shown on our HTW system map.
 (2) These pipes carry steam.

CONSTRUCTION COST ESTIMATE

Project: Purchase Leak Detection Equipment
Location: Fort Stewart, GA
Basis: Schematic Design
ECO No.: 11

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: W.T.Todd
Filename: EST-11.WQ1

[illegible]

LEGEND:

Vendor Price quote from telephone conversation with vendor.



Telephone Call Confirmation

Project Number 694 1331 002

Local LD. 800.327.2871 Placed B. Todd Rec'd Date 2-6-96

Conversed with Tom McGee of Fluid Conservation Systems
Cincinnati, OH

Regarding Purchase of leak locating equipment

The leak~~ing~~ locator is called a Correlator, and includes two sensors with transmitters. The model C-2000 is about 10 years old. The new models are:

MicroCorr Cub (made in UK) \$35,000 low end

Tri Corr - 2001 (made in USA) \$51,000 high end

Correlator has receiver; input pipe diameter, type and distance between valve contact locations; usually locates the leak within inches and it is uncovered on the first dig.


They also sell a survey tool that is hand held and can be used to ^{identify and} find the general area of the leak. The cost of the survey tool is about \$3,600.

They offer a training course that includes on site class room and field work for 4 1/2 days; cost ~ \$4,500

Distribution:-

Tom also recommended Consumers Applied Technologies out of Orlando to do leak detection work. Contact Keith Nelson at 407.382.0995. He is also familiar with USA group.

Figure 4.1-5
Fort Stewart HTW Make-up Water, 1995



022 | Earthwork

SITE WORK

022 200 | Excav./Backfill/Compact.

			CREW	DAILY OUTPUT	LABOR HOURS	UNIT	1996 BARE COSTS				TOTAL
							MAT.	LABOR	EQUIP.	TOTAL	INCL O&P
204	0500	Air tamp, add	A123	B-9	190	.211		4.25	.80	5.05	7.70
	0600	Vibrating plate, add	-110	A-1	60	.133		2.64	1	3.64	5.30
	0800	Compaction in 12" layers, hand tamp, add to above		1 Clab	34	.235		4.66		4.66	7.45
	0900	Roller compaction operator walking, add		B-10A	150	.080		1.90	.57	2.47	3.58
	1000	Air tamp, add		B-9	285	.140		2.84	.53	3.37	5.10
	1100	Vibrating plate, add		A-1	90	.089		1.76	.67	2.43	3.55
	1300	Dozer backfilling, bulk, up to 300' haul, no compaction		B-10B	1,200	.010		.24	.71	.95	1.15
	1400	Air tamped		B-11B	240	.067		1.52	4.46	5.98	7.30
	1600	Compacting backfill, 6" to 12" lifts, vibrating roller		B-10C	800	.015		.36	1.19	1.55	1.86
	1700	Sheepsfoot roller		B-10D	750	.016		.38	1.29	1.67	2.01
	1900	Dozer backfilling, trench, up to 300' haul, no compaction		B-10B	900	.013		.32	.95	1.27	1.53
	2000	Air tamped		B-11B	235	.068		1.55	4.56	6.11	7.40
	2200	Compacting backfill, 6" to 12" lifts, vibrating roller		B-10C	700	.017		.41	1.37	1.78	2.13
	2300	Sheepsfoot roller		B-10D	650	.018		.44	1.49	1.93	2.32
234	0010	DRILLING AND BLASTING Only, rock, open face, under 1500 C.Y.		B-47	225	.107	C.Y.	1.50	2.36	2.52	6.38
	0100	Over 1500 C.Y.		"	300	.080		1.50	1.77	1.89	5.16
	2200	Trenches, up to 1500 C.Y.		B-47	22	1.091		4.50	24	25.50	54
	2300	Over 1500 C.Y.		"	26	.923		4.29	20.50	22	46.79
250	0010	EXCAVATING, STRUCTURAL Hand, pits to 6' deep, sandy soil		1 Clab	8	1	C.Y.		19.80		19.80
	0100	Heavy soil or clay		"	4	2			39.50		39.50
	0300	Pits 6' to 12' deep, sandy soil		"	5	1.600			31.50		31.50
	0500	Heavy soil or clay		"	3	2.667			53		53
	0700	Pits 12' to 18' deep, sandy soil		"	4	2			39.50		39.50
	0900	Heavy soil or clay		"	2	4			79		79
	1500	For wet or muck hand excavation, add to above					%			50%	50%
254	0010	EXCAVATING, TRENCH or continuous footing, common earth	A123								
	0020	No sheeting or dewatering included	-110								
	0050	1' to 4' deep, 3/8 C.Y. tractor loader/backhoe		B-11C	150	.107	C.Y.	2.43	1.39	3.82	5.30
	0060	1/2 C.Y. tractor loader/backhoe		B-11M	200	.080		1.82	1.43	3.25	4.41
	0090	4' to 6' deep, 1/2 C.Y. tractor loader/backhoe		"	200	.080		1.82	1.43	3.25	4.41
	0100	5/8 C.Y. hydraulic backhoe		B-12Q	250	.064		1.56	1.58	3.14	4.12
	0110	3/4 C.Y. hydraulic backhoe		B-12F	300	.053		1.30	1.50	2.80	3.64
	0300	1/2 C.Y. hydraulic excavator, truck mounted		B-12J	200	.080		1.95	3.15	5.10	6.45
	0500	6' to 10' deep, 3/4 C.Y. hydraulic backhoe		B-12F	225	.071		1.73	2	3.73	4.86
	0600	1 C.Y. hydraulic excavator, truck mounted		B-12K	400	.040		.97	2.17	3.14	3.88
	0900	10' to 14' deep, 3/4 C.Y. hydraulic backhoe		B-12F	200	.080		1.95	2.25	4.20	5.45
	1000	1-1/2 C.Y. hydraulic backhoe		B-12B	540	.030		.72	1.32	2.04	2.56
	1300	14' to 20' deep, 1 C.Y. hydraulic backhoe		B-12A	320	.050		1.22	1.72	2.94	3.77
	1400	By hand with pick and shovel to 6' deep, light soil		1 Clab	8	1		19.80		19.80	31.50
	1500	Heavy soil		"	4	2		39.50		39.50	63
	1700	For tamping backfilled trenches, air tamp, add		A-1	100	.080		1.58	.60	2.18	3.19
	1900	Vibrating plate, add		"	90	.089		1.76	.67	2.43	3.55
	2100	Trim sides and bottom for concrete pours, common earth		"	600	.013	S.F.	.26	.10	.36	.53
	2300	Hardpan		"	180	.044		.88	.33	1.21	1.77
258	0010	EXCAVATING, UTILITY TRENCH Common earth									
	0050	Trenching with chain trencher, 12 H.P., operator walking									
	0100	4" wide trench, 12" deep		B-53	800	.010	L.F.	.25	.11	.36	.50
	0150	18" deep		"	750	.011		.26	.11	.37	.52
	0200	24" deep		"	700	.011		.28	.12	.40	.56
	0300	6" wide trench, 12" deep		"	650	.012		.30	.13	.43	.61
	0350	18" deep		"	600	.013		.33	.14	.47	.66
	0400	24" deep		"	550	.015		.36	.15	.51	.72
	0450	36" deep		"	450	.018		.44	.19	.63	.88
	0600	8" wide trench, 12" deep		"	475	.017		.42	.18	.60	.84

FCS

FLUID CONSERVATION SYSTEMS

TriCorr 2001

Leak Correlator



The TriCorr 2001 is an advanced, portable microprocessor system for pinpointing fluid leaks in pressurized pipe systems.

It is the most advanced correlator on the market but is simple to operate and can be easily used by a single operator.

FCS specially designed the TriCorr 2001 for public and private water utilities, industrial and commercial water systems, engineering and service firms, and utility contractors.



Typical Configuration

- ① Correlator console with rechargeable battery
- ② Two remote preamplifiers/radio links
- ③ Two high sensitivity sensors
- ④ 110 VAC battery charger
- ⑤ Stereo headphones
- ⑥ Cassette training tapes
- ⑦ Protective soft cases
- 12 VDC power cord/charger (not shown)
- Operations manual (not shown)

Additional Equipment

Sensor mounting kit
Hydrophones
Hydrophone attachment kit
Cable reels
Measuring wheel
Survey instrument
Pipe locator
Printer
Cassette recorder/player



Size/Weight

Length: 14 inches
Depth: 6 inches
Width: 13 inches
Weight: 14.5 lbs. (including soft cases and battery)

Power Supply

10V 2.5AH Battery

Warranty

12 months parts and labor

Specifications subject to change.

Features: Benefits

Tri-Correlation: simultaneous display of three correlation graphs simplifies evaluation of correlation results

Peak Suppression: eliminates interference on correlation graph

Fast Fourier Transform (F.F.T.) Filtering: provides real-time analysis and increased signal resolution

True Signal Display: provides real-time, visual leak signal verification

Signal-to-Noise Display: provides numerical and visual representation of correlation peaks

Signal Spectrum Display: focuses user toward potential leak frequencies via bar graph

Velocity Calculation: allows for accurate correlation if pipe material or diameter is unknown

Multiple Pipe Type Diversity: can correlate on up to 7 different pipe materials or diameters within the selected span


Trial Correlation: saves time/effort of correlating in insufficient leak signal situations

Rugged Construction: durable and effective in all field environments

Easy-to-use Software: easily used by all levels of personnel

Large High Visibility LCD: easy to read and interpret results

Large Button/Water-Resistant Keypad: can be used with gloves and in inclement weather



Looking for a way to expand your leak detection program? Upgrading equipment?

Customize your own deal by choosing one of these three great options:

Purchase the TriCorr 2001 Leak Correlator at \$51,500 and receive **FREE**:

- 3 Aqualogs for unmanned leak detection, and
- 1 laptop computer for downloading the data.

...save \$16,570

Purchase the TriCorr 2001 Leak Correlator at \$51,500 and receive **FREE**:

- 1 \$20 Leak Survey Tool
- 4.5-Day Training Course
- 1 Additional Year Warranty

...save \$10,400!

Or...**TRADE IT!**

We'll take **your** leak correlator (any make) as a trade-in, and give you \$8,585 towards the purchase of a brand new TriCorr 2001 system!

...save \$8,585

Call our sales department now at 800-531-5465 for information on this **limited time offer!**

offer expires 3/30/96

—The Water Accountability Specialists—
Fluid Conservation Systems Inc.
2001 Ford Circle Suite F
Milford, Ohio 45150
(800) 531-5465 (513) 831-9336 fax

A
HALMA GROUP
COMPANY

progress quickly and easily through the logical software programme, using the inbuilt push button keypad, to obtain fast accurate results.

The central unit of rigid polyurethane construction is easily portable, weighing only 3¹/₂ kg. Correlation results are displayed on the high contrast liquid crystal display, which is backlit for night time or poor visibility operation.

Filter and velocity settings are automatically allocated dependent on pipe type, diameter and other data entered. There is the option of manual filter choice, aided by audio monitoring using the studio quality headphones provided. Where pipe data is not available, velocity can be quickly and easily measured to ensure accuracy of results.

For a pipe run of mixed materials or diameter, the mixed material function allows data for different pipe sections to be entered. The system automatically compensates and chooses velocity and filter settings accordingly.

The zoom function reduces resolution errors by allowing detailed examination of specific sections of the correlator graphic. Results can be stored for later examination or printed on the portable thermal printer (available as an accessory).

• MICROCORR CUB TECHNICAL SPECIFICATION •

MicroCorr[®] Unit

Frequency response	37-5000 Hz
Filters: high pass	37,75,150,300,600 Hz
low pass	310,625,1250,2500,5000 Hz
Max time delay	1550 ms
Max theoretical range	2.1km (iron pipe) 750m (pvc pipe)
Resolution	±0.1m
Display type	Backlit LCD
Battery supply	12v lead acid
Battery life	15 hours
Mixed materials	3 sections
Printer	RS232 interface
Memory	66 correlations
Construction	Rigid polyurethane
Dimensions	330 x 230 x 145mm
Weight	3.65kg

Features

Battery level indication
Auto shutdown
Survey mode
Velocity measurement
Auto gain
Signal level display
Context related help
Language options
Download to PC
Real time clock/display

Transmitter Unit

Transmitter range	2000m
Level indication	Meter
Battery type	12v lead acid 2.3 Ah
Battery level indication	Test switch
Battery life	8 hours typical
Weight	2.2kg
Dimensions	140 x 165 x 300mm
Case construction	Rigid polyurethane

Features

Top mounted controls
Auto gain
Interchangeable battery



PALMER ENVIRONMENTAL

Ty Coch House, Llantarnam Park Way, Cwmbran, Gwent NP44 3AW, United Kingdom

Telephone (01633) 489479 Int +44 1633 489479

Telefax (01633) 877857 Int +44 1633 877857

A.3.11-21

—A—
**HALMA
GROUP
COMPANY**

ECO NUMBER 12

REDUCE BOILER AND HTW SYSTEM OPERATING PRESSURE

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-12

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-12 REDUCE BOILER AND HTW SYSTEM PRESSURE

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION A

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	0.	
B. SIOH	\$	0.	
C. DESIGN COST	\$	0.	
D. TOTAL COST (1A+1B+1C)	\$	0.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	0.	

***** No investment costs; Other items should be checked. *****

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	30244.	\$ 40527.	14.88	\$ 603041.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		30244.	\$ 40527.		\$ 603041.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	0.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	0.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 40527.

5. SIMPLE PAYBACK PERIOD (1G/4) .00 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 603041.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= *****
 (IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-12

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-12 REDUCE BOILER AND HTW SYSTEM PRESSURE

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION B

ANALYSIS DATE: 02-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	26657.	
B. SIOH	\$	1600.	
C. DESIGN COST	\$	1600.	
D. TOTAL COST (1A+1B+1C)	\$	29857.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	29857.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	53115.	\$ 71174.	14.88	\$ 1059071.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		53115.	\$ 71174.		\$ 1059071.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	0.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	0.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS \text{ ECONOMIC LIFE}))$ \$ 71174.

5. SIMPLE PAYBACK PERIOD (1G/4) .42 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 1059071.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 35.47
(IF < 1 PROJECT DOES NOT QUALIFY)

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-12

LCCID FY95 (92)

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-12 REDUCE BOILER AND HTW SYSTEM PRESSURE

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION C

ANALYSIS DATE: 08-14-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	26657.		
B. SIOH	\$	1600.		
C. DESIGN COST	\$	1600.		
D. TOTAL COST (1A+1B+1C)	\$	29857.		
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$		0.	
F. PUBLIC UTILITY COMPANY REBATE	\$		0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$			29857.

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	-26100.	\$ -114840.	18.57	\$ -2132579.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	110082.	\$ 147510.	14.88	\$ 2194947.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		83982.	\$ 32670.		\$ 62369.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$ -24600.
(1) DISCOUNT FACTOR (TABLE A)	14.88	
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$ -366048.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ -366048.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 8070.

5. SIMPLE PAYBACK PERIOD (1G/4) 3.70 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ -303680.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= -10.17
(IF < 1 PROJECT DOES NOT QUALIFY)

THIS PAGE BLANK

LIFE CYCLE COST ANALYSIS SUMMARY

STUDY: ECO-12X

ENERGY CONSERVATION INVESTMENT PROGRAM (ECIP)

LCCID FY95 (92)

INSTALLATION & LOCATION: FORT STEWART REGION NOS. 4 CENSUS: 3

PROJECT NO. & TITLE: ECO-12 REDUCE BOILER AND HTW SYSTEM PRESSURE

FISCAL YEAR 1995 DISCRETE PORTION NAME: OPTION B

ANALYSIS DATE: 02-15-96 ECONOMIC LIFE 20 YEARS PREPARED BY: W. TODD

1. INVESTMENT

A. CONSTRUCTION COST	\$	26657.	
B. SIOH	\$	1600.	
C. DESIGN COST	\$	1600.	
D. TOTAL COST (1A+1B+1C)	\$	29857.	
E. SALVAGE VALUE OF EXISTING EQUIPMENT	\$	0.	
F. PUBLIC UTILITY COMPANY REBATE	\$	0.	
G. TOTAL INVESTMENT (1D - 1E - 1F)	\$	29857.	

2. ENERGY SAVINGS (+) / COST (-)

DATE OF NISTIR 85-3273-X USED FOR DISCOUNT FACTORS OCT 1994

FUEL	UNIT COST \$/MBTU(1)	SAVINGS MBTU/YR(2)	ANNUAL \$ SAVINGS(3)	DISCOUNT FACTOR(4)	DISCOUNTED SAVINGS(5)
A. ELECT	\$ 13.74	0.	\$ 0.	15.08	\$ 0.
B. DIST	\$ 4.40	0.	\$ 0.	18.57	\$ 0.
C. RESID	\$.00	0.	\$ 0.	21.02	\$ 0.
D. NAT G	\$.00	0.	\$ 0.	18.58	\$ 0.
E. COAL	\$.00	0.	\$ 0.	16.83	\$ 0.
F. PPG	\$.00	0.	\$ 0.	17.38	\$ 0.
L. OTHER	\$ 1.34	22871.	\$ 30647.	14.88	\$ 456029.
M. DEMAND SAVINGS			\$ 0.	14.88	\$ 0.
N. TOTAL		22871.	\$ 30647.		\$ 456029.

3. NON ENERGY SAVINGS(+) / COST(-)

A. ANNUAL RECURRING (+/-)		\$	0.
(1) DISCOUNT FACTOR (TABLE A)	14.88		
(2) DISCOUNTED SAVING/COST (3A X 3A1)		\$	0.

B. NON RECURRING SAVINGS(+) / COSTS(-)

ITEM	SAVINGS(+) COST(-) (1)	YR OC (2)	DISCNT FACTR (3)	DISCOUNTED SAVINGS(+)/ COST(-)(4)
d. TOTAL	\$ 0.			0.

C. TOTAL NON ENERGY DISCOUNTED SAVINGS(+)/COST(-)(3A2+3Bd4)\$ 0.

4. FIRST YEAR DOLLAR SAVINGS $2N3+3A+(3Bd1/(YRS\ ECONOMIC\ LIFE))$ \$ 30647.

5. SIMPLE PAYBACK PERIOD (1G/4) .97 YEARS

6. TOTAL NET DISCOUNTED SAVINGS (2N5+3C) \$ 456029.

7. SAVINGS TO INVESTMENT RATIO (SIR)=(6 / 1G)= 15.27
(IF < 1 PROJECT DOES NOT QUALIFY)



SUBJECT FORT STEWART
REDUCE OPERATING PRESSURE
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF _____
DATE 2-13-96
DATE _____

ECO-12 REDUCE HTW PRESSURE

OPTION A. REDUCE PRESSURE FROM 180 TO 100 PSIG

SATURATION TEMPERATURE FOR 180 PSIG = 379°F

" " " " 100 " = 338°F

TOTAL LINEAL FT OF PIPE = 121,737 FT

LINEAL HEAT LOSS GOOD PIPE = 55 BTU/FT (see attached)

" " " " BAD PIPE = 275 BTU/FT (" ")

ASSUME 1/2 OF THE PIPE IS GOOD & 1/2 IS BAD.

SEP LINEAL FT OF PIPE = 17,500 FT

ENERGY SAVED IN HTW DISTRIBUTION SYSTEM

$$Q_{CEP} = \left(1 - \frac{(338-60)}{(379-60)}\right) \times (121,737 - 17,500) \text{ FT} \times \frac{(275+55)}{2} \text{ BTU/HR-FT} \times 8760 \text{ H/YR}$$

1 EG BTU/MBTU

$$= 19,364 \text{ MBTU/YR}$$

$$Q_{SEP} = \left(1 - \frac{(338-60)}{(379-60)}\right) \times 17,500 \text{ FT} \times \frac{275-55}{2} \text{ BTU/HR-FT} \times 135 \text{ D/YR} \times 24 \text{ H/D}$$

$$= 1202 \text{ MBTU/YR}$$

$$Q_{TOT} = \frac{Q_{CEP} + Q_{SEP}}{0.68}$$

NOTE: ASSUME 68% BOILER EFF.

$$= \frac{(19,364 + 1,202) \text{ MBTU/YR}}{0.68} = \frac{20,566}{0.68} \text{ MBTU/YR}$$

$$= \boxed{30,244 \text{ MBTU/YR}}$$

NOTE: THIS OPTION CAN BE IMPLEMENTED IMMEDIATELY BY
RESETTING THE CEP STEAM PRESSURE MASTER CONTROL
SET POINT TO 100 PSIG.

ANNUAL SAVINGS

$$\begin{aligned} \$ &= 30,244 \text{ MBTU/YR} \times 1.34 \text{ \$/MBTU} \\ &= 40,527 \text{ \$/YR} \end{aligned}$$

A.3.12-7



SUBJECT FORT STEWART
REDUCE OP. PRESSURE
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF _____
DATE 2-13-96
DATE _____

ECO 12 CONT. REDUCE HTW PRESSURE

OPTION B: REDUCE PRESSURE TO 60 PSIG

SATURATION TEMPERATURE FOR 60 PSIG = 307 °F

NOTE: 60 PSIG WAS CHOSEN BECAUSE THE AUTOCLAVES
IN THE HOSPITAL REQUIRE 50-80 PSIG STEAM.

ENERGY SAVED IN DISTRIBUTION SYSTEM

$$Q_{CEP} = \frac{\left(1 - \frac{(307-60)}{(379-60)}\right) \times (121737-17500) \text{ ft} \times \frac{(275+55)}{2} \text{ BTU/HR.FT} \times 8760 \text{ HR/YR}}{1 \text{ EG BTU/MBTU}}$$

$$= 34,006 \text{ MBTU/YR.}$$

$$Q_{SEP} = \frac{\left(1 - \frac{(307-60)}{(379-60)}\right) \times (17500) \text{ ft} \times \frac{(275+55)}{2} \text{ BTU/HR.FT} \times 135 \text{ D/YR} \times 24 \text{ H/D}}{1 \text{ EG BTU/MBTU}}$$

$$= 2112 \text{ MBTU/YR.}$$

$$Q_{TOT} = \frac{Q_{CEP} + Q_{SEP}}{0.68}$$

$$= \frac{(34006 + 2112)}{0.68} \text{ MBTU/YR}$$

$$= \boxed{53,115 \text{ MBTU/YR}}$$

ANNUAL COST SAVINGS

$$\text{SAVINGS} = 53,115 \text{ MBTU/YR} \times 1.34 \text{ \$/MBTU}$$

$$= 71,174 \text{ \$/YR}$$



SUBJECT FORT STEWART
Reduce Op. Pressure
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET 3 OF _____
DATE 2-13-96
DATE _____

ECO 12 CONT. REDUCE HTW PRESSURE

OPTION B (CONTINUED)

THE BOILER PRESSURE MUST REMAIN AT APPROXIMATELY 100 PSIG TO SUPPLY ITS OWN SOOT BLOWING PRESSURE.

A PRESSURE REDUCING STATION MUST BE PROVIDED TO REDUCE THE STEAM PRESSURE FROM 100 PSIG TO 60 PSIG. THE PRESSURE REDUCING STATION INCLUDES:

- 1 PRV W/ PNEUMATIC ACTUATOR
- 1 PRESSURE TRANSMITTER
- 1 PRESSURE CONTROLLER W/ SET POINT ADJUSTMENT.

INSTALLATIONS COST

SEE ESTIMATE SHEET.



SUBJECT FORT STEWART
Reduce Op. Pressure
DESIGNER G. Fallon
CHECKER _____

AEP NO 6941331002
SHEET 4 OF _____
DATE 2-13-96
DATE _____

ECO 12 CONT. REDUCE HTW PRESSURE

OPTION C: REDUCE PRESSURE TO 30 PSIG. THE STEAM KETTLES IN THE DINING FACILITIES OPERATE ON 30 PSIG STEAM. AN ALTERNATE HEATING TECHNIQUE WILL HAVE TO BE INSTALLED IN THE HOSPITAL TO SUPPLY THE AUTOCLAVES.

ENERGY SAVED IN DISTRIBUTION SYSTEM

$$Q_{CEP} = \frac{\left(1 - \frac{(274-60)}{(379-60)}\right) \times (121737 - 17500) \text{ ft} \times \frac{(275+55)}{2} \text{ BTU/ft}^2\text{HR} \times 8760 \text{ hr/yr}}{1.6 \text{ BTU/MBTU}}$$

$$= 49,592 \text{ MBTU/yr}$$

$$Q_{SEP} = \frac{\left(1 - \frac{(274-60)}{(379-60)}\right) \times (17500) \text{ ft} \times \frac{(275+55)}{2} \text{ BTU/ft}^2\text{HR} \times 135 \text{ D/yr} \times 24 \text{ H/D}}{1.6 \text{ BTU/MBTU}}$$

$$= 3079 \text{ MBTU/yr}$$

$$Q_{TOT} = Q_{CEP} + Q_{SEP}$$

$$= \frac{(49,592 + 3079) \text{ MBTU/yr}}{0.68}$$

$$= \underline{77,457 \text{ MBTU/yr}}$$

ANNUAL COST SAVINGS FROM DISTRIBUTION SYSTEM

$$\text{SAVINGS} = 77457 \text{ MBTU/yr} \times 1.34 \text{ \$/MBTU}$$

$$= 103,793 \text{ \$/yr.}$$

ENERGY REQUIRED IN HOSPITAL

ASSUME 5 AUTOCLAVES @ 60 PSIG, 1000 #/HR, 12 H/D
365 D/yr 85% BOILER EFF.

RS&H

SUBJECT FORT STEWART
Reduce Op. Pressure
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET 5 OF _____
DATE 2-13-96
DATE _____

ECO - 12 CONT. REDUCE HTW PRESSURE

OPTION C: (CONTINUED)

$$Q = \frac{5 \times 1000 \text{ #/HR} \times (1181 - (200 - 32)) \times 4380 \text{ H/yr}}{0.85 \times 116 \text{ B/MB}} = \frac{22185 \text{ MBtu/yr}}{0.85}$$
$$= \underline{26,100 \text{ MBtu/yr}} \text{ Additional Fuel Oil}$$

ANNUAL COST

$$\text{COST} = 26100 \text{ MBtu/yr} \times (4.40 - 1.34/0.68) \text{ \$/MBtu}$$
$$= \$63,408/\text{yr}$$

TOTAL ENERGY SAVINGS (INCREASE)

$$\text{HTG. FUEL} = 77457 \text{ MBtu/yr} + \frac{22185}{0.68} \text{ MBtu/yr} = \boxed{110082 \frac{\text{MBtu}}{\text{yr}}}$$

$$\text{FUEL OIL} = \boxed{(26,100) \text{ MBtu/yr.}}$$

NET COST SAVINGS

$$S_c = \$103,793/\text{yr} - \$63,408/\text{yr.}$$
$$= \$40385/\text{yr}$$



SUBJECT Fort Stewart HTW
Boiler O+m Costs
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET _____ OF _____
DATE 8-13-96
DATE _____

HOSPITAL BOILER O&M COSTS:

IF THE HOSPITAL BOILERS ARE OPERATED, THEY WILL REQUIRE AN OPERATOR / MAINTENANCE PERSON TO TEND AND REPAIR THEM. ASSUME THE TIME REQUIRED FOR O&M AVERAGES ABOUT $1\frac{1}{2}$ HOUR PER SHIFT, 365 DAYS PER YEAR.

$$\text{O\&M TIME} = 1.5 \text{ HR/SHIFT} \times 3 \text{ SHIFT/DAY} \times 365 \text{ DAY/YR} \approx 1640 \text{ HR/YR}$$

USING A RATE OF \$15 PER HOUR, THE ANNUAL O&M COSTS ARE:

$$\text{O\&M \$} = 1640 \text{ HR/YR} \times \$15/\text{HR} = \underline{\underline{\$24,600/\text{YR}}}$$



SUBJECT FORT STEWART
Reduce Op. Pressure
DESIGNER G. Fallon
CHECKER _____

AEP NO 694 1331 002
SHEET 7 OF _____
DATE 2-13-96
DATE _____

CURRENT PIPING ENERGY LOSS

$$Q_{CEP} = (121737 - 17500) \text{ ft} \times (275 + 55) / 2 \text{ BTU/HR} \cdot \text{ft} \times 8760 \\ 104237 \times 165 \times 8760 \\ = 150,664 \text{ MBTU/yr}$$

$$Q_{SEP} = (17500) \text{ ft} \times (275 + 55) / 2 \text{ BTU/HR} \cdot \text{ft} \times 135 \times 24 \\ = 9355 \text{ MBTU/yr}$$

$$Q_{TOT} = 150,664 \text{ MBTU/yr} + 9355 \text{ MBTU/yr} = 160,019 \text{ MBTU/yr}$$

$$\text{Current fuel use} = 160,019 \frac{\text{MBTU}}{\text{yr}} \div 0.68 = \underline{235,322 \frac{\text{MBTU}}{\text{yr}}}$$



SUBJECT FORT STEWART
DESIGNER W.T. TODD
CHECKER _____

AEP NO 694-1331-002
SHEET _____ OF _____
DATE 2-19-96
DATE _____

OPERATE HTW SYSTEM AT LOWER PRESSURES

AFFECT ON OTHER ECO'S

<u>OP. PRESSURE</u>	<u>HTW TEMP.</u>	<u>ΔT (1)</u>	<u>HEAT LOSS (2)</u>
180 PSIG	380 °F	310 °F	258.7 $\frac{\text{MBtu}}{\text{YR}}$
100 PSIG	238 °F	268 °F	223.6 $\frac{\text{MBtu}}{\text{YR}}$
60 PSIG	307 °F	237 °F	197.8 $\frac{\text{MBtu}}{\text{YR}}$

(1) Based on HTW make-up water temperature of 70 °F.

(2) See spreadsheet calculations on following 3 pages. Loss is for fictitious loss of 100,000 Gal/year.

All ECO's that reduce the HTW losses will be affected by operation at lower pressures. The energy savings for these ECO's will be reduced by the following amounts:

180 PSIG \rightarrow 100 PSIG :

$$\% \text{ Change} = \frac{257.8 - 223.6}{257.8} \Rightarrow \underline{13.57 \%}$$

100 PSIG \rightarrow 60 PSIG :

$$\% \text{ Change} = \frac{223.6 - 197.8}{223.6} \Rightarrow \underline{11.54 \%}$$

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: Existing Conditions
ECO Number: All

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/19/96

Assumptions:

1. HTW temperature	380 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Loss Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$\begin{aligned} 100000 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 310 \text{ }^\circ\text{F} &= 258.7 \text{ MBtu/Yr} \\ \text{Heating Fuel Use} &= 258.7 \text{ MBtu/yr} / 0.68 = 380.4 \text{ MBtu/Yr} \\ \text{Heating Fuel Cost} &= 380.4 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$510 \text{ /Year} \end{aligned}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.19 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.02 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\begin{aligned} \text{Electric Demand} &= 0.02 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.02 \text{ kW} \\ \text{Electricity Use} &= 0.02 \text{ kW} \times 8760 \text{ Hr/Yr} = 145 \text{ kWh/Yr} \\ \text{Electricity Cost} &= 145 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$7 \text{ /Year} \end{aligned}$$

Water Cost:

$$100000 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$56 \text{ /Year}$$

Total Utility Cost Savings:

Heating Fuel Cost	\$510 /Year
Pumping (Elec) Cost	\$7 /Year
Water Cost	\$56 /Year
<hr/> Total Savings	<hr/> \$573 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: With ECO-12 Option A
ECO Number: All

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/19/96

Assumptions:

1. HTW temperature	338 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Loss Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$100000 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 268 \text{ }^\circ\text{F} = 223.6 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 223.6 \text{ MBtu/yr} / 0.68 = 328.9 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 328.9 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$441 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.19 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.02 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.02 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.02 \text{ kW}$$

$$\text{Electricity Use} = 0.02 \text{ kW} \times 8760 \text{ Hr/Yr} = 145 \text{ kWh/Yr}$$

$$\text{Electricity Cost} = 145 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$7 \text{ /Year}$$

Water Cost:

$$100000 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$56 \text{ /Year}$$

Total Utility Cost Savings:

Heating Fuel Cost	\$441 /Year
Pumping (Elec) Cost	\$7 /Year
Water Cost	\$56 /Year
Total Savings	\$504 /Year

Location: Fort Stewart, GA
AEP Number: 694-1331-002
Project: With ECO-12 Option B
ECO Number: All

Reynolds, Smith and Hills, Inc.
Designer: W. T. Todd
Date: 02/19/96

Assumptions:

1. HTW temperature	307 °F
2. Make-up water temperature	70 °F
3. Boiler efficiency	68%
4. Pump head (from record drawings)	300 Ft H2O
5. Pump efficiency (from record drawings)	72%
6. Motor efficiency	90%
7. Average heating fuel cost	\$1.34 /MBtu
8. Electricity cost	\$0.0469 /kWh
9. Water cost	\$0.5562 /kGallons

Energy Loss Calculations:

Energy Use = flow rate x specific heat x temperature difference

$$100000 \text{ Gal/Yr} \times 8.345 \text{ lb/gal} \times 1 \text{ Btu/lb}^\circ\text{F} \times 237 \text{ }^\circ\text{F} = 197.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Use} = 197.8 \text{ MBtu/yr} / 0.68 = 290.8 \text{ MBtu/Yr}$$

$$\text{Heating Fuel Cost} = 290.8 \text{ MBtu/yr} \times \$1.34 \text{ /MBtu} = \$390 \text{ /Year}$$

Pumping Cost:

Pump BHP = (GPM x Feet Head) / (3960 x Pump Efficiency)

$$\text{BHP} = \frac{0.19 \text{ GPM} \times 300 \text{ Ft Head}}{3960 \times 0.72} = 0.02 \text{ BHP}$$

Energy Use = (BHP / Motor Efficiency) x 0.746 kW/HP x 8760 Hr/Yr

$$\text{Electric Demand} = 0.02 \text{ BHP} / 0.90 \times 0.746 \text{ kW/HP} = 0.02 \text{ kW}$$

$$\text{Electricity Use} = 0.02 \text{ kW} \times 8760 \text{ Hr/Yr} = 145 \text{ kWh/Yr}$$

$$\text{Electricity Cost} = 145 \text{ kWh/Yr} \times \$0.0469 \text{ /kWh} = \$7 \text{ /Year}$$

Water Cost:

$$100000 \text{ Gal/Yr} \times \$0.5562 \text{ /kGal} = \$56 \text{ /Year}$$

Total Utility Cost Savings:

Heating Fuel Cost	\$390 /Year
Pumping (Elec) Cost	\$7 /Year
Water Cost	\$56 /Year
<hr/>	
Total Savings	\$453 /Year

RS&H No.: 694-1331-002
Date: 02/14/96
Estimator: G.W. Fallon
Filename: EST-12.WQ1

A.3.12-18

FISHER-ROSEMOUNT

Key Controls Inc.
Jacksonville Branch
1409 Kingsley Ave. Suite 7B
Orange Park, Florida 32073-4532
Tel 1 (904) 269-5455
Fax 1 (904) 269-5446

February 13, 1996

Reynolds, Smith & Hills Inc.
4651 Salisbury Rd.
Jacksonville, FL 32216

Attn: George Fowler

RE: Budgetary Proposal Steam Pressure Control Valve; Key Controls' Quotation
#96-32080

Dear Mr. Fowler:

Thank you for your inquiry. As per your conversations with Wes King, we are pleased to quote budgetary pricing on the following Fisher Controls' products.

Item 1 Qty. 1

8" x 6" Fisher Type EWD globe control valve. ANSI Class 300# carbon steel body, 416 SST seat ring, 17-4PH SST plug, 416 SST Whisper III cage. Operated by a Fisher Type 471-16, size 60, pneumatic double-acting piston actuator, and Fisher Type 3570 pneumatic valve positioner. 60 psig actuator supply. 3-15 psig positioner input. Increasing signal to open. An external fail-safe device would be required to achieve failure for this valve. Also includes Fisher Type 4195KB, proportional-plus reset pneumatic controller. 300 psig bourdon tube element. With 2" pipestand mounting.

UNIT PRICE = \$ 22,233.30

ESTIMATED DELIVERY = 10-12 WKS ARO

Pricing for this estimate is firm for 30 days from today's date, and is quote FOB shipping point, with surface freight allowed to jobsite.

Please find enclosed a control valve specification sheet, detailing valve construction and selected service conditions. If you have any further questions, please contact Tom Glaspie or Wes King at your convenience.

Sincerely yours,


Wes King

CONF-8406132--2

NOTICE

PORTIONS OF THIS REPORT ARE ILLEGIBLE. It
has been reproduced from the best available
copy to permit the broadest possible avail-
ability.

ANALYSIS OF A SMALL DISTRICT STEAM SYSTEM AT
FT. McCLELLAN, ALABAMA

Gerald D. Pine and Michael A. Karnitz

CONF-8406132

DE84 014051

Energy Division
Oak Ridge National Laboratory*
Oak Ridge, Tennessee 37831

615 576-5454

574-5150

For presentation at the
75th Annual Conference of the International
District Heating Association
Mount Washington, New Hampshire

June 17-20, 1984

MASTER

By acceptance of this article, the
publisher or recipient acknowledges
the U.S. Government's right to
retain a nonexclusive, royalty-free
license in and to any copyright
covering the article.

* Research sponsored by the U. S. Army, Construction Engineering
Research Laboratory, under Interagency Agreement Number 40-1361-83, Army
Number CERL-83-080, operated by Martin Marietta Energy Systems, Inc.,
under Contract No. DE-AC05-84OR21400 with the U.S. Department of Energy.

DISTRIBUTION OF THIS DOCUMENT IS UNLIMITED

A.3.12-21

ps

Of the total steam produced, we estimate that approximately 95% enters the steam distribution system. The remaining 5% is used within the boiler plants to power auxiliaries. This amounts to some 570 lb/hr on the average or 5.0 million lb/yr. Then approximately 96 million lb/yr enters the distribution system.

5. CAUSES FOR HEAT LOSS FROM BURIED PIPE

In order to minimize heat losses from steam and condensate pipe lines, the lines are usually insulated. Sometimes the pipes may run above ground but more commonly, the pipes are buried from two to six feet below the surface. If the insulation is intact and dry, the ground helps to insulate the pipe from cold temperatures in the winter and to reduce the heat losses. In this section, we present estimates of the heat losses for well insulated pipes as well as for pipes with deteriorated insulation and under various failure conditions.

Heat Loss From Dry, Insulated, Buried Pipes. Heat losses have been calculated for varied soil conditions and various types of insulation by King et al. [3]. For the example of a six-inch steam line at 325°F with four inches of calcium silicate insulation in clay of average moisture and a soil temperature of 50°F, the rate of heat loss would be approximately 35 Btu/hour per linear foot of pipe. For the Ft. McClellan system with a steam temperature of 338°F and a ground temperature of 80°F, the loss rate would be about 52 Btu/hr-ft. ←

Heat Loss From Bare Pipes in Air. The simplest case to consider is a bare pipe exposed to ambient air on a dry, still day. For this case, the two major heat loss mechanisms are natural convection and radiation. We consider the case of a six-inch pipe with 338°F steam and ambient air at 150°F (a typical temperature inside a dry vault, where much of the bare pipe is found). The estimated loss due to natural convection under these conditions is about 350 Btu/hour per foot of pipe. Kreith [4] in Table 5.1 gives a value of emissivity of 0.8 for oxidized steel pipe. For the same pipe, the estimated radiation loss is approximately 570 Btu/hr-ft. The total loss per foot of bare pipe under these circumstances is then 920 Btu/hr-ft.

Buried Pipes With Entrapped Moisture and Deteriorated Insulation. Observations of actual buried steam lines indicates that the heat losses are substantially higher than the theoretical losses. Consideration of the magnitudes of the observed losses suggests that the pipe is behaving as though there were no insulation, and that the pipe is in direct contact with the surrounding soil. The most likely physical explanation is that the conductivity has been greatly enhanced by the deterioration of the insulation from the combined effects of heat and moisture that gets into the system by steam leaks or the intrusion of ground water. Entrapped moisture could be boiling near the surface of the pipe and condensing on the jacket, or subcooled boiling and the formation of a thermal convection loop in water filling the space between the pipe and jacket could be occurring. Both these processes produce extremely high heat transfer rates compared to the rate through dry insulation. If it is assumed that the conductivity of the insulation is infinite, the model of King et al. yields a heat transfer factor of about 1.8 Btu/hr-°F per foot of six-inch diameter pipe. For the six-inch pipe at 330°F and a 80°F ground temperature, the rate of heat loss per foot of pipe would be 460 Btu/hr-ft. This compares with the observed value of about 275 Btu/hr-ft. ←

Heat Loss From Flooding of Vaults. A commonly observed failure of steam lines is the failure of sump pumps in valve pits and the subsequent covering of the steam pipe with water. The source of the water can be either condensate from steam traps, which collects in the vault and causes flooding when sump pumps fail, or intrusion of ground water into the pits through cracks in the pit wall or around pipes that penetrate the pit walls. Water in the vaults is commonly heated to temperatures that are rather hot; we assume here that the water in the vault is heated to 150°F. The estimated rate of heat loss from a bare, six-inch steam pipe carrying 338°F steam and covered by 150°F water is 50,000 Btu/hr-ft. (This estimate could be higher, perhaps as high as 150,000 Btu/hr-ft depending on the assumed heat transfer mechanism.) Notice that the loss is nearly sixty times as large as the loss from dry, bare pipe. Perhaps even more interesting, the rate of heat loss would be 190 times greater than the

A.4 HTW LOSS CALCULATIONS

Fort Stewart - Measured/Estimated HTW Leaks
Filename: F-MAKEUP.WB2

WATER LOSS ESTIMATE		
ITEM	GPD	GPM
1) Boiler & Cascade Blowdown	1440	1.00
2) Sootblowing - Boiler No. 4	468	0.33
3) CEP - Miscellaneous Leaks	302	0.21
4) CEP - No. 4 Boiler Pipe & Fitting	323	0.22
5) SEP - Miscellaneous Leaks	336	0.23
6) Valve Pit Leaks - Valves & Fitting	1398	0.97
7) Mechanical Equip. Room Leaks	1260	0.88
8) Heating Equip./SEP Losses (1)	1034	0.72
9) SEP Start-up Losses (1)	158	0.11
10) Repaired HTW Piping Leaks (1)	55	0.04
Subtotal Identified Losses (2)	6774	4.71
Average 1995 Make-up Water Use	9173	6.37
- Total Losses Identified	6774	4.71
Estimated HTW Piping Leaks (3)	2399	1.66
(1) Losses obtained from the HTW make-up data, could not be visually verified during survey.		
(2) Some leaks may have been repaired or new leaks may have formed since the survey.		
(3) Other leaks include HVAC equipment, hot water generators, equipment repair, etc.		

PIE CHART VALUES

Blowdown & Soot Blowing	1908	1.33	21%
CEP/SEP/VP/ME Rm Leaks	3619	2.51	39%
Other Identified Losses	1247	0.87	14%
HTW Piping Leaks	2399	1.66	26%
			100%

BAR CHART VALUES

	1993	1994	1995
Blowdown & Soot Blowing	1908	1908	1908
Valve & Equip. Leaks	3619	3619	3619
Other Losses	1247	1247	1247
HTW Piping Leaks	6072	7682	2399

Test Procedure

Objective

To determine the hot water system leaks external to the Steam Plant

System Description

The hot water heating and distribution system consists of three gas/oil fired package boilers, one stoker fired wood boiler, three (3) cascade water heaters and circulating pumps. Boiler steam is condensed in the cascade heaters warming the water. The hot water is circulated facility wide in an underground distribution system supplying the heat for various needs including domestic hot water heating for kitchen, bathroom and laundry use, steam for cooking. Space heating is also provided during the winter months. Closed heat exchangers at each use point remove heat from the water. The slightly cooled water is returned to the steam plant for re-heating. The hot water distribution and return system is a closed system. With all valves closed any required make-up water would be due to leaks.

The heated water from the cascade heaters is used for boiler feedwater. The known system losses are the result of steam soot blowing (primarily on the wood fired boiler) and boiler blowdown along with scattered steam leaks typical of such a facility.

Procedure

Fill the system (no. 1 heater) to the desired level. Note the time and the make-up water totalizer reading. Operate the facility normally for 8 hours, except:

- do not operate the steam soot blowers.
- do not blow down the boilers.
- do not blow down the heaters.
- do not deliberately allow water or steam losses from any source.

Keep the power plant as "tight" as possible. Keep heater water levels within acceptable limits. Near the end of the 8 hour period fill the heaters to the starting level, record the time and the makeup water totalizer reading.

Results

The amount of make-up water used during the test should be theoretically equal the total system losses during the test. Since the system losses in the steam plant are minimized, the make-up water consumed is equal to system leaks outside the steam plant.

Leak Test Results

The results of the enclosed leak test procedure yielded a loss of 1787 gallons in an 8 hour period (223 gal/hr, 3.72 gpm, 5361 gpd). This loss was attributed to hot water distribution system leaks outside of the steam plant. Summing these losses with those from sootblowing and blowdown estimates above yields a daily make-up flow of 6045 gallons (5361+468+216). More importantly, however the losses from sootblowing and boiler blow down are shown to be a small part (11.3%) of the total system losses.

CALCULATE % LOSSES

Fort Stewart - Central Energy Plant
 Estimate of HTW System Losses
 Filename: F-HTW-CP.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Ft w/loops	Pipe Vol. (CF)	Pipe Vol. (Gal)
ZONE 1					
HTWS	All (main)	8	1485	518.4	3880
HTWR	All (main)	8	1485	518.4	3880
HTWS	All (main)	8	2200	767.9	5750
HTWR	All (main)	8	2200	767.9	5750
HTWS	All (main)	6	220	43.2	320
HTWR	All (main)	6	220	43.2	320
HTWS	All (main)	6	2035	399.6	2990
HTWR	All (main)	6	2035	399.6	2990
HTWS	All (main)	6	825	162.0	1210
HTWR	All (main)	6	825	162.0	1210
HTWS	All (main)	4	825	72.0	540
HTWR	All (main)	4	825	72.0	540
HTWS	All (main)	2	880	19.2	140
HTWR	All (main)	2	880	19.2	140
HTWS	All (main)	5	385	52.5	390
HTWR	All (main)	5	385	52.5	390
HTWS	All (main)	4	880	76.8	570
HTWR	All (main)	4	880	76.8	570
HTWS	All (main)	2.5	440	15.0	110
HTWR	All (main)	2.5	440	15.0	110
Branch Piping (assume 5% of mains)					1590
Bldgs	72	1	100	0.5	290
SUBTOTAL ZONE 1			20350		33680
ZONE 2					
HTWS	All (main)	6	4070	799.1	5980
HTWR	All (main)	6	4070	799.1	5980
HTWS	All (main)	5	1375	187.5	1400
HTWR	All (main)	5	1375	187.5	1400
HTWS	All (main)	4	550	48.0	360
HTWR	All (main)	4	550	48.0	360
HTWS	All (main)	2	4510	98.4	740
HTWR	All (main)	2	4510	98.4	740
HTWS	All (main)	1.5	330	4.0	30
HTWR	All (main)	1.5	330	4.0	30
HTWS	All (main)	2.5	550	18.7	140
HTWR	All (main)	2.5	550	18.7	140
HTWS	All (main)	2.25	990	27.3	200
HTWR	All (main)	2.25	990	27.3	200
HTWS	All (main)	1.25	1980	16.9	130
HTWR	All (main)	1.25	1980	16.9	130
HTWS	All (main)	2	770	16.8	130
HTWR	All (main)	2	770	16.8	130
Branch Piping (assume 5% of mains)					910
Bldgs	34	1	100	0.5	140
SUBTOTAL ZONE 2			30250		19270

CALCULATE % LOSSES

Fort Stewart - Central Energy Plant
 Estimate of HTW System Losses
 Filename: F-HTW-CP.WQ1

ZONE 3

HTWS	All (main)	10	5225	2849.8	21320
HTWR	All (main)	10	5225	2849.8	21320
HTWS	All (main)	10	3850	2099.8	15710
HTWR	All (main)	10	3850	2099.8	15710
HTWS	All (main)	6	1980	388.8	2910
HTWR	All (main)	6	1980	388.8	2910
HTWS	All (main)	5	990	135.0	1010
HTWR	All (main)	5	990	135.0	1010
HTWS	All (main)	8	605	211.2	1580
HTWR	All (main)	8	605	211.2	1580
HTWS	All (main)	6	605	118.8	890
HTWR	All (main)	6	605	118.8	890
HTWS	All (main)	4	1100	96.0	720
HTWR	All (main)	4	1100	96.0	720
HTWS	All (main)	2	880	19.2	140
HTWR	All (main)	2	880	19.2	140
HTWS	All (main)	4	1650	144.0	1080
HTWR	All (main)	4	1650	144.0	1080
Branch Piping (assume 5% of mains)					4540
Bldgs	27	1	100	0.5	110
SUBTOTAL ZONE 3			33770		95370

SEP ZONE

HTWR	All (main)	4	5390	470.4	3520
HTWR	All (main)	2	5390	117.6	880
STMS	All (main)	10	5390	2939.8	150
HTWS	All (main)	8	440	153.6	1150
HTWR	All (main)	8	440	153.6	1150
HTWS	All (main)	4	2860	249.6	1870
HTWR	All (main)	4	2860	249.6	1870
HTWS	All (main)	3	880	43.2	320
HTWR	All (main)	3	880	43.2	320
HTWS	All (main)	2.5	1760	60.0	450
HTWR	All (main)	2.5	1760	60.0	450
HTWS	All (main)	2	770	16.8	130
HTWR	All (main)	2	770	16.8	130
HTWS	All (main)	2	990	21.6	160
HTWR	All (main)	2	990	21.6	160
Branch Piping (assume 5% of mains)					640
Bldgs	5	1	100	0.5	20
SUBTOTAL SEP ZONE			31570		13370

Cascade Htrs, Expansion Tanks, etc., estimated 14500

Total Estimated System Volume 176190 Gallons

CALCULATE % LOSSES

Fort Stewart - Central Energy Plant
Estimate of HTW System Losses
Filename: F-HTW-CP.WQ1

CALCULATION OF PERCENT HTW LOSSES

Typical Closed Loop Piping Systems

0.5% of total volume lost per day = 881 Gal/Day

881 gal/day x 30.4 day/mo = 26796 Gal/Mo.

881 gpd / 1440 min/day = 0.61 Gal/Min

Fort Stewart HTW Piping System

2203 gal/day x 30.4 day/mo = 67014 Gal/Mo.

2203 gpd / 1440 min/day = 1.53 Gal/Min

Percent of total volume lost per day = 1.3%

Blowdown

Blowing down the boiler is required to control the boiler water chemistry. Excessive blowdown is wasteful. Insufficient blowdown can severely damage the boiler pressure parts over time. Generally, the boilers should be blown down as little as possible while keeping the boiler water chemistry under control. The blowdown procedures should be reviewed. Blowing down the lower headers every shift is generally regarded as excessive.

The American Boiler Manufacturers Association recommends that boilers operating below 300 psig should have less than 3500 ppm total solids, less than 700 ppm total Alkalinity, and less than 300 ppm total suspended solids. If the boiler water concentrations of these parameters are substantially below these values, then perhaps the boilers are being blown down too much.

The lower header blowdown valves are 1-1/2" diameter, but are connected to 3/4" diameter pipe from the valves to the blowdown tank. The 3/4" pipe controls the flow from the boiler's lower headers when the blowdown valves are wide open. Assuming an equivalent of 100 feet of pipe from the valves to the blow down tank yields a flow rate of 48 gpm. A ten second blow from each of the three lower headers would actually take 30 seconds each (10 seconds to open the valve, ten seconds to blow, and ten seconds to close the valve) yielding a consumption of 24 gallons per blow. With three lower headers and three blows per day per header, 216 gal. per day are discharged requiring an equivalent amount of make-up.

Table 4.2-1 ESTIMATED WATER LOSS DUE TO BLOWDOWN

Table 4.2-1 ESTIMATED WATER LOSS DUE TO BLOWDOWN									
Blowdown Point	Duration Est. (min)		Pipe Dia. (in)	Pipe Length (ft)	Pres. Drop (ft)	Flow		Average (gpd)	
	Est. #1	Est. #2				(gpm)	(gpd, #1)		(gpd, #2)
Intermittent (1)									
Heater #1	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #2	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #3	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
No. 4 Boiler									
East Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
West Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
Rear Wall	0.33	0.50	1	100	400	87.5	29.2	43.8	
East Drum	0.33	0.50	1	100	400	87.5	29.2	43.8	
West Drum	0.33	0.50	1	100	400	87.5	29.2	43.8	
Sub-total Intermittent Blowdown - Summer						448	343	395	
Heater #4	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Heater #5	0.42	0.17	1	100	400	87.5	36.5	14.6	
Level Xmtr.	0.20	0.08	1	10	400	320.9	64.2	26.7	
Additional Intermittent Blowdown - Winter						201	83	142	
Continuous (2)									
Steam Drum	1440	0	1/16	100	400	1.353	1948	0	974
Total Blowdown - Summer						2396	343	1369	
Total Blowdown - Winter						2597	425	1511	


- (1) Assumes 200 psi, 1 inch orifice, square edged, C=0.82; Cameron Hydraulic Data, pages 2-8 and 2-9.
(2) Assumes 200 psi, 1/16 inch orifice, square edged, C=0.82; Cameron Hydraulic Data, pages 2-8 and 2-9.

BOILER & CASCADE HEATER BLOWDOWN

				1.886	-2.01536	6.59603	0.133273			
0.5	0.033	-0.6931	-3.41	0.036						
0.6	0.041	-0.5108	-3.19	0.051						
0.8	0.102	-0.2231	-2.28	0.087						
1	0.155	0	-1.86	0.133						
2	0.526	0.69315	-0.64	0.493						
3	1.09	1.09861	0.086	1.059						
4	1.83	1.38629	0.604	1.822						
5	2.75	1.60944	1.012	2.775						
6	3.84	1.79176	1.345	3.915						
8	6.6	2.07944	1.887	6.736						
10	9.99	2.30259	2.302	10.261						
15	21.6	2.70805	3.073	22.050						
20	37.8	2.99573	3.632	37.940						
25	57.7975907			57.798						
30	81.52346277			81.523						
35				109.037						
40				140.273						
48.275				200.000						
50				213.694						
FLOW (GPM)	TIME (SEC/SHIFT)	BLOW POINTS	SHIFT /DAY		GAL/DAY	GPM				
48	30	3	3		216	0.150				
LBS/CY	GAL/CY	LOWER	CY/SH	SH/D						
325	39.0	2	2	3	468	0.325				
					684	0.475				
5.63	3.72									
5.63	4.20									
8100	6045									

FIGURE 2

3/4 Inch Pipe Characteristic



FLOW THROUGH ORIFICES AND NOZZLES

Approximate discharge through orifice or nozzle.

$$Q = 19.636 C d_1^2 \sqrt{h} \sqrt{1 - \left(\frac{d_1}{d_2}\right)^4} \text{ where } \frac{d_1}{d_2} \text{ is greater than } 0.3$$

$$Q = 19.636 C d_1^2 \sqrt{h} \text{ where } \frac{d_1}{d_2} \text{ is less than } 0.3$$

Q = flow, in gpm

d₁ = dia of orifice or nozzle opening, inches

h = differential head at orifice, in feet of liquid.

d₂ = dia of pipe in which orifice is placed, inches

C = discharge coefficient (typical values below for water)

RE-ENTRANT TUBE	SHARP-EDGED	SQUARE-EDGED	RE-ENTRANT TUBE	SQUARE-EDGED	WELL-ROUNDED
C = .52	C = .61	C = .73	C = .82	C = .98	

Table on next page shows flow using a value of C = 1.00. These flows values may be multiplied by the C value for a particular discharge to obtain actual flow.

Approximate flow through Venturi tube.

$$Q = 19.05 d_1^2 \sqrt{H} \sqrt{1 - \left(\frac{d_1}{d_2}\right)^4} \text{ for any Venturi tube}$$

$$Q = 19.17 d_1^2 \sqrt{H} \text{ for a Venturi tube in which } d_1 = 1/3 d_2$$

Q = flow, in gpm

d₁ = dia. of venturi throat, inches

d₂ = dia. of main pipe, inches

H = diff. in head between upstream end and throat (ft.)

These formulas are suitable for any liquid with viscosities similar to water. The values given here are for water. A value of 32.174 ft. per sec² was used for the acceleration of gravity and a value of 7.48 gal. per cu ft in computing the constants.

FORMULAS AND EQUIVALENCES

Flow Data — Nozzles

Theoretical Discharge of Nozzles in U S Gallons Per Minute

Head* psi	Velocity ft/sec	Diameter of nozzle in inches															
		1/16	1/8	3/16	1/4	3/8	1/2	5/8	3/4	7/8	1	1 1/8	1 1/4	1 1/2	1 3/4	1 3/8	1 3/4
10	23.1	0.37	1.48	3.32	5.91	13.3	23.6	36.9	53.1	72.4	94.5	120	148	179	181	179	179
15	34.6	0.45	1.81	4.06	7.24	16.3	28.9	45.2	65.0	88.5	116	147	181	219	219	219	219
20	46.2	0.52	2.09	4.69	8.35	18.8	33.4	52.2	75.1	102.	134	169	209	253	253	253	253
25	57.7	0.58	2.34	5.25	9.34	21.0	37.3	58.3	84.0	114.	149	189	234	283	283	283	283
30	69.3	0.64	2.56	5.75	10.2	23.0	40.9	63.9	92.5	125.	164	207	256	309	309	309	309
35	80.8	0.69	2.77	6.21	11.1	24.8	44.2	69.0	99.5	135.	177	224	277	334	334	334	334
40	92.4	0.74	2.96	6.64	11.8	26.6	47.3	73.8	106.	145.	188	239	296	357	357	357	357
45	103.9	0.78	3.13	7.03	12.5	28.2	50.1	78.2	113.	153.	200	253	313	379	379	379	379
50	115.5	0.83	3.30	7.41	13.2	29.7	52.8	82.5	119.	162.	211.	267	330	399	399	399	399
55	127.0	0.87	3.46	7.77	13.8	31.1	55.3	86.4	125.	169.	221.	280	346	418	418	418	418
60	138.6	0.90	3.62	8.12	14.5	32.5	57.8	89.4	130.	177.	231.	293	362	438	438	438	438
65	150.1	0.94	3.77	8.45	15.1	33.8	60.2	92.4	136.	184.	241.	305	376	455	455	455	455
70	161.7	0.98	3.91	8.78	15.7	35.2	62.5	95.7	141.	191.	250.	317	391	473	473	473	473
75	173.2	1.01	4.05	9.08	16.2	36.4	64.7	101.	146.	198.	259.	327	404	489	489	489	489
80	184.8	1.05	4.18	9.38	16.7	37.6	66.8	104.	150.	205.	276.	349	431	521	521	521	521
85	196.3	1.08	4.31	9.67	17.3	38.8	68.9	108.	155.	211.	276.	349	431	521	521	521	521
90	207.9	1.11	4.43	9.95	17.7	39.9	70.8	111.	160.	217.	284.	359	443	536	536	536	536
95	219.4	1.14	4.56	10.2	18.2	41.0	72.8	114.	164.	223.	292.	369	456	551	551	551	551
100	230.9	1.17	4.67	10.5	18.2	42.1	74.7	117.	168.	229.	299.	378	467	565	565	565	565
105	242.4	1.20	4.79	10.8	19.2	43.1	76.5	120.	172.	234.	306.	388	479	579	579	579	579
110	254.0	1.23	4.90	11.1	19.6	44.1	78.4	122.	176.	240.	314.	397	490	591	591	591	591
115	265.5	1.25	5.01	11.2	20.0	45.1	80.1	125.	180.	245.	327.	414	512	619	619	619	619
120	277.1	1.28	5.12	11.5	20.5	46.0	81.8	128.	184.	251.	341.	432	533	645	645	645	645
130	300.2	1.33	5.33	12.0	21.3	48.0	85.2	133.	192.	261.	354.	448	553	668	668	668	668
140	323.3	1.44	5.72	12.9	22.9	51.6	91.5	143.	206.	280.	366.	463	572	692	692	692	692
150	346.4	1.49	5.85	13.3	24.1	53.6	95.8	154.	222.	302.	385.	500	618	747	747	747	747
175	404.1	1.61	6.31	14.8	26.4	59.5	106.	165.	238.	323.	423.	535	660	799	799	799	799
200	461.9	1.72	6.81	16.8	29.6	65.5	118.	185.	266.	362.	473.	598	739	894	894	894	894
250	577.4	1.93	7.39	18.8	32.4	72.8	129.	202.	291.	396.	517.	655	808	977	977	977	977
300	692.8	2.11	8.08	18.2	32.4	72.8	129.	202.	291.	396.	517.	655	808	977	977	977	977
10	23.1	0.37	1.48	3.32	5.91	13.3	23.6	36.9	53.1	72.4	94.5	120	148	179	181	179	179
15	34.6	0.45	1.81	4.06	7.24	16.3	28.9	45.2	65.0	88.5	116	147	181	219	219	219	219
20	46.2	0.52	2.09	4.69	8.35	18.8	33.4	52.2	75.1	102.	134	169	209	253	253	253	253
25	57.7	0.58	2.34	5.25	9.34	21.0	37.3	58.3	84.0	114.	149	189	234	283	283	283	283
30	69.3	0.64	2.56	5.75	10.2	23.0	40.9	63.9	92.5	125.	164	207	256	309	309	309	309
35	80.8	0.69	2.77	6.21	11.1	24.8	44.2	69.0	99.5	135.	177	224	277	334	334	334	334
40	92.4	0.74	2.96	6.64	11.8	26.6	47.3	73.8	106.	145.	188	239	296	357	357	357	357
45	103.9	0.78	3.13	7.03	12.5	28.2	50.1	78.2	113.	153.	200	253	313	379	379	379	379
50	115.5	0.83	3.30	7.41	13.2	29.7	52.8	82.5	119.	162.	211.	267	330	399	399	399	399
55	127.0	0.87	3.46	7.77	13.8	31.1	55.3	86.4	125.	169.	221.	280	346	418	418	418	418
60	138.6	0.90	3.62	8.12	14.5	32.5	57.8	89.4	130.	177.	231.	293	362	438	438	438	438
65	150.1	0.94	3.77	8.45	15.1	33.8	60.2	92.4	136.	184.	241.	305	376	455	455	455	455
70	161.7	0.98	3.91	8.78	15.7	35.2	62.5	95.7	141.	191.	250.	317	391	473	473	473	473
75	173.2	1.01	4.05	9.08	16.2	36.4	64.7	101.	146.	198.	259.	327	404	489	489	489	489
80	184.8	1.05	4.18	9.38	16.7	37.6	66.8	104.	150.	205.	276.	349	431	521	521	521	521
85	196.3	1.08	4.31	9.67	17.3	38.8	68.9	108.	155.	211.	276.	349	431	521	521	521	521
90	207.9	1.11	4.43	9.95	17.7	39.9	70.8	111.	160.	217.	284.	359	443	536	536	536	536
95	219.4	1.14	4.56	10.2	18.2	41.0	72.8	114.	164.	223.	292.	369	456	551	551	551	551
100	230.9	1.17	4.67	10.5	18.2	42.1	74.7	117.	168.	229.	299.	378	467	565	565	565	565
105	242.4	1.20	4.79	10.8	19.2	43.1	76.5	120.	172.	234.	306.	388	479	579	579	579	579
110	254.0	1.23	4.90	11.1	19.6	44.1	78.4	122.	176.	240.	314.	397	490	591	591	591	591
115	265.5	1.25	5.01	11.2	20.0	45.1	80.1	125.	180.	245.	327.	414	512	619	619	619	619
120	277.1	1.28	5.12	11.5	20.5	46.0	81.8	128.	184.	251.	341.	432	533	645	645	645	645
130	300.2	1.33	5.33	12.0	21.3	48.0	85.2	133.	192.	261.	354.	448	553	668	668	668	668
140	323.3	1.44	5.72	12.9	22.9	51.6	91.5	143.	206.	280.	366.	463	572	692	692	692	692
150	346.4	1.49	5.85	13.3	24.1	53.6	95.8	154.	222.	302.	385.	500	618	747	747	747	747
175	404.1	1.61	6.31	14.8	26.4	59.5	106.	165.	238.	323.	423.	535	660	799	799	799	799
200	461.9	1.72	6.81	16.8	29.6	65.5	118.	185.	266.	362.	473.	598	739	894	894	894	894
250	577.4	1.93	7.39	18.8	32.4	72.8	129.	202.	291.	396.	517.	655	808	977	977	977	977
300	692.8	2.11	8.08	18.2	32.4	72.8	129.	202.	291.	396.	517.	655	808	977	977	977	977
10	23.1	0.37	1.48	3.32	5.91	13.3	23.6	36.9	53.1	72.4	94.5	120	148	179	181	179	179
15	34.6	0.45	1.81	4.06	7.24	16.3	28.9	45.2	65.0	88.5	116	147	181	219	219	219	219
20	46.2	0.52	2.09	4.69	8.35	18.8	33.4	52.2	75.1	102.	134	169	209	253	253	253	253
25	57.7	0.58	2.34	5.25	9.34	21.0	37.3	58.3	84.0	114.	149	189	234	283	283	283	283
30	69.3	0.64	2.56	5.75	10.2	23.0	40.9	63.9	92.5	125.	164	207	256	309	309	309	309
35	80.8	0.69	2.77	6.21	11.1	24.8	44.2	69.0	99.5	135.	177	224	277	334	334	334	334

Sootblowing

The sootblowing operations should be carefully reviewed. Blowing soot twice per shift regardless of need is not proper procedure. Blowing too frequently can cause excessive tube erosion perhaps resulting in premature tube replacement. Frequent blowing is also wasteful of valuable steam, particularly at reduced boiler loads.

Soot blowing should be initiated primarily by high exit gas temperature which indicates that the energy released by the fuel is not being absorbed by the dirty tube surfaces. A 40° rise in exit gas temperature is approximately equal to 1% in boiler efficiency. Often this rule of thumb is used to determine when the boiler has become fouled with the solid products of combustion and should be cleaned by operating the sootblowers. Unfortunately, there is no indication of exit gas temperature on the boiler.

A simple thermometer (\$50) can be installed in the hot gas duct to the air heater to indicate the exit gas temperature. Operators can record the exit gas temperature hourly and activate the soot blowers when the exit gas temperature gets too high.

The Diamond Power factory calculates that 325 lb. steam (39 gals water) are consumed every time the IK sootblower is operated. With two IK blowers and 6 operations each per day the total steam consumption is 3900 lb. steam (468 gals) per day.



SUBJECT FORT STEWART
CEP Misc. Leaks
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 1 OF 2
DATE 2-2-96
DATE _____

CEP MISCELLANEOUS LEAKS

Valves & Fittings:

Cascade Heater No. 1

- Valve to top of sight glass leaking steam
- Valve on top left of heater leaking steam

Leak Rate
Estimate.

2 drop/sec
2 "

Cascade Heater No. 2

- Valve on bottom left of heater leaking steam

2 "

Cascade Heater No. 3

- Valve on top of sight glass leaking steam

2 "

Deaerator Tank

- Strainer next to control valve leaking steam and about 3 drops/second HTW.
- Valve above stairs leaking steam
- Vent to outside blowing steam (intermittant)

5 "

2 "

2 "

Total valves & fittings leaks

17 drops/sec

$$17 \text{ drops/second} \times 2.5 \times 10^{-3} \frac{\text{gpm}}{\text{d/s}} = \underline{0.042 \text{ gal/min}}$$

HTW Zone Pumps:

- P-4 & P-5 ~ 1 drop / 4 seconds

= 0.0006 GPM

- P-10 ~ steady 1/8" stream *

= 0.109 GPM

- P-11 ~ Intermittant 1/8" stream*

= 0.054 GPM



SUBJECT Fort Stewart
CEP Misc. Leaks
DESIGNER W. Todd
CHECKER _____

AEP NO 694 1331 002
SHEET 2 OF 2
DATE 2-2-96
DATE _____

Pumps (continued)

$$- P-23 \text{ \& } P-24 \sim 2 \text{ drops / 3 seconds} = 0.0017 \text{ GPM}$$

* A $\frac{1}{8}$ " stream was measured and timed and found to be $\sim 1.75 \text{ cups/min} \div 16 \frac{\text{cups}}{\text{gal}} \approx 0.109 \text{ GPM}$

$$\text{Total Leaks from HTW Pumps} = \underline{0.165 \text{ GPM}}$$

Total Miscellaneous CEP Leaks:

Valves & Fittings	0.042 GPM
HTW Zone Pumps	0.165 GPM

$$\text{Total} = \underline{0.207 \text{ GPM}}$$

Central Energy Plant (CEP) Leak Test #4 Boiler

On November 30, 1995 a leak test was conducted at CEP to determine the extent of the leaks associated with Boiler No.4. A significant amount of steam continually vents from the No.4 blowdown tank. To quantify this loss, a CEP leak test would be conducted with the No.4 boiler configured in as a "tight" a mode as possible, and then a second test would be conducted with No.4 in a "normal" (leaky) configuration. The difference in the test results would be the leaks due to No. 4's normal configuration.

The leak test consists of measuring the make-up water required to maintain constant heater levels over an 8 hour period. Unfortunately, the test results showed no heater level changes over the 6 hour test period when a 6-7 inch change in the gauge glass level was expected. This testing technique has yielded results in the past. No explanation for the lack of results was determined; however, improper system valving is strongly suspected.


Configuring the boiler in as tight a configuration as possible stopped the blowdown tank steam venting. Leaking steam traps in the main steam line, the soot blower warm-up line, and in the boiler feed pump turbine line are the sources of the steam venting. Furthermore, the rear water wall header blowdown valves are leaking slightly. This leak was so small that only warm water entered the blow down tank.

A graph (enclosed) of the daily make-up consumption data shows a wide scattering of data, perhaps lending credence to the suspicion that observing heater tank levels over a short period of time (8 hours) yields uncertain results. However, when averaged over longer periods of time (weeks), yields more reliable results. The graph shows the daily make-up consumption (DMC) prior to October 15, 1995 averaged about 7000 gpd (4.86 gpm) while unit 4 alone was operating. During the period October 15 through November 10, 1995 unit 4 was shut down and units 1,2 and 3 were operating, and the DMC fell to 5900 gpd (4.10 gpm). This reduction in DMC can be attributed to two principal causes; 1) the general leaky state of unit No. 4; and 2) the required consumption of steam for sootblowing. The magnitude of the change 1100 gpd (0.764 gpm) seems reasonable. The fact that the consumption returned to the original levels when 4 boiler was returned to service implies that some of the leaks are in fact related to unit No. 4.

No. 4 Boiler Operation Recommendations

1. Repair steam trap leaks.
2. Reduce soot blowing frequency. Change from a time based operation to an exit gas temperature based operation.
3. Reduce blow down frequency to maintain American Boiler Manufacturers Association standard of 3500 ppm total dissolved solids.

Ft. Stewart Make-up Flow vs Time



SEP - MISC. HTW LEAKS

Satellite Energy Plant (SEP) Leak test.

On November 29, 1995 the SEP was tested for system leaks. The testing procedure consists of stopping all steam flow to, and condensate return flow from, the SEP, and measuring the decrease in the level of the two cascade heaters in the SEP. By calculating the volume change in the heaters, a leak rate may be determined.

Time (EST)	9:46	10:34	11:13	11:37	11:48
Level (in)	14.3	14.3	14.3	14.3	14.3
Temp (°F)	375	360	340	335	330
Pres. (psig)	190	140	115	105	100

The data from the 2 hour test indicated that the water level in the heaters never changed while the circulating hot water showed a -45° temperature change and a -90 psig pressure change. It was concluded therefore the SEP system was "tight".

It is important to note however that the testing method used is quite crude over the short time period of the test. The two, 4000 gallon, cascade heaters are connected by symmetrical piping assuring "equal" water levels in both heaters. A one inch change in water level, at normal operating level, would be equivalent to 140 gallons of water. The leaks found and measured during the test are tabulated below.

<u>Location</u>	<u>Amount (gpm)</u>
East Heater gauge glass	2.23×10^{-4}
East Heater Steam Stop valve	2.11×10^{-3}
West Heater Equalization valve	1.00×10^{-3}
HTWS Check Valve	0.03
Both Heaters blow down valves	<u>0.2</u>
TOTAL	0.233

The total amount of water lost during the test is $0.233 \text{ gpm} \times 122 \text{ min.} = 29 \text{ gals.}$, or approximately 0.2 inches on the gauge glass. With normal, slow, level swings (generally attributable to sloshing) between the tanks, this leak rate is barely detectable in the sight glass over the time span of the test. Because of the large heater storage capacity, a longer test period is warranted. In the future this test could be a reasonable leak detection and quantification method at the SEP if conducted over longer testing periods. The best time for the test would be when the heat load from the SEP is minimal, perhaps on a warm day after a cool night.

VALVE PIT HTW LEAKS

RS&H

SUBJECT Fort Stewart
Repair Leaks in Valve Pits
 DESIGNER W. Todd
 CHECKER _____

AEP NO 694 1331 002
 SHEET _____ OF _____
 DATE 2-5-96
 DATE _____

Valve Pit No.	Drops / Sec	Stream Dia./GPM	Leak From
VP-1-11	1/3	-	Valve ↓ 2 valves flange Valve " flange ↓
VP-1-16	3+2	-	
VP-2N-5	5+	-	
VP-2S-1	2	-	
VP-2S-3	2	-	
VP-2S-8	2+2	-	
VP-3-1	2	1/4" / 0.438	
VP-3-5	1/10 + 2	-	
VP-3-11	-	1/8" / 0.109	
VP-3-15	-	1/8" / 0.109	
VP-3-16	-	3/16" / 0.246	
VP-3-18	2	-	
VP-3-27	1+2	-	
Totals	13 pits	27.4 D/s	0.902 GPM

Minor Leaks :

$$27.4 \text{ drop/s} \times 2.5 \times 10^{-3} \frac{\text{GPM}}{\text{d/s}} = 0.069 \text{ GPM} = 36,270 \frac{\text{GAL}}{\text{YR}}$$

Proposed HTW losses : Assume 50% of minor leaks

$$0.069 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} \times 0.5 = 18130 \frac{\text{GAL}}{\text{YR}}$$

Major Leaks : (Assume 100% can be repaired)

$$0.902 \text{ GPM} \times 1440 \frac{\text{min}}{\text{day}} \times 365 \frac{\text{day}}{\text{YR}} = 474,090 \text{ GAL/YR}$$

Current HTW Losses :

$$474,090 \text{ GAL/YR} + 18,130 \text{ GAL/YR} = 510,360 \text{ GAL/YR}$$

MECH. EQUIP. ROOM HTW LEAKS

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
206	3	Learning Center	80	DHW	Y	Y	Y	2.00	0.33
207	3	Dining Facility	124	DHW	Y	N	N		
208	3	Fitness Center	113	DHW	Y	Y	N	0.06	
211	3	Admin.	N/A	N/A	Y	Y	N	4.00	
212	3	Admin/Barracks	131	DHW	Y	N	N		
213	3	Barracks	120	DHW	Y	N	N		
215	3	Barracks	137	DHW	Y	Y	N	2.00	1.50
216	3	Barracks	110	DHW	Y	Y	N	2.50	
217	3	Admin.	N/A	N/A	Y	Y	N	0.13	
218	3	Barracks	124	DHW	Y	N	Y		
223	3	Admin.	N/A	N/A	Y	Y	N	0.17	
224	3	Admin.	N/A	N/A	Y	Y	N	5.00	6.67
225	3	Admin.	N/A	N/A	Y	N	N		
230	3	Tac Equip Shop	N/A	N/A	Y	N	N		
241	3	Tac Equip Shop	N/A	N/A	Y	N	N		
260	3	Tac Equip Shop	N/A	N/A	Y	N	N		
270	3	Tac Equip Shop	N/A	N/A	Y	Y	N	2.20	
276	3	Tac Equip Shop	N/A	N/A	N				
302	3	Hospital	137	DHW	Y	N	N		
403	N/A	Child Care Ctr	N/A	N/A	Y	N/A	N		
439	N/A	Fitness Center	139	DHW	Y	N/A	N		
440	2	Dental Clinic	114	DHW	Y	N	N		
501	2	Barracks	134	DHW	Y	Y	N	0.33	
503	2	Barracks	122	DHW	Y	Y	N	2.00	0.25
504	2	Barracks	158	DHW	Y	Y	N		0.75
506	2	Admin.	N/A	N/A	Y	N	N		
507	2	Admin.	N/A	N/A	Y	Y	N	1.00	
508	2	Admin.	N/A	N/A	Y	N	N		
509	2	Admin.	N/A	N/A	Y	N	Y		
512	2	Dining Facility	145	DHW	Y	?	Y		1.17
514	2	Barracks	126	DHW	Y	Y	N	1.25	
515	2	Barracks	123	DHW	Y	N	Y		
516	2	Barracks	145	DHW	Y	?	Y		
517	2	Barracks	175	DHW	LOCKED				
518	2	Barracks	183	DHW	Y	?	Y	3.33	
520	2	Admin.	N/A	N/A	Y	N	Y		
521	2	Admin.	N/A	N/A	Y	Y	N	0.50	
522	2	Admin.	N/A	N/A	Y	Y	N	0.25	
523	2	Admin.	N/A	N/A	Y	N	N		
524	2	Admin.	N/A	N/A	Y	N	N		
525	2	Admin.	N/A	N/A	Y	Y	N	0.09	

10 Flanges
10 Valves

MECH. ROOM HTW LEAKS

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
608	2	Fitness Center	127	DHW	Y	Y	N	0.08	
610	2	Chapel	115	DHW	Y	N	N		
612	2	Admin.	N/A	N/A	Y	Y	Y	0.08	✓
614	1	Admin.	N/A	N/A	Y	N	Y		
616	1	Admin.	N/A	N/A	Y	N	Y		
617	1	Admin.	N/A	N/A	Y	N	N		
618	1	Admin.	N/A	N/A	Y	N	N		
619	1	Admin.	N/A	N/A	Y	N	N		
620	1	Admin.	112	DHW	Y	N	N		
621	1	Admin.	91	DHW	Y	N	N		
622	1	Admin.	85	DHW	Y	N	N		
623	1	Admin.	109	DHW	Y	N	Y		
624	1	Admin.	109	DHW	Y	N	Y		
626	1	Dining Facility	145	DHW	Y	N	N		
628	1	Admin.	N/A	N/A	Y	Y	N	0.20	✓
629	1	Barracks	160	DHW	Y	?	Y		
630	1	Barracks	117	DHW	Y	N	Y		
631	1	Barracks	142	DHW	Y	Y	Y		0.88 ✓
632	1	Barracks	160	DHW	Y	N	Y		
633	1	Barracks	128	DHW	Y	Y	Y	2.00	F
634	1	Barracks	LOCKED	LOCKED	Y	N	N		
635	1	Barracks	140	DHW	Y	Y	N	1.59	✓
636	1	Barracks	138	DHW	Y	Y	Y	1.22	✓
637	1	Barracks	158	DHW	Y	N	N		
638	1	Admin.	N/A	N/A	Y	N	Y		
639	1	Admin.	N/A	N/A	Y	Y	N	1.56	✓
640	1	Admin.	N/A	N/A	Y	N	N		
641	1	Admin.	N/A	N/A	Y	N	N		
642	1	Dining Facility	154	DHW	Y	N	Y		
643	1	Admin.	N/A	N/A	Y	Y	N	0.10	✓
644	1	Admin.	N/A	N/A	Y	Y	N	0.33	✓
645	1	Admin.	N/A	N/A	Y	N	N		
646	1	Admin.	N/A	N/A	Y	N	N		
647	1	Admin.	N/A	N/A	Y	Y	N	0.20	✓
648	1	Admin.	N/A	N/A	Y	N	Y		
649	1	Admin.	N/A	N/A	Y	N	N		

3 Flanges
9 Valves

MECH. Room HTW LEAKS

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
701	1	Health Clinic	152	DHW	Y	Y	N	1.00	✓
702	1	Ent. Center	143	DHW	Y	N	N		
703	1	Enl. Mens Club	N/A	N/A	LOCKED		Y		
704	1	Theater	N/A	N/A	Y	N	Y		
706	1	Branch Exchange	N/A	N/A	Y	N	Y		
708	1	Fitness Center	131	DHW	Y	N	Y		
710	1	Admin.	N/A	N/A	Y	N	Y		
712	1	Barracks	135	DHW	Y	N	Y		
713	1	Barracks	133	DHW	Y	N	Y		
714	1	Barracks	137	DHW	Y	N	Y		
715	1	Barracks	135	DHW	Y	Y	N	0.20	✓
717	1	Barracks	131	DHW	Y	N	N		
718	1	Barracks	124	DHW	Y	Y	Y	0.20	2 ✓
719	1	Barracks	112	DHW	Y	Y	N	1.00	✓
720	1	Barracks	130	DHW	Y	N	Y		
721	1	Admin.	N/A	N/A	Y	N	N		
722	1	Admin.	N/A	N/A	Y	Y	Y	5.00	✓
723	1	Admin.	N/A	N/A	Y	N	N		
724	1	Admin.	N/A	N/A	Y	N	N		
725	1	Admin.	N/A	N/A	Y	N	N		
726	1	Dining Facility	158	DHW	Y	N	Y		
727	N/A	Training Facility	N/A	N/A	Y	N/A	N		
728	1	Admin.	N/A	N/A	Y	Y	N	3.05	2 ✓
810	1	Barracks	131	DHW	Y	N	N		
811	1	Admin.	N/A	N/A	Y	N	N		
812	1	Admin.	N/A	N/A	Y	N	N		
813	1	Admin.	N/A	N/A	Y	N	N		
814	1	Admin.	N/A	N/A	Y	N	Y		
815	1	Admin.	N/A	N/A	Y	N	N		
816	1	Admin.	N/A	N/A	Y	N	Y		
818	1	Admin.	N/A	N/A	Y	N	N		
819	1	Admin.	N/A	N/A	Y	Y	N	0.13	3 ✓

Ø Flanges

|| Valves

MECH. ROOM HTW LEAKS

Fort Stewart - HTW Distribution System

Filename: FS-BLDGS.WB2

Building No.	HTW Zone	Building Type	DHW Temp.	Water Sample	Mech Rm Survey	HTW Leaks	Other Leaks	HTW Drop/Sec	HTW Cup/Min
1160	3	D.S. Maint Fac	N/A	N/A	Y	Y	N	2.03	21
1170	3	G.S. Maint Fac	N/A	N/A	Y	N	N		
1208	1	Tac Equip Shop	N/A	N/A	Y	N	Y		
1209	1	Tac Equip Shop	N/A	N/A	Y	N	N		
1211	1	Tac Equip Shop	N/A	N/A	Y	N	N		
1245	N/A	Tac Equip Shop	N/A	N/A	Y	N/A	Y		
1259	1	Tac Equip Shop	N/A	N/A	Y	Y	N		0.25
1261	2	Tac Equip Shop	N/A	N/A	N				
1265	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1280	N/A	Tac Equip Shop	N/A	N/A	Y	N/A	Y		
1320	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1330	2	Tac Equip Shop	N/A	N/A	Y	Y	N	0.13	✓
1340	2	Tac Equip Shop	N/A	N/A	Y	N	N		
1412		C. Energy Plant	N/A	HTW	Y	Y			
1500	3	Div Logis Fac	N/A	N/A	w/ 1509?				
1503	3	Auto Hobby Shop	N/A	N/A	LOCKED				
1509	3	Div Logis Fac	N/A	N/A	Y	Y	Y	3.00	✓
1510	3	Tac Equip Shop	N/A	N/A	N				
1540	3	Tac Equip Shop	95	PW	N				
1720	2	D.S. Maint Fac	148	DHW	Y	N-N/A	N		
1810	2	Tac Equip Shop	N/A	N/A	N				
1820	2	Tac Equip Shop	N/A	N/A	Y	N-N/A	N		
1840	2	Tac Equip Shop	N/A	N/A	Y	N	Y		
2115	1	Dental Clinic	N/A	N/A	Y	N	N		
2125	1	Chapel	120	DHW	Y	N	N		
3001	S	S. Energy Plant	N/A	N/A	Y	Y			
3002	S	Admin.	N/A	N/A	Y	Y	N	5.20	F+V
4502	S	Tac Equip Shop	N/A	N/A	N				
4528	S	Tac Equip Shop	N/A	N/A	N				
4577	S	Tac Equip Shop	N/A	N/A	N				
4578	S	Tac Equip Shop	N/A	N/A	N				
TOTALS		140			127	42	41	55.11 Drop/Sec	11.80 Cup/Min

Leaks (GPM) = 0.138 0.737

% of Total = 16% 84%

Total Leaks = 0.875 GPM

1 Flange
6 Valves

HEATING EQUIP. & SEP LOSSES

RS&HSUBJECT Fort Stewart HTW

AEP NO _____

DESIGNER W.T. TODD

SHEET _____ OF _____

CHECKER _____

DATE _____

DATE _____

HTW losses during the heating season were substantially higher than the rest of 1995. These losses must be due to leaks in the SEP system and from building HVAC heating equipment.

<u>Month/Yr.</u>	<u>Avg. HTW Losses</u>	<u>Annual Avg.</u>	<u>Difference</u>
Jan/95	9.0 GPM	6.4 GPM	2.6 GPM
Feb/95	11.0 GPM	6.4 GPM	4.6 GPM
Mar/95	8.1 GPM	6.4 GPM	1.7 GPM

HEATING EQUIP. & SEP LOSSES:

$$2.6 \text{ GPM} \times 1440 \text{ min/day} \times 31 \text{ days} = 116,064 \text{ Gal}$$

$$4.6 \text{ GPM} \times 1440 \text{ min/day} \times 28 \text{ days} = 185,472 \text{ Gal}$$

$$1.7 \text{ GPM} \times 1440 \text{ min/day} \times 31 \text{ days} = 75,888 \text{ Gal}$$

$$\text{TOTAL} = 377,424 \text{ GAL}$$

$$377,424 \text{ GAL/YR} \div 365 \text{ days/YR} = \underline{1034 \text{ Gal/Day}}$$

$$1034 \text{ GAL/DAY} \div 1440 \text{ min/day} = \underline{0.718 \text{ Gal/min}}$$



SUBJECT FORT STEWART
 DESIGNER W. TODD
 CHECKER _____

AEP NO _____
 SHEET _____ OF _____
 DATE _____
 DATE _____

SEP START-UP LOSSES

See calculations for ECD-9.

HTW PIPING LEAKS - REPAIRED

Average loss during leak = 25000 Gal (see Figure 4.1-5)

Average loss w/o leak = 15000 Gal (see Figure 4.1-5)

Loss from leak = 10000 Gal

Total losses = 10000 Gal/leak \times 2 leaks = 20000 GAL

20000 GAL \div 365 day/YR = 55 GAL/DAY

55 GAL/DAY \div 1440 min/DAY = 0.038 GAL/MIN

A.5 ENERGY DATA, BOILER LOGS AND MAKE-UP WATER DATA

Fort Stewart Central Energy Plant
Energy Consumption
Filename: FS-ENRGY.WQ1

Month	Yr	Wood Tons (1)	Wood MBtu (2)	Wood Cost (2)	#2 Oil Gals (1)	#2 Oil MBtu (3)	#2 Oil Cost (3)	Used Oil Gals (4)	Used Oil MBtu (5)	Used Oil Cost (5)	N.Gas CuFt (1)	N.Gas MBtu (6)	N.Gas Cost (6)	Total MBtu	Total Cost
7	94	6052	62941	65483	75497	10645	46808	0	0	0	5572730	5701	18563	79287	130854
8	94	8169	84958	88389	13822	1949	8570	12956	1749	0	874295	894	2878	89549	99836
9	94	4969	51678	53765	40667	5734	25214	17703	2390	0	352500	361	1056	60163	80034
10	94	3947	41049	42707	42608	6008	26417	18775	2535	0	598230	611	1790	50203	70913
11	94	5000	52000	54100	15884	2240	9848	24298	3280	0	1082030	1107	3488	58627	67436
12	94	6631	68964	71749	22257	3138	13799	9470	1278	0	1366090	1398	4363	74778	89912
1	95	6100	63441	66003	39741	5603	24639	8891	1200	0	1027820	1049	3199	71294	93841
2	95	5024	52250	54360	110411	15568	68455	13181	1779	0	1159730	1186	3368	70783	126182
3	95	5723	59519	61923	19404	2736	12030	11576	1563	0	518890	530	1463	64348	75417
4	95	1869	19438	20223	550	78	341	0	0	0	12995190	13268	37455	32783	58019
5	95	5322	55349	57584	6525	920	4046	11324	1529	0	550120	563	1724	58361	63354
6	95	4768	49587	51590	11466	1617	7109	5476	739	0	2081740	2128	6435	54071	65134
Averages		5298	55098	57323	33236	4686	20606	11138	1504	0	2348280	2400	7148	63687	85078
Totals		63574	661173	687874	398832	56235	247276	133650	18043	0	28179365	28796	85782	764246	1020931
% of Total			86.5%	67.4%		7.4%	24.2%		2.4%	0.0%		3.8%	8.4%		
Avg Cost			\$1.04 /MBtu			\$4.40 /MBtu			\$0.00 /MBtu			\$2.98 /MBtu		\$1.34 /MBtu	

- (1) Source is Fort Stewart Operating Logs.
(2) Assumes 40% moisture and heating value of 5200 btu/lb; cost is \$10.82/ton.
(3) Assumes heating value of 141000 btu/gal; cost is \$0.62/gal.
(4) Source is monthly Oil Reports prepared at the CEP.
(5) Assumes heating value of 18000 btu/lb, 7.5 lb/gal; no cost.
(6) Uses heating value and cost from utility bills.

ELECTRIC BILLS



DPW, SERVICE BRANCH
FAX NO. 767-7570



TO: Bill Todd, RS: H. Jax, FL.
FROM: Denise Kelley
DATE: 18 Aug 95
MESSAGE: As Requested

$\frac{\$3070487}{65,491,200 \text{ kWh}}$

NO OF PAGES -----

Average elec. cost = \$0.0469/kwh

PLEASE DO NOT STAPLE, FOLD OR PAPER CLIP

Georgia Power Company
96 Annex, Atlanta, Ga. 30396

1 0475 B

831853000402007250846530081095000000000

FORT STEWART
DPW
BLDG 1139
SERVICE BRANCH
FT STEWART GA

31314

REMIT TO ↑

Georgia Power Company
P. O. BOX 102473
68 ANNEX
ATLANTA GA 30368

725084.65 SVC 520

8318530004020

725084.65 XXXXXXXXXXXXX

PLEASE RETURN THIS PORTION WITH YOUR REMITTANCE.

Total Net Due

Account Number		Service Period		DSO DB		FUEL CS		ECON CR		Georgia Power Company	
		From	To								
8318530004020	06-23	07-24-95		0.934350X		0.015097		0.009150X		HINESVILLE GA	31313
RATE	METER	PRES	PREV	KWH	KW HRS	BILL	ACT	ACT			Amount
520	E70396	4344	4110	19200	16608000	30701	30701	14632			725084.65
				CONST	USED	DEM	DEM	RKVA CD			
				EXCESS RKVA	4398						

CONSUMPTION FORWARDED METERS
E70398 0346 9715 19200

Sales Tax		Local Tax		Date of Bill		Service Name and Location		PLEASE PAY BY		Total Net Due	
				0728		FORT STEWART DPW HERO RD FORT STEWART GA	31313	08-10-95		725084.65	

PLEASE RETAIN THIS PORTION FOR YOUR RECORDS.
REFERENCE REVERSE SIDE FOR EXPLANATIONS AND DESCRIPTIONS OF RATE NAMES, ABBREVIATIONS AND BILLING CODES.

$$\frac{\$725085}{16608000 \text{ KWH}} = \$0.0437/\text{kwh}$$

A.5-5

PLEASE DO NOT STAPLE, FOLD OR PAPER CLIP

Georgia Power Company
96 Annex, Atlanta, Ga. 30396

1 0480 B

831853000402006613207430071195000000000

FORT STEWART
DPW
BLDG 1139
SERVICE BRANCH
FT STEWART GA

31314 REMIT TO ↑

Georgia Power Company
P. O. BOX 102473
68 ANNEX
ATLANTA GA 30368

661320.74 SVC 520

8318530004020

661320.74 XXXXXXXXXXXX

PLEASE RETURN THIS PORTION WITH YOUR REMITTANCE.

Total Net Due

Account Number		Service Period						Georgia Power Company	
		From	To	DSO DB	0.934350%				
8318530004020		05-24	06-23-95	FUEL CS	\$0.015097	HINESVILLE GA		31313	
				ECON CR	0.009150%	(912) 368-3376			
RATE	METER	PRES	PREV	KWH	KW HRS	BILL	ACT	ACT	Amount
NAME	NO.	READ	READ	CONST	USED	DEM	DEM	RKVA	
520	E70396	4110	3898	19200	14515200	29818	29818	14355	
EXCESS RKVA				4416					661320.74

CONSUMPTION FORWARDED METERS
E70398 9715 9171 19200

*Rec'd 6/24/95
Dianne Henry*

Sales Tax		Local Tax		0629		FORT STEWART DPW HERO RD FORT STEWART GA 31313		PLEASE PAY BY 07-11-95		661320.74	
Current Bill Includes				Date of Bill		Service Name and Location				Total Net Due	

PLEASE RETAIN THIS PORTION FOR YOUR RECORDS.
REFERENCE REVERSE SIDE FOR EXPLANATIONS AND DESCRIPTIONS OF RATE NAMES, ABBREVIATIONS AND BILLING CODES.

$$\frac{\$661,321}{14,515,200 \text{ kwh}} = \$0.0456/\text{kwh}$$

PLEASE DO NOT STAPLE, FOLD OR PAPER CLIP

Georgia Power Company
96 Annex, Atlanta, Ga. 30396

1 0479 B

83185300040200604300088006129500000000

FORT STEWART
DPW
BLDG 1139
SERVICE BRANCH
FT STEWART GA

Georgia Power Company
P. O. BOX 102473
68 ANNEX
ATLANTA GA 30368

31314

REMIT TO ↑

604300.08 SVC 520

8318530004020

PLEASE RETURN THIS PORTION WITH YOUR REMITTANCE.

Account Number		Service Period		DSO DB		FUEL CS		ECON CR		Total Net Due	
8318530004020		From	To	0.934350%		#0.015097		0.009150%		604300.08 XXXXXX XXXXXX	
04-24		05-24-95		KWH		KWH		KWH		Georgia Power Company	
RATE	METER	PRES	PREV	CONST	USED	BILL	ACT	ACT	ACT	HINESVILLE GA 31313	
NAME	NO.	READ	READ	CONST	USED	DEM	DEM	DEM	DEM	(912) 368-3376	
520	E70396	3898	3688	19200	13056000	27816	27725	13014	13014	Amount	
EXCESS RKVA		5772								604300.08	

CONSUMPTION FORWARDED METERS
E70398 9171 8701 19200

Sales Tax		Local Tax		0531	FORT STEWART DPW		PLEASE PAY BY		604300.08	
Current Bill Includes		Date of Bill			HERO RD FORT STEWART GA 31313		06-12-95			
					Service Name and Location					Total Net Due

PLEASE RETAIN THIS PORTION FOR YOUR RECORDS.
REFERENCE REVERSE SIDE FOR EXPLANATIONS AND DESCRIPTIONS OF RATE NAMES, ABBREVIATIONS AND BILLING CODES.

$$\frac{\$604,300}{13,056,000 \text{ kwh}} = \$0.0463/\text{kwh}$$

PLEASE DO NOT STAPLE, FOLD OR PAPER CLIP

Georgia Power Company
96 Annex, Atlanta, Ga. 30396

1 0483 B

831853000402005241511400051095000000000

FORT STEWART
DPW
BLDG 1139
SERVICE BRANCH
FT STEWART GA

31314

REMIT TO ↑

Georgia Power Company
P. O. BOX 102473
68 ANNEX
ATLANTA GA 30368

524151.14 SVC 520

8318530004020

524151.14 XXXXXXXXXXXXX

PLEASE RETURN THIS PORTION WITH YOUR REMITTANCE.

Total Net Due

Account Number		Service Period		From		To		DSO DB		FUEL CS		ECON CR		Georgia Power Company		HINESVILLE GA		31313	
8318530004020		03-27		04-24-95				0.934350X		0.015097		0.005660X				(912) 368-3376			
RATE	METER	PRES	PREV	KWH	KW HRS	BILL	ACT	ACT	ACT	ACT	ACT	ACT	ACT	ACT	ACT	ACT	ACT	ACT	Amount
520	E70396	3688	3506	19200	10060800	27816	24058	11096	11096	11096	11096	11096	11096	11096	11096	11096	11096	11096	524151.14
				EXCESS RKVA	3077														

CONSUMPTION FORWARDED METERS
E70398 8701 8359 19200

Sales Tax		Local Tax		0428		FORT STEWART		HERO RD		FORT STEWART GA		31313		PLEASE PAY BY		05-10-95		524151.14	
Current Bill Includes				Date of Bill		Service Name and Location												Total Net Due	

PLEASE RETAIN THIS PORTION FOR YOUR RECORDS.
REFERENCE REVERSE SIDE FOR EXPLANATIONS AND DESCRIPTIONS OF RATE NAMES, ABBREVIATIONS AND BILLING CODES.

$$\frac{\$524,151}{10,060,800 \text{ kwh}} = \$0.0521/\text{kwh}$$

A.5-B

PLEASE DO NOT STAPLE, FOLD OR PAPER CLIP

Georgia Power Company
96 Annex, Atlanta, Ga. 30396

1 0482 8

831853000402005556298430041195000000000

FORT STEWART
DPW
BLDG 1139
SERVICE BRANCH
FT STEWART GA

31314 REMIT TO ↑

Georgia Power Company
P. O. BOX 102473
68 ANNEX
ATLANTA GA 30368

555629.84 SVC 520

555629.84 XXXXXXXXXXXX

Total Net Due

Georgia Power Company

HINESVILLE GA 31313
(912) 368-3376

Account Number		Service Period		DSO DB		FUEL CS		ECON CR		HINESVILLE GA		31313	
		From	To							(912) 368-3376			
8318530004020		02-22	03-27-95										
RATE	METER	PRES	PREV	KWH	KW HRS	BILL	ACT	ACT					Amount
NAME	NO.	READ	READ	CONST	USED	DEM	DEM	RKVA	CD				555629.84
520	E70396	3506	3307	19200	11251200	27816	19238	8358					
EXCESS RKVA				1945									
CONSUMPTION FORWARDED METERS													
E70398		8359	7972	19200									

CONSUMPTION FORWARDED METERS
E70396 8359 7972 19200

Sales Tax		Local Tax		Date of Bill		Service Name and Location		PLEASE PAY BY		Total Net Due	
Current Bill Includes				0331		FORT STEWART DPW HERO RD FORT STEWART GA 31313		04-15-95		555629.84	

PLEASE RETAIN THIS PORTION FOR YOUR RECORDS.
REFERENCE REVERSE SIDE FOR EXPLANATIONS AND DESCRIPTIONS OF RATE NAMES, ABBREVIATIONS AND BILLING CODES.

$$\frac{\$555,630}{11,251,200 \text{ kwh}} = \$0.0494/\text{kwh}$$

A.5-9

GEORGIA POWER COMPANY

Full Use Service to Governmental Institutions

SCHEDULE "G-10"

AVAILABILITY:

Throughout the Company's service area from existing lines of adequate capacity, except that service under this tariff is not available to a customer who is served from an underground network system or who applies for service after December 29, 1981 at a service level below 12 kV.

APPLICABILITY:

Full use service to large Federal, State, and Municipal agencies and Institutions at a single delivery point through a single meter. This schedule is not applicable to Housing Projects or other Governmental agencies or Institutions whose service requirements are predominantly residential, nor is it available to any customer who has more than one meter per structure.

TYPE OF SERVICE:

Single or three phase, 60 hertz, at a standard voltage.

MONTHLY RATE - Energy Charge Including Demand Charge:

Base Charge \$55.00

All consumption (kWh) not greater than
300 hours times the billing demand:

First 50,000 kWh	@	6.00¢ per kWh
Next 150,000 kWh	@	5.82¢ per kWh
Next 800,000 kWh	@	4.42¢ per kWh
Over 1,000,000 kWh	@	4.10¢ per kWh

All consumption (kWh) in excess
of 300 hours times the billing
demand

@ 1.15¢ per kWh

Minimum Monthly Bill:

\$55.00 Base Charge plus \$8.00 per kW of Billing Demand, but not less than \$3,400.00 per month, plus excess kVAR charges and Fuel Cost Recovery as applied to the current month kWh.

FUEL COST RECOVERY:

The amount calculated at the above rate will be increased under the provisions of the Company's effective Fuel Cost Recovery Schedule, including any applicable adjustments.

DETERMINATION OF BILLING DEMAND:

The Billing Demand shall be based on the highest 30-minute kW measurement during the current month and the preceding eleven (11) months.

For the billing months of June through September, the Billing Demand shall be the greatest of:

- (1) The current actual demand, or,
- (2) Ninety-Five percent (95%) of the highest actual demand occurring in any previous applicable summer month (June through September), or,
- (3) Sixty percent (60%) of the highest actual demand occurring in any previous applicable winter month (October through May).

For the billing months of October through May, the Billing Demand shall be the greater of:

- (1) Ninety-Five percent (95%) of the highest summer month (June through September), or,
- (2) Sixty percent (60%) of the highest winter month (October through May), including the current month.

In no case shall the Billing Demand be less than the greatest of:

- (1) The contract minimum, or,
- (2) Fifty percent (50%) of the total contract capacity, or,
- (3) 3,000 kW for any customer applying for service under this rate subsequent to December 22, 1971, or,
- (4) 6,000 kW for any customer applying for service under this rate subsequent to December 29, 1981.

Where there is an indication of a power factor of less than 95% lagging, the Company may, at its option, install metering equipment to measure Reactive Demand. The Reactive Demand shall be the highest 30-minute kVAR measured during the month. The Excess Reactive Demand shall be kVAR which is in excess of one-third of the measured actual kW in the current month. The Company will bill excess kVAR at the rate of \$0.27 per excess kVAR.

TERM OF CONTRACT:

Not less than one year.

REVENUE ADJUSTMENT:

The bill calculated at the above rate is subject to change in such an amount as may be determined under the provisions of the Company's Revenue Adjustment Rider, Schedule "RA-1", as approved by the Georgia Public Service Commission or as may be later amended.

Service hereunder subject to Rules and Regulations for Electric Service on file with the Georgia Public Service Commission.

Sub station Capacity -
Evans -
Pembroke -

Effective with service rendered on and after December 4, 1991

FUEL OIL REPORTS

Denise Kelly
797-

Oil Report Jan 94

\$0.59 Budget
\$0.494 Actual 10/94

OH 174,119
Rec 41,987 From Hunter
Total 216,106
Used 66,349
OH 149,757

CEP 125,813
Ldry 23,044

ON HAND

Natural Gas Used 31,190 Cu.Ft.

\$

Wood Fuel Tons

\$ 10.82/Ton

OH -0-
Rec 7503.20
Total 7503.20
Used 6627.00
OH 875.20

Tickets 19776-20036

- May 96

Oil Report Feb 94

OH 149,757

CEP 112,135

Rec 5,861 Used Oil

Ldry 23,944

Total 155,618

Used 19,539 [(13,678 #20.1)(5861 Used Oil)]

OH 136,079

Natural Gas 2548 Cu. Ft.

Wood Fuel Tons

OH 875.20

Rec 8470.69

Tickets 20037-20328

Total 9345.89

Used 5845.89

OH 3500.00

Oil Report Mar 94

OH	136,079	CEP	106,399
Rec	-0-	Ldry	23,944
Total	136,079		
Used	5,736 #2 Oil (-0-Reclaimed Oil)		
OH	130,343		

Natural Gas 6160 Cu. ft.

Wood Fuel Tons

OH	3500.00	
Rec	6,608.03	Tickets 20329-20554
Total	10,108.03	
Used	5,884.00	
OH	4,224.03	

Oil Report April 94

OH	130,343	CEP	101,987
Rec	-0-	Ldry	23,944
Total	130,343		
Used	4,412 #2 (-0- Used Oil)		
OH	125,931		

Natural Gas 1,714,010 Cu. Ft.

Wood Fuel Tons

OH	4,224.03	
Rec	2996.84	Tickets 20555 - 20658
Total	7220.87	Ticket 20658 Void
Used	6870.87	
OH	350.00	

Oil Report May 94

OH 125,931

Rec -0-

Total 125,931

Used 4853 #2(-0-used oil)

OH 121,078

CEP 97,134

Ldry 23,944

Natural Gas 11,816,530 Cu.ft

Wood Fuel Tons

OH 350.00

Rec 6458.66

Total 6808.66

Used 5374.00

OH 1434.66

Tickets 20659-20885

Oil Report June 94

OH 121,078
Rec 181,200 From HAAF
Total 302,278
Used 184,388 #2 (-O- Used Oil)
O.H. 117,890

CEP 93,971
Ldry 23,919

Natural Gas 18,922,740 Cu.ft.

Wood Fuel Tons

OH 1434.66
Rec 1299.07
Total 2733.73
Used 613.00
OH 2120.73

Tickets 20886-20931

Oil Report July 94

OH 117,890
Rec 127,639 From HAAE
Total 245,529
Used 75,497 #2 oil (-0-used) ✓
OH 170,032

CEP 146,113
Ldry 23,919

Natural Gas 5570,730 Cu. ft. ✓

Wood Fuel Tons

OH 2120.73
Rec 7,272.60
Total 9,393.33
Used 6,052.00 ✓
OH 3,341.33

Oil Report Aug 94

OH	170,032		CEP	147,437
Rec	15,146	#2 Heating Oil from FS	Ldry	23,919
Rec	12,956	Used Oil		
Total	198,134			
Used	26,778	(Used Oil 12,956) (13,822 #2 oil)		
OH	171,356			

Natural Gas Used 874,295 Cu. Ft. ✓

Wood Fuel Tons

OH	3,341.33	
Rec.	5321.54	Tickets 21193-21383
Total	8662.87	
Used	8169.00 ✓	
OH	493.87	

Oil Report Sept 94

OH	171,356	CEP	110,370
Rec	3600 #2 Heating Oil from F.S.	Ldry	23,919
Rec	17,703 Used Oil		
Total	192,659		
Used	58,370 (17,703 Used Oil) (40,667 #2 Oil)		
OH	134,289		

Natural Gas Used 352,500 Cu. Ft.

Wood Fuel Tons

OH	493.87	
Rec	7,123.66	Tickets 21384-21644
Total	7617.47	
Used	4969.00 ✓	
OH	2648.47	

OIL REPORT OCT 94

OH	134,289		CEP	267,515
REC	199,753	From Contractor	Ldry	23,919
REL	18,775	Reclaimed Oil		
TOTAL	352,817			
USED	61,383	(18,775 Reclaimed Oil) (42,608 #2 Heating Oil)		
OH	291,434			358,215

NATURAL Gas USED 598,230 ✓

WOOD Fuel Tons

OH	2645.47	Ticket	21645	Void
REL	6999.43	Tickets	21646 - 21877	
TOTAL	9647.90			
USED	3947.00 ✓			
OH	5700.90			

OIL REPORT NOV 94

OH	291,434		CEP	237,717
REC	24,298	RECLAIMED OIL	LDY	23,919
TOTAL	315,732			
USED	54,096			
OH	261,636			

(24,298 Reclaimed oil) (29,798 #2 Heating oil)

See next page

NATURAL GAS 1,082,030 ✓

WOOD FUEL TONS

OH	5700.90
REC	5465.80
TOTAL	11,166.70
USED	5,000 ✓
OH	6166.70

TICKETS 21889 - 22080

CORRECTED COPY OF NOV 94 OIL REPORT

OH	291,434	CEP	251,631
REC	24,289	Used O.I.	LPRY 23,919
TOTAL	315,732		
USED	40,182	(24,298 Used O.I.)	(15,884 #2 O.I.)
OH	275,550		

CORRECTED COPY NECESSARY DUE TO A 13,914
GALLON ERROR IN TANK SOUNDING

OIL REPORT DEC 94

OH	261,636	CEP	215,460
REC	9,470 RECLAIMED OIL	LDRY	23,919
TOTAL	271,106		
USED	31,727 (9,470 RECLAIMED OIL) (22,257 # 2 HEATING OIL)		
OH	239,379		

OIL ACTUALLY USED WAS 13,914 GALLONS MORE THAN SHOWED IN USED COLUMN ABOVE, DUE TO ERROR IN NOV 94, REPORT.

NATURAL GAS 1,366,090 ✓

WOOD FUEL TONS

TICKETS

OH	6166.70	22081-22231
REC	4264.48	
TOTAL	10431.18	
USED	6631.18 ✓	
OH	3800.00	

OIL REPORT

JAN 95

OH 239,379

CEP 175,759

REC 8,891 Reclaimed oil

LDRY 23,879

TOTAL 248,270

USED 248,632

(8891 Reclaimed oil) (39,741 #2 Heating oil)

OH 199,638

NATURAL GAS

1,072,820 CF

WOOD FUEL TONS

OH 3800.00

TICKET 22232-22426

REC 4996.10

TICKET 22363 VOID

TOTAL 8796.10

USED 6100.10 ✓

OH 2696.00

Janas

POL MONTHLY REPORT

Diane ^{Jay} 5440

FORT STEWART - FS#2

OPENING INVENTORY

239,379

RECEIPTS

31,291

BLDG 1412 8891
POSTWIDE 22400

ISSUES

71,032

BLDG 1412 48632
POSTWIDE 22400

BOOK BALANCE

199,638

DIFFERENCE (+ or -)

-

CLOSING INVENTORY

199,638

FORT STEWART - FUEL OIL RECOVERED

8891

REMARKS:

DATE 2 Jul 95 SIGNATURE Dennis Kelly

OIL REPORT JAN 95

OH 239,379 CEP 175,759

REC 8,891 Reclaimed oil LDRY 23,879

TOTAL 248,270

USED 148,632 (8891 Reclaimed oil) (39,741 #2 Heating oil)

OH 199,638

NATURAL GAS 1,072,820 CF

WOOD FUEL TONS

OH 3800.00

TICKET 22232-22426

REC 4996.10

TICKET 22363 VOID

TOTAL 8796.10

USED 6100.10

OH 2696.00

OIL REPORT FEB 95

OH 199,638 CEP 230,461

REL 13,181 (RECLAIMED OIL) LDRY 23,819

REL 145,053 (#2 HEATING OIL FROM CONTRACTOR)

TOTAL 377,872 ✓

USED 123,592 (13,181 Reclaimed oil) (110,411 #2 HEATING OIL)

OH 254,280

NATURAL GAS 1159,730 CF ✓

WOOD FUEL TONS

OH 2696.00

TICKET 22427-22696

REL 7116.96

TICKET 22696 VOID

TOTAL 9812.96 ✓

USED 5024.00 ✓

OH 4788.96

OIL REPORT MARCH 95

OH 254,280 CIP 311057
REL 11,576 (RECLAIMED OIL) LDRY 23,819
TOTAL 265,856
USED 30,980 (11,576 RECLAIMED OIL) (19,404 #2 HEATING OIL)
OH 234,876

NATURAL GAS 518,890 CF

WOOD FUEL TONS TICKET 22697-22852
OH 4788.96
REL 4076.56
TOTAL 8865.52
USED 5723.00
OH 3142.52

OIL REPORT APRIL 95

OH 234,876 CEP 211145
REL 638 (FROM UNITS) LORY 23,819
TOTAL 235,514
USED 550 ✓ (#2 HEATING OIL)
OH 234,964

NATURAL GAS
12,995,190 CF

WOOD FUEL TONS

OH 3142.52 TICKET 22853 - 22888
REL 897.77
TOTAL 4040.29
USED 1869.00
OH 2171.29

OIL REPORT MAY 95

OH 234,964

CEP 234,989

REC 30,369 FROM UNITS

LDRY 23,819

REC 11,324 RECLAIMED OIL

TOTAL 276,657

USED 17,849 (11,324 RECLAIMED OIL) (6,525 #2 HEATING OIL)

OH 258,808

NATURAL GAS 550,120 CF

WOOD FUEL TONS

OH 2171.29

REC 4851.67

TOTAL 7022.96

USED 5322.00

OH 1700.96

Tickets 22890-23069

TICKET 22889 VOID

OIL REPORT JUNE 95

OH 258,808

CEP 223,523

REC 5,476

(RECLAIMED OIL) LDRY 23,819

TOTAL 264,284

USED 16,942

(5476 RECLAIMED OIL) (11,466 #2 HEATING OIL)

OH 247,342

NATURAL GAS 2,081,740 CF

WOOD FUEL TONS

OH 1700.96

TICKET 23270-23302

REC 6322.41

TICKET 23294+23295 VOID

TOTAL 8023.37

USED 4768.00 ✓

OH 3255.37

OIL REPORT July 95

OH 247,342

CEP 218,672

REL 10,615

LDRY 23,819

TOTAL 257,957

USED 15,466

(10,615 RECLAIMED OIL) (4,851 #2 HEATING OIL)

OH 242,491

NATURAL GAS

3,381,820 CU. FT.

WOOD FUEL TONS

OH 3255.37


TICKET 23303-23524

REL 5805.28


TOTAL 9060.65

USED 5316.00

OH 3744.65



DPW, SERVICE BRANCH
FAX NO. 767-7570



TO: Bill Todd, RS 'H, Jax, IL
FROM: Denise Kelly
DATE: 9 Aug 95
MESSAGE: As Requested

NO OF PAGES -----

NATURAL GAS BILLS

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

JULY, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER
686
5141

USAGE
5840
6647

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 12487

CONVERT TO THERMS (10.23 /MCF X NET MCF = 127,738)

MONTHLY CUSTOMER CHARGE (BASED ON 93/12 USAGE OF 347,985 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	127,738	6.950	8,877.79
I-20 SEASONAL SUPPLY COST	127,738	24.750	31,615.16
BASE TAKE OR PAY COST	127,738	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	127,738	.000	0.00
SUB TOTAL			41,592.95
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$41,592.95
TOTAL CURRENT CHARGES			\$41,592.95

Swis Redd
15 Aug 94
Danue Kelley

REPORT ID: 0000051 521 - JESUP-WAYCROSS
RUN DATE : 08/08/94

U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 16:
CHAB269-1

JULY

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.23		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1,	10,312	10,312	10,312
2	9,667	9,667	9,667
3	9,616	9,616	9,616
4	10,220	10,220	10,220
5	11,089	11,089	11,089
6	11,048	11,048	11,048
7	11,110	11,110	11,110
8	10,598	10,598	10,598
9	3,274	3,274	3,274
10	2,619	2,619	2,619
11	2,107	2,107	2,107
12	2,066	2,066	2,066
13	2,046	2,046	2,046
14	2,015	2,015	2,015
15	1,565	1,565	1,565
16	1,166	1,166	1,166
17	1,708	1,708	1,708
18	2,036	2,036	2,036
19	1,974	1,974	1,974
20	2,107	2,107	2,107
21	2,066	2,066	2,066
22	1,463	1,463	1,463
23	1,228	1,228	1,228
24	1,749	1,749	1,749
25	2,015	2,015	2,015
26	2,118	2,118	2,118
27	1,964	1,964	1,964
28	1,882	1,882	1,882
29	1,586	1,586	1,586
30	1,616	1,616	1,616
31	1,708	1,708	1,708
=====		=====	=====
DAILY TOTAL	127,738	127,738	127,738
EXCESS REALLOC			
GRAND TOTAL	127,738	127,738	127,738

A.5-38

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

AUGUST, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER
686
5141

USAGE
2852
3279

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 6131

CONVERT TO THERMS (10.22 /MCF X NET MCF = 62,658)

MONTHLY CUSTOMER CHARGE (BASED ON 93/12 USAGE OF 347,985 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	62,658	6.950	4,354.73
I-20 SEASONAL SUPPLY COST	62,658	23.500	14,724.63
BASE TAKE OR PAY COST	62,658	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	62,658	.000	0.00
SUB TOTAL			20,179.36
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$20,179.36
TOTAL CURRENT CHARGES			\$20,179.36

Swis Beck
19 Sep 94
Danise Kelly
A.5-39

REPORT ID: CHAH0051
UN DATE : 09/12/94

521 - JESUP-WAYCROSS

U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE
RUN TIME
CHAB269-1

AUGUST

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.22		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	2,238	2,238	2,238
2	2,259	2,259	2,259
3	2,167	2,167	2,167
4	2,320	2,320	2,320
5	2,259	2,259	2,259
6	1,635	1,635	1,635
7	2,003	2,003	2,003
8	2,075	2,075	2,075
9	2,575	2,575	2,575
10	2,678	2,678	2,678
11	1,870	1,870	1,870
12	1,421	1,421	1,421
13	1,216	1,216	1,216
14	2,064	2,064	2,064
15	2,494	2,494	2,494
16	2,259	2,259	2,259
17	2,197	2,197	2,197
18	2,095	2,095	2,095
19	1,921	1,921	1,921
20	1,870	1,870	1,870
21	1,942	1,942	1,942
22	2,064	2,064	2,064
23	2,146	2,146	2,146
24	2,054	2,054	2,054
25	2,146	2,146	2,146
26	1,533	1,533	1,533
27	1,267	1,267	1,267
28	1,758	1,758	1,758
29	2,085	2,085	2,085
30	2,075	2,075	2,075
31	1,972	1,972	1,972
DAILY TOTAL		62,658	62,658
EXCESS REALLOC			
GRAND TOTAL		62,658	62,658

A.5-40

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

SEPTEMBER, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER
686
5141

USAGE
2552
3214

TEMPERATURE FACT.
1.000000
1.000000

TOTAL MCF METERED 5766

CONVERT TO THERMS (10.24 /MCF X NET MCF = 59,041)

MONTHLY CUSTOMER CHARGE (BASED ON 93/12 USAGE OF 347,985 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	59,041	6.950	4,103.35
I-20 SEASONAL SUPPLY COST	59,041	20.430	12,062.08
BASE TAKE OR PAY COST	59,041	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	59,041	.000	0.00
SUB TOTAL			17,265.43
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$17,265.43
TOTAL CURRENT CHARGES			\$17,265.43

REPORT ID: CHAM0051 521 - JESUP-WAYCROSS
IN DATE : 10/07/94

U S ARMY - FT. STEWART

SEPTEMBER

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF 1
RUN TIME: 11:52
CHAB269-1

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.24		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	1,884	1,884	1,884
2	1,413	1,413	1,413
3	1,229	1,229	1,229
4	1,229	1,229	1,229
5	4,485	4,485	4,485
6	2,109	2,109	2,109
7	2,109	2,109	2,109
8	2,621	2,621	2,621
9	1,669	1,669	1,669
10	2,509	2,509	2,509
11	1,823	1,823	1,823
12	2,181	2,181	2,181
13	2,068	2,068	2,068
14	2,099	2,099	2,099
15	2,017	2,017	2,017
16	1,536	1,536	1,536
17	1,270	1,270	1,270
18	1,843	1,843	1,843
19	2,099	2,099	2,099
20	2,099	2,099	2,099
21	2,099	2,099	2,099
22	1,966	1,966	1,966
23	1,577	1,577	1,577
24	1,188	1,188	1,188
25	1,915	1,915	1,915
26	2,140	2,140	2,140
27	2,150	2,150	2,150
28	2,171	2,171	2,171
29	1,997	1,997	1,997
30	1,546	1,546	1,546
31	0	0	0
=====		=====	=====
AILY TOTAL		59,041	59,041
XCESS REALLOC			
RAND TOTAL		59,041	59,041

A.5-42

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O. BOX 105256 ATLANTA, GA 30348-5256

CMAA

INTERRUPTIBLE MONTHLY BILLING INVOICE

OCTOBER, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER

686

5141

USAGE

3251

4191

TEMPERATURE FACT.

1.0000000

1.0000000

TOTAL MCF METERED

7442

CONVERT TO THERMS (10.22 /MCF X NET MCF = 76,056)

MONTHLY CUSTOMER CHARGE (BASED ON 93/12 USAGE OF 347,985 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	76,056	6.950	5,285.89
I-20 SEASONAL SUPPLY COST	76,056	20.880	15,880.49

BASE TAKE OR PAY COST	76,056	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	76,056	.000	0.00

SUB TOTAL

22,266.38

.00 % SALES TAX

0.00

TOTAL CURRENT AMOUNT

\$22,266.38

TOTAL CURRENT CHARGES

\$22,266.38

*See Book
14 Nov 94
Dennis Kelley*

REPORT ID: CHA0051
RUN DATE : 11/10/94

521 - JESUP-WAYCROSS

U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 10:3
CHAB269-1

OCTOBER

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.22		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	1,318	1,318	1,318
2	1,778	1,778	1,778
3	2,187	2,187	2,187
4	2,432	2,432	2,432
5	2,361	2,361	2,361
6	2,136	2,136	2,136
7	1,523	1,523	1,523
8	1,308	1,308	1,308
9	1,410	1,410	1,410
10	1,911	1,911	1,911
11	3,771	3,771	3,771
12	3,086	3,086	3,086
13	7,992	7,992	7,992
14	2,780	2,780	2,780
15	1,921	1,921	1,921
16	2,627	2,627	2,627
17	3,689	3,689	3,689
18	2,657	2,657	2,657
19	2,391	2,391	2,391
20	2,310	2,310	2,310
21	1,574	1,574	1,574
22	1,318	1,318	1,318
23	1,911	1,911	1,911
24	2,310	2,310	2,310
25	2,361	2,361	2,361
26	2,862	2,862	2,862
27	3,516	3,516	3,516
28	2,780	2,780	2,780
29	1,564	1,564	1,564
30	1,952	1,952	1,952
31	2,320	2,320	2,320
=====		=====	=====
DAILY TOTAL	76,056	76,056	76,056
EXCESS REALLOC			
GRAND TOTAL	76,056	76,056	76,056

A.5-44

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

NOVEMBER, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER

686

5141

USAGE

4710

5805

TEMPERATURE FACT.

1.0000000

1.0000000

TOTAL MCF METERED

10515

CONVERT TO THERMS (10.23 /MCF X NET MCF = 107,571)

MONTHLY CUSTOMER CHARGE (BASED ON 93/12 USAGE OF 347,985 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	107,571	6.950	7,476.18
I-20 SEASONAL SUPPLY COST	107,571	23.540	25,322.21
BASE TAKE OR PAY COST	107,571	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	107,571	.000	0.00
SUB TOTAL			33,898.39
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$33,898.39
TOTAL CURRENT CHARGES			\$33,898.39

Does Debt
19 Nov 94
Dennis Kelly
A.5-45

REPORT ID: CHAB0051 521 - JESUP-WAYCROSS
RUN DATE : 12/09/94
U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF 3
RUN TIME: 08:33
CHAB269-1

NOVEMBER

TOTAL VOLUMES METERED WITH BTU FACTOR OF		I-20 INTERRUPTIBLE TOTAL USED		I-20 SEASONAL SUPPLY USED	
10.23					
1	3,509	3,509	3,509	3,509	3,509
2	5,115	5,115	5,115	5,115	5,115
3	3,253	3,253	3,253	3,253	3,253
4	3,212	3,212	3,212	3,212	3,212
5	2,189	2,189	2,189	2,189	2,189
6	2,660	2,660	2,660	2,660	2,660
7	3,325	3,325	3,325	3,325	3,325
8	2,813	2,813	2,813	2,813	2,813
9	2,639	2,639	2,639	2,639	2,639
10	4,123	4,123	4,123	4,123	4,123
11	4,941	4,941	4,941	4,941	4,941
12	2,885	2,885	2,885	2,885	2,885
13	2,558	2,558	2,558	2,558	2,558
14	3,192	3,192	3,192	3,192	3,192
15	2,926	2,926	2,926	2,926	2,926
16	3,683	3,683	3,683	3,683	3,683
17	4,338	4,338	4,338	4,338	4,338
18	2,742	2,742	2,742	2,742	2,742
19	2,486	2,486	2,486	2,486	2,486
20	2,926	2,926	2,926	2,926	2,926
21	3,079	3,079	3,079	3,079	3,079
22	3,632	3,632	3,632	3,632	3,632
23	5,545	5,545	5,545	5,545	5,545
24	5,759	5,759	5,759	5,759	5,759
25	4,164	4,164	4,164	4,164	4,164
26	4,051	4,051	4,051	4,051	4,051
27	2,926	2,926	2,926	2,926	2,926
28	3,049	3,049	3,049	3,049	3,049
29	3,570	3,570	3,570	3,570	3,570
30	6,281	6,281	6,281	6,281	6,281
31	0	0	0	0	0
=====		=====		=====	
AILY TOTAL		107,571		107,571	
XCESS REALLOC		107,571		107,571	
RAND TOTAL		107,571		107,571	

A.5-46

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

DECEMBER, 1994

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER

686

5141

USAGE

8560

10224

TEMPERATURE FACT.

1.0000000

1.0000000

TOTAL MCF METERED 18784

CONVERT TO THERMS (10.23 /MCF X NET MCF = 192,157)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	192,157	6.950	13,354.91
I-20 SEASONAL SUPPLY COST	192,157	23.700	45,541.21

BASE TAKE OR PAY COST	192,157	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	192,157	.000	0.00

SUB TOTAL 59,996.12

.00 % SALES TAX 0.00

TOTAL CURRENT AMOUNT \$59,996.12

TOTAL CURRENT CHARGES \$59,996.12

REPORT ID: 0051 521 - JESUP-WAYCROSS
RUN DATE : 01/12/95

U S ARMY - FT. STEWART

DECEMBER

ATLANTA LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 10:
CHAB269-1

	TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.23	I-20 INTERRUPTIBLE ¹ TOTAL USED	SEASONAL SUPPLY USED
1	7,202	7,202	7,202
2	4,348	4,348	4,348
3	2,803	2,803	2,803
4	3,355	3,355	3,355
5	3,734	3,734	3,734
6	3,396	3,396	3,396
7	3,816	3,816	3,816
8	3,724	3,724	3,724
9	3,171	3,171	3,171
10	2,639	2,639	2,639
11	6,731	6,731	6,731
12	9,043	9,043	9,043
13	8,961	8,961	8,961
14	7,785	7,785	7,785
15	6,731	6,731	6,731
16	6,997	6,997	6,997
17	5,759	5,759	5,759
18	6,711	6,711	6,711
19	9,299	9,299	9,299
20	7,079	7,079	7,079
21	9,555	9,555	9,555
22	10,660	10,660	10,660
23	8,378	8,378	8,378
24	7,683	7,683	7,683
25	5,309	5,309	5,309
26	6,118	6,118	6,118
27	7,069	7,069	7,069
28	6,230	6,230	6,230
29	4,685	4,685	4,685
30	7,478	7,478	7,478
31	5,708	5,708	5,708
=====			
DAILY TOTAL	192,157	192,157	192,157
EXCESS REALLOC			
GRAND TOTAL	192,157	192,157	192,157

A.5-48

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O. BOX 105256 ATLANTA, GA 30348-5256

CMAA

INTERRUPTIBLE MONTHLY BILLING INVOICE

JANUARY, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4630267

METER NUMBER
686
5141

USAGE
10681
12680

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 23361

CONVERT TO THERMS (10.21 /MCF X NET MCF = 238,514)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	238,514	6.950	16,576.72
I-20 SEASONAL SUPPLY COST	238,514	23.070	55,025.18

BASE TAKE OR PAY COST	238,514	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	238,514	.000	0.00

SUB TOTAL 72,701.90

.00 % SALES TAX 0.00

TOTAL CURRENT AMOUNT \$72,701.90

TOTAL CURRENT CHARGES \$72,701.90

*Swiss Dred
17-1-95
Denise Kelly*

REPORT ID: CHAM0051 521 - JESUP-WAYCROSS
IN DATE : 02/13/95
U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 06:50
CHAB269-1

JANUARY

	TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.21	I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	4,411	4,411	4,411
2	6,953	6,953	6,953
3	8,964	8,964	8,964
4	11,221	11,221	11,221
5	11,313	11,313	11,313
6	4,390	4,390	4,390
7	5,095	5,095	5,095
8	8,648	8,648	8,648
9	8,239	8,239	8,239
10	7,024	7,024	7,024
11	6,238	6,238	6,238
12	4,748	4,748	4,748
13	2,930	2,930	2,930
14	5,166	5,166	5,166
15	7,147	7,147	7,147
16	7,392	7,392	7,392
17	6,749	6,749	6,749
18	6,443	6,443	6,443
19	7,821	7,821	7,821
20	8,352	8,352	8,352
21	7,831	7,831	7,831
22	8,025	8,025	8,025
23	11,333	11,333	11,333
24	11,915	11,915	11,915
25	9,904	9,904	9,904
26	9,495	9,495	9,495
27	7,167	7,167	7,167
28	5,728	5,728	5,728
29	5,809	5,809	5,809
30	10,812	10,812	10,812
31	11,251	11,251	11,251
=====			
AILY TOTAL	238,514	238,514	238,514
XCESS REALLOC			
RAND TOTAL	238,514	238,514	238,514

A.5-50

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

CMA

INTERRUPTIBLE MONTHLY BILLING INVOICE

FEBRUARY, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4530267

METER NUMBER
686
5141

USAGE
9591
11318

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 20909

CONVERT TO THERMS (10.23 /MCF X NET MCF = 213,897)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	213,897	6.950	14,865.84
I-20 SEASONAL SUPPLY COST	213,897	20.920	44,747.25
BASE TAKE OR PAY COST	213,897	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	213,897	.000	0.00
SUB TOTAL			60,713.09
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$60,713.09
TOTAL CURRENT CHARGES			\$60,713.09

SanDiego
21 Mar 95
Denise Kelly

REPORT ID: CHAM0051 521 - JESUP-MAYCROSS
UN DATE : 03/14/95
U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 11:3
CMAB269-1

FEBRUARY

	TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.23	I-20		I-20 SEASONAL SUPPLY USED
		INTERRUPTIBLE TOTAL USED	INTERRUPTIBLE TOTAL USED	
1	8,685	8,685	8,685	8,685
2	5,964	5,964	5,964	5,964
3	4,655	4,655	4,655	4,655
4	9,094	9,094	9,094	9,094
5	9,483	9,483	9,483	9,483
6	12,818	12,818	12,818	12,818
7	15,232	15,232	15,232	15,232
8	15,181	15,181	15,181	15,181
9	11,447	11,447	11,447	11,447
10	6,956	6,956	6,956	6,956
11	6,690	6,690	6,690	6,690
12	6,977	6,977	6,977	6,977
13	8,614	8,614	8,614	8,614
14	7,304	7,304	7,304	7,304
15	5,023	5,023	5,023	5,023
16	3,570	3,570	3,570	3,570
17	3,703	3,703	3,703	3,703
18	6,097	6,097	6,097	6,097
19	5,862	5,862	5,862	5,862
20	6,251	6,251	6,251	6,251
21	9,105	9,105	9,105	9,105
22	8,399	8,399	8,399	8,399
23	6,588	6,588	6,588	6,588
24	5,667	5,667	5,667	5,667
25	6,128	6,128	6,128	6,128
26	5,463	5,463	5,463	5,463
27	9,289	9,289	9,289	9,289
28	3,652	3,652	3,652	3,652
29	0	0	0	0
30	0	0	0	0
31	0	0	0	0
=====				
DAILY TOTAL	213,897	213,897	213,897	213,897
EXCESS REALLOC				
RAND TOTAL	213,897	213,897	213,897	213,897

A.5-52

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

CMAI

INTERRUPTIBLE MONTHLY BILLING INVOICE

MARCH, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4530267

METER NUMBER
686
5141

USAGE
7176
8484

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 15660

CONVERT TO THERMS (10.21 /MCF X NET MCF = 159,888)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	159,888	6.950	11,112.22
I-20 SEASONAL SUPPLY COST	159,888	19.980	31,945.62
BASE TAKE OR PAY COST	159,888	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	159,888	.000	0.00
SUB TOTAL			44,157.84
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$44,157.84
TOTAL CURRENT CHARGES			\$44,157.84

Swes Peak
18 Apr 95
Denise Miller

REPORT ID: CHAM0051
UN DATE : 04/11/95

521 - JESUP-MAYCROSS

U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 08:0
CHAB269-1

MARCH

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.21		I-20 TOTAL USED	I-20 SEASONAL SUPPLY USED
1	4,421	4,421	4,421
2	5,901	5,901	5,901
3	4,993	4,993	4,993
4	4,717	4,717	4,717
5	5,922	5,922	5,922
6	4,482	4,482	4,482
7	4,115	4,115	4,115
8	6,003	6,003	6,003
9	10,169	10,169	10,169
10	11,313	11,313	11,313
11	5,758	5,758	5,758
12	4,809	4,809	4,809
13	4,727	4,727	4,727
14	4,799	4,799	4,799
15	4,104	4,104	4,104
16	4,574	4,574	4,574
17	3,655	3,655	3,655
18	4,390	4,390	4,390
19	5,381	5,381	5,381
20	4,625	4,625	4,625
21	4,462	4,462	4,462
22	4,809	4,809	4,809
23	4,809	4,809	4,809
24	4,492	4,492	4,492
25	4,390	4,390	4,390
26	5,381	5,381	5,381
27	4,625	4,625	4,625
28	4,462	4,462	4,462
29	4,809	4,809	4,809
30	4,809	4,809	4,809
31	3,982	3,982	3,982
=====			
AILY TOTAL	159,888	159,888	159,888
XCESS REALLOC			
RAND TOTAL	159,888	159,888	159,888

A.5-54

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O. BOX 105256 ATLANTA, GA 30348-5256

CMA

INTERRUPTIBLE MONTHLY BILLING INVOICE

APRIL, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4530267

METER NUMBER
686
5141

USAGE
10595
13917

TEMPERATURE FACT.
1.0000000
1.0000000

TOTAL MCF METERED 24512

CONVERT TO THERMS (10.21 /MCF X NET MCF = 250,269)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	250,269	6.950	17,393.70
I-20 SEASONAL SUPPLY COST	250,269	20.840	52,156.06

BASE TAKE OR PAY COST	250,000	.000	0.00
EXCESS TAKE OR PAY COST	269	.000	0.00
BASE ENVIRONMENTAL RESPONSE COST	250,000	.000	0.00
EXCESS ENVIRONMENTAL RESPONSE COST	269	.000	0.00

SUB TOTAL 70,649.76

.00 % SALES TAX 0.00

TOTAL CURRENT AMOUNT \$70,649.76

TOTAL CURRENT CHARGES \$70,649.76

*Swishfield
18 May 95
Denise Kelly*

REPORT ID: CHAH0051 521 - JESUP-WAYCROSS
RUN DATE : 05/09/95
U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 12:2
CHAB269-1

APRIL

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.21		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	13,610	13,610	13,610
2	13,610	13,610	13,610
3	13,610	13,610	13,610
4	13,610	13,610	13,610
5	13,610	13,610	13,610
6	14,008	14,008	14,008
7	14,223	14,223	14,223
8	14,365	14,365	14,365
9	16,407	16,407	16,407
10	14,468	14,468	14,468
11	12,763	12,763	12,763
12	12,783	12,783	12,783
13	13,018	13,018	13,018
14	12,375	12,375	12,375
15	11,731	11,731	11,731
16	12,038	12,038	12,038
17	4,880	4,880	4,880
18	2,553	2,553	2,553
19	2,461	2,461	2,461
20	2,226	2,226	2,226
21	1,725	1,725	1,725
22	1,358	1,358	1,358
23	2,011	2,011	2,011
24	3,043	3,043	3,043
25	3,339	3,339	3,339
26	2,746	2,746	2,746
27	2,491	2,491	2,491
28	1,899	1,899	1,899
29	1,399	1,399	1,399
30	1,909	1,909	1,909
31	0	0	0
DAILY TOTAL		250,269	250,269
EXCESS REALLOC			
GRAND TOTAL		250,269	250,269

A.5-56

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

MAY, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4530267

METER NUMBER	USAGE	TEMPERATURE FACT.
686	3038	1.0000000
5141	3586	1.0000000

TOTAL MCF METERED 6624

CONVERT TO THERMS (10.24 /MCF X NET MCF = 67,830)

MONTHLY CUSTOMER CHARGE (BASED ON 94/06 USAGE OF 310,484 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	67,830	6.950	4,714.19
I-20 SEASONAL SUPPLY COST	67,830	21.990	14,915.82
BYPASS RECOVERY FACTOR	67,830	.050	33.92
SUB TOTAL			20,763.93
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$20,763.93
TOTAL CURRENT CHARGES			\$20,763.93

*Sup Deck
19 June 95*

REPORT ID: CHM0051
RUN DATE : 06/09/95

521 - JESUP-WAYCROSS

U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF
RUN TIME: 09:
CHAB269-1

MAY

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.24		I-20 TOTAL USED	I-20 SEASONAL SUPPLY USED
1)	2,314	2,314	2,314
2	2,509	2,509	2,509
3	2,509	2,509	2,509
4	2,284	2,284	2,284
5	1,669	1,669	1,669
6	1,413	1,413	1,413
7	2,314	2,314	2,314
8	3,205	3,205	3,205
9	2,109	2,109	2,109
10	2,109	2,109	2,109
11	2,386	2,386	2,386
12	1,792	1,792	1,792
13	1,280	1,280	1,280
14	2,028	2,028	2,028
15	2,468	2,468	2,468
16	2,294	2,294	2,294
17	2,273	2,273	2,273
18	2,314	2,314	2,314
19	1,853	1,853	1,853
20	1,710	1,710	1,710
21	2,099	2,099	2,099
22	2,468	2,468	2,468
23	2,601	2,601	2,601
24	2,376	2,376	2,376
25	2,376	2,376	2,376
26	1,987	1,987	1,987
27	1,751	1,751	1,751
28	1,731	1,731	1,731
29	2,365	2,365	2,365
30	2,601	2,601	2,601
31	2,642	2,642	2,642
=====		=====	=====
DAILY TOTAL	67,830	67,830	67,830
EXCESS REALLOC			
GRAND TOTAL	67,830	67,830	67,830

A.5-58

ATLANTA GAS LIGHT COMPANY - GEORGIA NATURAL GAS - SAVANNAH NATURAL GAS COMPANY
P.O.BOX 105256 ATLANTA, GA 30348-5256

INTERRUPTIBLE MONTHLY BILLING INVOICE

JUNE, 1995

U S ARMY - FT. STEWART
ARTILLERY FIRING CTR

ACCOUNT 23558-0300-0-8
I-20 COMMERCIAL RATE

DISTRICT 4530267

METER NUMBER	USAGE	TEMPERATURE FACT.
686	4548	1.0000000
5141	5173	1.0000000

TOTAL MCF METERED 9721

CONVERT TO THERMS (10.22 /MCF X NET MCF = 99,348)

MONTHLY CUSTOMER CHARGE (BASED ON 95/04 USAGE OF 250,269 THERMS) \$1,100.00

	THERMS	CENTS/THM	AMOUNT
I-20 COMMODITY CHARGE	99,348	6.950	6,904.69
I-20 SEASONAL SUPPLY COST	99,348	22.140	21,995.65
BYPASS RECOVERY FACTOR	99,348	.050	49.67
SUB TOTAL			30,050.01
.00 % SALES TAX			0.00
TOTAL CURRENT AMOUNT			\$30,050.01
TOTAL CURRENT CHARGES			\$30,050.01

REPORT ID: CHAM0051 521 - JESUP-WAYCROSS
RUN DATE : 07/10/95
U S ARMY - FT. STEWART

ATLANTA GAS LIGHT COMPANY
INTERRUPTIBLE CUSTOMER WORKSHEET (THERMS)
ACCOUNT # 23558 0300 0 8

PAGE 1 OF 1
RUN TIME: 10:30
CMAB269-1

JUNE

TOTAL VOLUMES METERED WITH BTU FACTOR OF 10.22		I-20 INTERRUPTIBLE TOTAL USED	I-20 SEASONAL SUPPLY USED
1	2,473	2,473	2,473
2	2,085	2,085	2,085
3	1,758	1,758	1,758
4	3,178	3,178	3,178
5	8,953	8,953	8,953
6	3,260	3,260	3,260
7	2,494	2,494	2,494
8	2,269	2,269	2,269
9	1,983	1,983	1,983
10	1,543	1,543	1,543
11	2,667	2,667	2,667
12	12,826	12,826	12,826
13	4,527	4,527	4,527
14	2,167	2,167	2,167
15	2,279	2,279	2,279
16	1,983	1,983	1,983
17	1,533	1,533	1,533
18	2,156	2,156	2,156
19	2,514	2,514	2,514
20	2,340	2,340	2,340
21	2,126	2,126	2,126
22	2,310	2,310	2,310
23	1,574	1,574	1,574
24	1,502	1,502	1,502
25	1,789	1,789	1,789
26	2,300	2,300	2,300
27	2,289	2,289	2,289
28	2,064	2,064	2,064
29	4,946	4,946	4,946
30	13,460	13,460	13,460
31	0	0	0
DAILY TOTAL		99,348	99,348
EXCESS REALLOC		99,348	99,348
RAND TOTAL		99,348	99,348

A.5-60

BOILER LOGS

For use of this form, see AR 420-49; the proponent agency is USACE.

For use of this form, see AR 420-49; the proponent agency is USACE.

[illegible]

REMARKS
*N^o 2 OIL; 9709; RECLAIMED OIL FS: 11494

WOOD: 2395; OIL: 118; NAT GAS: 8944

SEE 01/17/55 CONF

FOR INSTRUCTIONS*

1

A.1 NOV 72 3967

REPLACES DA FORM 5-02, 1 JUN 52, WHICH WILL BE USED.

1

1

10

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)
For use of this form, see AR 420-49; the proponent agency is USACE.

For use of this form, see AR 420.49; the proponent agency is USACE.

100N HEADQUARTERS FORT STEWART
FORT STEWART, GEORGIA 31313

PLANT

11/15
LDG. mn

MONTH

14/

95

7

DATE	STEAM PRODUCED										WATER TO BOILER	#2 FUEL USED GAL	M.G. PER TNT	OUTSIDE TEMP.			FEEDWATER HEATER			%CO ₂			FLUE GAS TEMPERATURE				TEMP. SUPPLY °F.	TUBES CLEANED OF TIMES	PREVENT MAINT. CHECK	#4	CUMUL					
	STEAM PRESSURE		BOILER		TOTAL	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.				1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.						1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.
	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.																																
	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.				1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.						1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.
1	200	616	616	616	1232	—	—	—	—	—	—	763201	67	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
2	200	200	200	200	847	—	—	—	—	—	—	555800	74	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
3	200	864	864	864	864	—	—	—	—	—	—	628400	71	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
4	200	864	864	864	864	—	—	—	—	—	—	614510	55	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
5	200	864	864	864	864	—	—	—	—	—	—	628400	45	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
6	200	864	864	864	864	—	—	—	—	—	—	628400	52	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
7	200	864	864	864	864	—	—	—	—	—	—	628400	66	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
8	200	864	864	864	864	—	—	—	—	—	—	628400	54	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
9	200	864	864	864	864	—	—	—	—	—	—	628400	54	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
10	200	864	864	864	864	—	—	—	—	—	—	628400	54	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
11	200	864	864	864	864	—	—	—	—	—	—	628400	54	—	108	110	113	114	115	344	108	108	108	108	374	0	0	0	120	120	120	120				
12	200	864	864	864																																

REMARKS					
		APPROVED BY.	DATE	POST ENGINEER	DATE
FUEL USED DURING MONTH (STANDARD TONS)					
PREPARED BY		DATE			
SEE REVERSE SIDE FOR INSTRUCTIONS					

A.5-64

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-49; the proponent agency is USACE.

DATE	STEAM PRODUCED										WATER-TO-STEAM RATIO	FUEL USED (GAL.)	NAT GAS EVAP. (GAL.)	OUTSIDE TEMP. (°F)		FEEDWATER HEATER		% CO ₂		FLUE GAS TEMPERATURE					TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	MONTH	CHILL WATER 11/14																																																																																																																																																																																																																																																																																																																																																																																																			
	STEAM PRESSURE (LB.)		BOILER						TOTAL (1,000 LB.)	1,000 LB.				2,000 LB.	3,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.					1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.	1

REMARKS: * N^o 2 OIL 7062; RECEIVED OIL F.S. 0

APPROVED BY: *Bob H. Falk* DATE: 12 NOV 95

POST ENGINEER: *Bob H. Falk* DATE: 12 NOV 95

FORM 1 NOV 72 3957 REPLACES DA FORM 5-96, 1 JUN 58, WHICH WILL BE USED.

A.5-66

MONTH		SEPT 1995		CHILL WATER m/u	
TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	1211	1221	1221	1221
6	FU				2700
6	DR				3000
6	FU				2800
6	DR				2600
6	FU				4100
6	DR				3300
6	FU				2200
6	DR				3200
6	FU				2400
6	DR				2600
6	FU				2900
6	DR				2700
6	FU				2900
6	DR				3600
6	FU				2600
6	DR				2600
6	FU				3000
6	DR				3100
6	FU				3000
6	EB				3600
6	DR				3700
6	FU				2600
6	FU				3100
6	FU				3800
6	FU				3600
6	DR				2200
6	DR				2900
6	DR				3000
6	RS				2700
6	RS				2500
180					87,900
6					4100
6					3200
6					2930
906					
MEAN					DATE

[illegible]

A.5-69

FAC IES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-48; the proponent agency is USACE.

DATE	STEAM PRODUCED				TOTAL 1,000 LB.	FEED- WATER TO BOILER 1,000 LB.	FUEL USED LB. M.C.F. GAL.	INST # 2	HEADQUARTERS FORT STEWART FORT STEWART, GEORGIA 31313	PLANT CEP	BLDG. NO. 1412	MONTH June 1998	TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	CUNA																																																																																						
	BOILER		1,000 LB.	1,000 LB.																																																																																																	
	1	2																																																																																																			
1	200	1265	173	173	1265	173	74	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
2	200	1274	173	173	1274	173	112	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
3	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
4	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
5	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
6	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
7	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
8	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
9	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
10	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
11	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
12	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200
13	200	1282	173	173	1282	173	3054	16410	34	0	100	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184																

A.5-70

21 705 11 1010

For use of this form, see AR 420-49; the appointing agency is the Chief of Engineers.

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

PLANT: **CEP** BLDG. NO.: **1412** MONTH: **MAY - 1995**

INC. LOCATION: **Ft. Stewart**

DATE	STEAM PRODUCER				TOTAL 1,000 LB.	WATER 1,000 LB.	FUEL 1,000 LB.	N.G. 1,000 LB.	OUTSIDE TEMP.	FEEDWATER TEMP.	HANDUP GAL.	FLUE GAS TEMPERATURE				TEMP. SUPPLY	TURNS CLEANED NUMBER OF TIMES	PREVENT CHECK	N° A OIS	CUMULATIVE
	STEAM PRESSURE LB.	1	2	3								1	2	3	4					
1	1230				1231	168	103	21930	86		5980				465	375	6	CCP	14	8100
2	220				1177	157	275	2287	76	0	6010				465	375	6	CCP	39	9000
3	220				1244	172	159	4044	71	0	6010				465	375	6	CCP	21	10200
4	220				1318	182	112	3230	71	0	4060				465	375	6	CCP	13	5200
5	200				1231	168	109	5060	83	0	4060				465	375	6	CCP	13	5200
6	200				1226	167	117	3090	75	0	4060				465	375	6	CCP	16	1100
7	200				1214	165	138	5880	78	0	3010				465	375	6	CCP	19	700
8	200				1043	137	397	4580	82	0	6450				465	375	6	CCP	53	800
9	200				1229	166	219	3190	82	0	3750				465	375	6	CCP	29	500
10	200				1154	165	199	2050	84	0	8950				465	375	6	CCP	29	1100
11	200				1232	164	102	6450	77	0	8110				465	375	6	CCP	41	900
12	200				1193	160	1000	10210	85	3223	8800				465	375	6	CCP	39	900
13	200				1192	156	1000	5510	85	2238	6450				465	375	6	CCP	278	900
14	200				1189	154	1000	7220	89	3516	10380				465	375	6	CCP	432	1140
15	200				1027	125	1083	7270	87	2347	2290				465	375	6	CCP	219	350
16	200				1228	169	108	5270	88	0	11300				465	375	6	CCP	1	2340
17	200				1187	163	1100	9000	87	0	7650				465	375	6	CCP	13	1150
18	200				1193	162	1120	3260	89	0	5080				465	375	6	CCP	15	1000
19	200				1170	180	1078	6370	85	0	7570				465	375	6	CCP	10	1000
20	200				1210	166	1053	6370	76	0	7490				465	375	6	CCP	7	1100
21	200				1182	163	1240	3500	74	0	7200				465	375	6	CCP	0	2460
22	200				1230	167	144	5120	76	0	6610				465	375	6	CCP	7	1730
23	200				1265	170	257	7783	74	0	5550				465	375	6	CCP	34	1750
24	200				1222	173	175	194	72	0	7250				465	375	6	CCP	26	2200
25	200				1251	172	395	6680	81	0	8200				465	375	6	CCP	45	2200
26	200				1222	184	1000	1910	81	0	4450				465	375	6	CCP	0	1810
27	200				1225	185	164	12400	87	0	6470				465	375	6	CCP	1	800
28	200				1195	182	164	13785	87	0	5800				465	375	6	CCP	22	540
29	200				1263	189	261	15255	87	0	6100				465	375	6	CCP	34	540
30	200				1295	180	452	1660	88	0	7490				465	375	6	CCP	60	1100
31	200				1274	185	292	7610	83	0	5790				465	375	6	CCP	39	500
TOTAL	6200	7441	1116	3588	3774	5322	1789	45980	2520	11224	92680				465	375	186		1906	69620
MAXIMUM	200	7441	1116	3588	3774	5322	1789	45980	2520	11224	92680				465	375	186		1906	69620
MINIMUM	200	7441	1116	3588	3774	5322	1789	45980	2520	11224	92680				465	375	186		1906	69620
AVERAGE	200	7441	1116	3588	3774	5322	1789	45980	2520	11224	92680				465	375	186		1906	69620
EVAPORATION LB. STEAM PER LB. STD. FUEL																				

PREPARED BY: **1** DATE: **11/16/95**

APPROVED BY: **1** DATE: **11/16/95**

PORT ENGINEER: **1** DATE: **11/16/95**

REMARKS: **1**

DA FORM 3967

REPLACES DA FORM 3967 1 JUN 88 WHICH WILL BE USED.

A.5-70

100% of Rock

For use of this term, see AR 420-49; the proponent agency is the Corps of Engineers.

For use of this term, see AR 420-49; the proponent agency is the Corps of Engineers.

**SEE REVERSE SIDE
FOR INSTRUCTIONS**

DA FORM 3967, NOV 72

REPLACES DA FORM 8-98 1 JUN 88 WHICH WILL BE USED.

$\frac{1}{2} \times 10 = 5$

A.5-71

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)
 For use of this form, see AR 420-49; the responsible agency is the Corps of Engineers.

STATION **REPORT** **BLDG. NO.** **MONTH**

FT. STEWART **CEP** **1412** **FEB. 95**

DATE	STEAM PRODUCED				TOTAL 1,000 LB.	WATER TO BOILER 1,000 LB.	#2 FUEL OIL GAL.	MIS. FUEL OIL GAL.	OUTSIDE TEMP. AV.	FEEDWATER HEATER		WATER		FLUE GAS TEMPERATURE		TEMP. H.W. SUPPLY	TURNS CLEANED NUMBER OF TIMES	PREVENT H.W. CHECK	#4 O/S	O/M/V
	STEAM PRESSURE LB.	1,000 LB.	1,000 LB.	1,000 LB.						TEMP. °F.	PRESS. PSI	TEMP. °F.	INLET °F.	OUTLET °F.	INLET °F.					
1	200	1860	4	1740	1860	228	1545	16940	47	-0-	1717	14990	7.4	7.4	420	378	6	CCP	203	355
2	200	1740	4	1624	1740	150	1325	1610	56	1982	14990	7.4	7.4	420	376	6	CCP	131	945	
3	200	1555	4	1404	1555	166	8550	1610	62	1982	14990	7.4	7.4	420	376	6	CCP	344	340	
4	200	1555	4	1404	1555	166	8550	1610	44	1506	14990	7.4	7.4	420	376	6	CCP	212	10	
5	200	1555	4	1404	1555	166	8550	1610	37	-	14990	7.4	7.4	420	376	6	CCP	2	200	
6	200	1555	4	1404	1555	166	8550	1610	47	-	14990	7.4	7.4	420	376	6	CCP	2	700	
7	200	1555	4	1404	1555	166	8550	1610	35	-	14990	7.4	7.4	420	376	6	CCP	-	760	
8	200	1555	4	1404	1555	166	8550	1610	58	1433	14990	7.4	7.4	420	376	6	CCP	40	700	
9	200	1555	4	1404	1555	166	8550	1610	49	1433	14990	7.4	7.4	420	376	6	CCP	223	200	
10	200	1555	4	1404	1555	166	8550	1610	45	1433	14990	7.4	7.4	420	376	6	CCP	597	300	
11	200	1555	4	1404	1555	166	8550	1610	59	-	14990	7.4	7.4	420	376	6	CCP	212	200	
12	200	1555	4	1404	1555	166	8550	1610	73	-	14990	7.4	7.4	420	376	6	CCP	132	900	
13	200	1555	4	1404	1555	166	8550	1610	64	-	14990	7.4	7.4	420	376	6	CCP	80	330	
14	200	1555	4	1404	1555	166	8550	1610	50	-	14990	7.4	7.4	420	376	6	CCP	145	200	
15	200	1555	4	1404	1555	166	8550	1610	58	-	14990	7.4	7.4	420	376	6	CCP	217	200	
16	200	1555	4	1404	1555	166	8550	1610	58	-	14990	7.4	7.4	420	376	6	CCP	264	100	
17	200	1555	4	1404	1555	166	8550	1610	47	-	14990	7.4	7.4	420	376	6	CCP	264	300	
18	200	1555	4	1404	1555	166	8550	1610	39	-	14990	7.4	7.4	420	376	6	CCP	166	300	
19	200	1555	4	1404	1555	166	8550	1610	51	-	14990	7.4	7.4	420	376	6	CCP	203	300	
20	200	1555	4	1404	1555	166	8550	1610	50	-	14990	7.4	7.4	420	376	6	CCP	142	200	
21	200	1555	4	1404	1555	166	8550	1610	57	-	14990	7.4	7.4	420	376	6	CCP	176	300	
22	200	1555	4	1404	1555	166	8550	1610	65	-	14990	7.4	7.4	420	376	6	CCP	77	300	
23	200	1555	4	1404	1555	166	8550	1610	51	-	14990	7.4	7.4	420	376	6	CCP	123	500	
24	200	1555	4	1404	1555	166	8550	1610	75	-	14990	7.4	7.4	420	376	6	CCP	14712	10,010	
25	200	1555	4	1404	1555	166	8550	1610	35	-	14990	7.4	7.4	420	376	6	CCP	597	945	
26	200	1555	4	1404	1555	166	8550	1610	38	-	14990	7.4	7.4	420	376	6	CCP	40	10	
27	200	1555	4	1404	1555	166	8550	1610	51	-	14990	7.4	7.4	420	376	6	CCP	669	385	
28	200	1555	4	1404	1555	166	8550	1610	57	-	14990	7.4	7.4	420	376	6	CCP			
29	200	1555	4	1404	1555	166	8550	1610	65	-	14990	7.4	7.4	420	376	6	CCP			
30	200	1555	4	1404	1555	166	8550	1610	51	-	14990	7.4	7.4	420	376	6	CCP			
31	200	1555	4	1404	1555	166	8550	1610	51	-	14990	7.4	7.4	420	376	6	CCP			
TOTAL	5600	40,472	318	2740	5720	5076	23,332	115,280	1426	13181	10972	330,000	37	396	2940	10486	168		14712	10,010
MAXIMUM	200	2041	100	100	1108	2041	17,105	140,280	75	4752	422	385,885	74	74	420	378	4		597	945
MINIMUM	200	1555	4	1404	1555	166	8550	1610	35	217	14990	7.4	7.4	420	376	6			40	10
AVERAGE	200	1557	280	1467	1813	193	14,114	52,715	51	2197	14745	714	74	422	385	375	6		669	385

EVAPORATION LB. STEAM PER LB. STD. FUEL

REMARKS

APPROVED BY DATE

POST ENGINEER DATE

SEE REVERSE SIDE FOR INSTRUCTIONS

PREPARED BY

DA FORM 3967 NOV 72 REPLACES DA FORM 8-88 1 JUN 88 WHICH WILL BE USED.

A.5-73

For use of this form, see AR 420-39; the proponent agency is the Corps of Engineers.

For use of this form, see AR 420-39; the proponent agency is the Corps of Engineers.

SEE REVERSE SIDE FOR INSTRUCTIONS	PREPARED BY	DATE	APPROVED BY	DATE	POST ENGINEER	DATE

ALL INFORMATION CONTAINED HEREIN IS UNCLASSIFIED
DATE 08-01-2001 BY 60322 UCBAW

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)															LATION		PLANT		BLDG. NO.		MONTH	
For use of this form, see AR 420-49; the responsible agency is the Corps of Engineers.															N. G.		CEP		1412		Dec 94	
DATE	STEAM PRODUCED				TOTAL	FUEL				N. G.	FEEOWATER HEATER		FLUE GAS TEMPERATURE		TEMP. SUPPLY	TURNS AND NUMBER OF TIMES	PREVIOUS MAINT. CHECK	No. 4	CWMU			
	STEAM PRESSURE	1,000 LB.	2	3		1,000 LB.	2	3	1,000 LB.		2	3	1	2						3	1	2
1	200	1324			1324	331	7548	43100	49	3029	220	16310	11	435		382	6	DT	372	5700		
2	200	1725			1725	378	1548	25650	59	2487	220	19280	11	435		381	6	DT	372	5700		
3	200	1276			1276	370	821	30710	63	—	220	18220	11	435		381	6	DT	372	5700		
4	200	1134			1134	259	231	44010	70	—	220	18390	11	435		381	6	DT	372	5700		
5	200	1186			1186	214	236	71500	69	2129	220	16600	11	435		381	6	DT	372	5700		
6	200	1315			1315	182	1548	13350	67	3029	220	18870	11	435		381	6	DT	372	5700		
7	200	1397			1397	176	1092	18150	62	—	220	10970	11	435		381	6	DT	372	5700		
8	200	1349			1349	181	1278	20080	63	—	220	10970	11	435		381	6	DT	372	5700		
9	200	1411			1411	188	355	20200	62	—	220	10970	11	435		381	6	DT	372	5700		
10	200	1400			1400	193	1049	6990	62	—	220	10970	11	435		381	6	DT	372	5700		
11	200	1518			1518	199	598	8950	53	—	220	10970	11	435		381	6	DT	372	5700		
12	200	1654			1654	228	401	5900	43	—	220	10970	11	435		381	6	DT	372	5700		
13	200	1810			1810	229	1145	23090	41	—	220	10970	11	435		381	6	DT	372	5700		
14	200	1680			1680	232	457	17260	47	—	220	10970	11	435		381	6	DT	372	5700		
15	200	1727			1727	226	725	21240	51	—	220	10970	11	435		381	6	DT	372	5700		
16	200	1767			1767	230	751	22000	47	—	220	10970	11	435		381	6	DT	372	5700		
17	200	1649			1649	223	1256	18880	49	—	220	10970	11	435		381	6	DT	372	5700		
18	200	1589			1589	217	1243	19460	52	—	220	10970	11	435		381	6	DT	372	5700		
19	200	1767			1767	237	362	25330	43	—	220	10970	11	435		381	6	DT	372	5700		
20	200	1774			1774	245	1102	13660	48	—	220	10970	11	435		381	6	DT	372	5700		
21	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
22	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
23	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
24	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
25	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
26	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
27	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
28	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
29	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
30	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
31	200	1724			1724	231	570	79920	49	895	220	19460	11	435		381	6	DT	372	5700		
TOTAL	6200	44514			44514	5105	49169	6631	31172	2096	220	51910	1660	12612		435	6	DT	372	5700		
MINIMUM	200	1784			1784	1796	2025	257	1596	2020	220	20800	70	435		435	6	DT	372	5700		
AVERAGE	200	1534			1534	181	1134	160	355	883	220	7830	43	434		435	6	DT	372	5700		
EVAPORATION LB. STEAM PER LB. STD. FUEL						729	1600	214	4080	53	2019	220	13521	434		435	6	DT	372	5700		

A.5-75

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)															BLDG. NO.		MOUNT		MOUNT			
For use of this form, see AR 420-49; the responsible agency is the Corps of Engineers.															1412		C.E.P.		OCT 94			
STEAM PRODUCED															FUEL		FEEDWATER		TEMP.		TURNS	
DATE	STEAM PRESSURE			BOILER			TOTAL			FUEL	FUEL	PRESS.	TEMP.	FEEDWATER			TURNS	TURNS	TURNS			
	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.	1,000 L.B.					1,000 L.B.	1,000 L.B.	1,000 L.B.				1,000 L.B.	1,000 L.B.	1,000 L.B.
1	200	1244					1244	166	387	8170	73	3	223	7050			384	6	5.2	38	94012	
2	200	1244					1244	165	400	30	73	3	217	9190			384	6	5.2	53	94012	
3	200	1321					1321	127	400	30	73	3	223	7050			384	6	5.2	402	94012	
4	200	965					965	85	204	30	63	3	222	6720			384	6	5.2	352	94012	
5	200	1401					1401	182	350	30	64	3	224	8520			384	6	5.2	123	94012	
6	200	1443					1443	149	350	30	67	3	220	12350			384	6	5.2	27	94012	
7	200	1373					1373	135	303	30	66	3	220	1210			384	6	5.2	27	94012	
8	200	1383					1383	136	268	110	68	3	220	1010			384	6	5.2	35	94012	
9	200	1406					1406	135	458	10	76	3	220	9820			384	6	5.2	60	94012	
10	200	1295					1295	155	471	150	75	3	220	9460			384	6	5.2	168	94012	
11	200	1416					1416	137	471	150	75	3	220	9460			384	6	5.2	421	94012	
12	200	1427					1427	146	471	150	75	3	220	9460			384	6	5.2	217	94012	
13	200	1291					1291	137	471	150	75	3	220	9460			384	6	5.2	51	94012	
14	200	1618					1618	137	471	150	75	3	220	9460			384	6	5.2	122	94012	
15	200	1839					1839	141	471	150	75	3	220	9460			384	6	5.2	90	94012	
16	200	1850					1850	141	471	150	75	3	220	9460			384	6	5.2	213	94012	
17	200	1844					1844	120	1902	57350	40	3	223	1800			384	6	5.2	251	94012	
18	200	1823					1823	115	2010	57350	40	3	223	1800			384	6	5.2	265	94012	
19	200	1459					1459	101	2751	9770	68	3	223	2194			384	6	5.2	364	94012	
20	200	1363					1363	138	88	3100	74	3	223	1730			384	6	5.2	110	94012	
21	200	1328					1328	174	506	3100	74	3	223	1730			384	6	5.2	67	94012	
22	200	1305					1305	124	442	3100	74	3	223	1730			384	6	5.2	54	94012	
23	200	1265					1265	124	442	3100	74	3	223	1730			384	6	5.2	63	94012	
24	200	1286					1286	169	471	3100	74	3	223	1730			384	6	5.2	102	94012	
25	200	1256					1256	160	254	3100	74	3	223	1730			384	6	5.2	102	94012	
26	200	800					800	110	110	3100	74	3	223	1730			384	6	5.2	102	94012	
27	200	800					800	110	110	3100	74	3	223	1730			384	6	5.2	102	94012	
28	200	1153					1153	1153	134	1508	54	3	223	1730			384	6	5.2	102	94012	
29	200	1161					1161	110	1508	10	125	3	223	1730			384	6	5.2	102	94012	
30	200	1146					1146	101	1508	10	125	3	223	1730			384	6	5.2	102	94012	
31	200	14054					14054	3947	35820	2014	74	3	223	1730			384	6	5.2	102	94012	
TOTAL	6200	1850					1850	109	3369	18820	76	3	223	1730			384	6	5.2	102	94012	
MINIMUM	200	800					800	85	42	10	54	3	223	1730			384	6	5.2	102	94012	
AVERAGE	200	13065					13065	132	1379	27912	60	3	223	1730			384	6	5.2	102	94012	
EVAPORATION	200	13065					13065	132	1379	27912	60	3	223	1730			384	6	5.2	102	94012	

A.5-77

DA FORM 1 NOV 71 3967
 REPLACES DA FORM 8-88 1 JUN 68 WHICH WILL BE USED.
 965 715 421
 12.007 74 422

For use of this form, see AR 420-49; the proponent agency is the Corps of Engineers.

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

(10/1/88)

DATE	STEAM PRODUCED				TOTAL 1,000 LB.	FUEL USED 1,000 LB.	FUEL CONSUMPTION PER LB. OF STEAM	OUTSIDE TEMP. °F.	FEEDWATER HEATER		% FO.	FLUE GAS TEMPERATURE				TEMP. H.W. SUPPLY °F.	TURNS CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	#4042 O/S	CWMU		
	STEAM PRESSURE LB.	BOILER							PRESS. LB.	TEMP. °F.		WATER GAL.	BOILER	°F.								
		1	2	3										1	2						3	4
1	250	2015			2015	222	845	82	3	223	6740	11	430	382	6	24	46					
2	200	1952			1952	258	556	91	3	223	10850	11	430	382	6	24	46					
3	200	1610			1610	214	430	84	3	223	7990	11	430	382	6	24	46					
4	200	1596			1596	186	120	71	3	223	7390	11	430	382	6	24	46					
5	200	1400			1400	156	-	70	3	223	5060	11	430	382	6	24	46					
6	200	1549			1549	196	300	78	3	223	17800	11	430	382	6	24	46					
7	200	1672			1672	209	126	77	3	223	9410	11	430	382	6	24	46					
8	200	1878			1878	241	954	78	3	223	10420	11	430	382	6	24	46					
9	220	2003			2003	275	1430	75	3	223	8540	11	430	382	6	24	46					
10	220	1154			1154	119	2040	75	3	223	8540	11	430	382	6	24	46					
11	220	2025			2025	267	1731	76	3	223	8200	11	430	382	6	24	46					
12	220	2277			2277	277	9220	77	3	223	8200	11	430	382	6	24	46					
13	220	260			260	277	8700	74	3	223	8200	11	430	382	6	24	46					
14	200	260			260	277	8700	74	3	223	8200	11	430	382	6	24	46					
15	200	1199			1199	149	920	76	3	223	8200	11	430	382	6	24	46					
16	200	1275			1275	149	920	76	3	223	8200	11	430	382	6	24	46					
17	200	1275			1275	149	920	76	3	223	8200	11	430	382	6	24	46					
18	200	1342			1342	153	20	75	3	223	8200	11	430	382	6	24	46					
19	200	1331			1331	240	268	71	3	223	8200	11	430	382	6	24	46					
20	200	1344			1344	174	2425	76	3	223	8200	11	430	382	6	24	46					
21	200	1366			1366	171	914	76	3	223	8200	11	430	382	6	24	46					
22	200	1274			1274	167	441	72	3	223	8200	11	430	382	6	24	46					
23	200	1358			1358	187	397	73	3	223	8200	11	430	382	6	24	46					
24	200	1328			1328	179	551	72	3	223	8200	11	430	382	6	24	46					
25	200	1305			1305	179	403616	70	3	223	8200	11	430	382	6	24	46					
26	200	1350			1350	130	20252	70	3	223	8200	11	430	382	6	24	46					
27	200	1284			1284	132	20252	70	3	223	8200	11	430	382	6	24	46					
28	200	1305			1305	132	20252	70	3	223	8200	11	430	382	6	24	46					
29	200	1288			1288	132	20252	70	3	223	8200	11	430	382	6	24	46					
30	200	1277			1277	176	82553	75	3	223	8200	11	430	382	6	24	46					
31	200	1277			1277	176	82553	75	3	223	8200	11	430	382	6	24	46					
TOTAL	200	110285			110285	4489	4969	58270	352500	2305												
MINIMUM	200	2025			2025	267	8700	139290	91													
MAXIMUM	200	2025			2025	267	8700	139290	91													
AVERAGE	200	1389			1389	27	120	10	70													
EVAPORATION LB. STEAM PER LB. STD. FUEL						613	1406	177.5	2094.6	29375	77											

FUEL USED DURING MONTH (STANDARD TONS)

DATE: 11/1/88

PORT ENGINEER: [Signature]

DATE: 11/1/88

APPROVED BY: [Signature]

REMARKS: *

F. UTILITIES ENGINEERING OPERATING LOG (Boiler Plant)														PLANT				BLOG. NO.		MONTH				
For use of this form, see AR 420-49; the proponent agency is USACE														HEADQUARTERS FORT STEWART				1412		Aug 94				
FORT STEWART, GEORGIA 31313																								
DATE	STEAM PRODUCED			TOTAL 1,000 LB.	WATER USED 1,000 LB.	FUEL USED LB. M.C.F.	N.G. UNIT	OUTSIDE TEMP. AV.	PRESS. LB.	TEMP. °F.	FEEDWATER HEATER			%CO ₂	FLUE GAS TEMPERATURE			TEMP. SUPPLY °F.	TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	# 4812	CUMULATIVE		
	STEAM PRESSURE LB.	1,000 LB.	3								1	2	3		1	2	3						1	2
1	200	2030	276	2030	276	183	4880	80	3	203	19920	11	119	119	119	382	6	121	212	22	121	22	121	22
2	200	2033	271	2033	271	455	2310	81	3	223	17770	11	119	119	119	380	6	121	212	22	121	22	121	22
3	200	2003	257	2003	257	487	4880	84	3	223	18120	11	119	119	119	382	6	121	212	22	121	22	121	22
4	200	1970	264	1970	264	473	4880	82	3	223	17850	11	119	119	119	382	6	121	212	22	121	22	121	22
5	200	2026	272	2026	272	440	4300	80	3	223	13000	11	119	119	119	382	6	121	212	22	121	22	121	22
6	200	2011	260	2011	260	1115	39880	80	3	223	13500	11	119	119	119	381	6	121	212	22	121	22	121	22
7	200	2022	260	2022	260	734	21750	76	3	223	16090	11	119	119	119	381	6	121	212	22	121	22	121	22
8	200	2026	274	2026	274	354	4880	78	3	223	17210	11	119	119	119	380	6	121	212	22	121	22	121	22
9	200	2050	263	2050	263	634	24120	78	3	223	16420	11	119	119	119	380	6	121	212	22	121	22	121	22
10	200	1977	267	1977	267	305	57370	80	3	223	12430	11	119	119	119	380	6	121	212	22	121	22	121	22
11	200	2031	278	2031	278	614	4880	78	3	223	17110	11	119	119	119	381	6	121	212	22	121	22	121	22
12	200	1992	263	1992	263	618	4880	80	3	223	14950	11	119	119	119	380	6	121	212	22	121	22	121	22
13	200	1992	261	1992	261	700	700	78	3	223	15940	11	119	119	119	380	6	121	212	22	121	22	121	22
14	200	1951	259	1951	259	528	22510	82	3	223	15040	11	119	119	119	380	6	121	212	22	121	22	121	22
15	200	1970	259	1970	259	655	37660	82	3	223	18540	11	119	119	119	380	6	121	212	22	121	22	121	22
16	200	1951	267	1951	267	376	5930	76	3	223	17880	11	119	119	119	380	6	121	212	22	121	22	121	22
17	200	1912	261	1912	261	2649	7610	85	3	223	13990	11	119	119	119	380	6	121	212	22	121	22	121	22
18	200	1945	267	1945	267	2709	4880	84	3	223	11160	11	119	119	119	380	6	121	212	22	121	22	121	22
19	200	1842	235	1842	235	1185	6550	82	3	223	5240	11	119	119	119	380	6	121	212	22	121	22	121	22
20	200	1986	266	1986	266	389	35640	81	3	223	9080	11	119	119	119	384	6	121	212	22	121	22	121	22
21	200	1982	258	1982	258	326	26110	80	3	223	10430	11	119	119	119	381	6	121	212	22	121	22	121	22
22	200	2043	263	2043	263	2715	4880	83	3	223	9310	11	119	119	119	380	6	121	212	22	121	22	121	22
23	200	2038	263	2038	263	41381	4880	78	3	223	6640	11	119	119	119	380	6	121	212	22	121	22	121	22
24	200	1960	246	1960	246	4172	30	78	3	223	11450	11	119	119	119	380	6	121	212	22	121	22	121	22
25	200	2010	272	2010	272	366	7800	76	3	223	8500	11	119	119	119	380	6	121	212	22	121	22	121	22
26	200	2054	263	2054	263	1336	4880	80	3	223	5730	11	119	119	119	380	6	121	212	22	121	22	121	22
27	200	2054	273	2054	273	550	2150	80	3	223	4470	11	119	119	119	380	6	121	212	22	121	22	121	22
28	200	2123	279	2123	279	743	2430	80	3	223	11630	11	119	119	119	380	6	121	212	22	121	22	121	22
29	200	2100	272	2100	272	351	1230	90	3	223	12460	11	119	119	119	380	6	121	212	22	121	22	121	22
30	200	2089	279	2089	279	750	170	80	3	223	9440	11	119	119	119	381	6	121	212	22	121	22	121	22
31	200	2109	288	2109	288	154	4880	86	3	223	2310	11	119	119	119	384	6	121	212	22	121	22	121	22
TOTAL	6820	12956	62837	62837	62837	13922	87095	2488	3	224	40710					11796	186							
MAXIMUM	200	2715	2058	2058	2058	2715	57190	86								384	6							
MINIMUM	200	839	1842	1842	1842	107	76	76								380	6							
AVERAGE	200	2159	2014	2014	2014	2014	2014	80								380.5	6							

REMARKS				APPROVED BY		DATE		POST ENGINEER		DATE	
FUEL USED DURING MONTH (STANDARD TONS)				464010							

A.5-79

A.5-80

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)										INS.		HEADQUARTERS PORT STEWART PORT STEWART, GEORGIA 31313		PLANT		BLDG. NO.		MONTH		DATE			
DATE		STEAM PRODUCED		FEED WATER TO BOILER		FUEL USED		OUTSIDE TEMP.		FEEDWATER HEATER		BOILER		FLUE GAS TEMPERATURE		TEMP. SUPPLY		TURNS CLEANED		PRIORITY		REMARKS	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	
1	200	677	1000	1000	1677	6000	64000	86	3	213	7230	11	11	420	420	380	380	13	24	8200	44102	44102	
2	200	758	1000	1000	1758	6000	62600	86	3	213	7530	11	11	420	420	380	380	3	24	8100	44102	44102	
3	200	744	1000	1000	1744	6000	61800	83.5	3	223	7230	11	11	420	420	380	380	3	24	8400	44102	44102	
4	200	765	1000	1000	1765	6000	61800	80.5	3	223	7230	11	11	420	420	380	380	3	24	8400	44102	44102	
5	200	828	1000	1000	1828	6000	64300	83	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
6	200	847	1000	1000	1847	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
7	200	851	1000	1000	1851	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
8	200	861	1000	1000	1861	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
9	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
10	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
11	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
12	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
13	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
14	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
15	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
16	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
17	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
18	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
19	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
20	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
21	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
22	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
23	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
24	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
25	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
26	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
27	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
28	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
29	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
30	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
31	200	890	1000	1000	1890	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
TOTAL	6200	2051	45241	45241	8667	60987	6052	75497	84	3	223	7230	11	11	420	420	380	380	153	5	540670	540670	540670
MAXIMUM	2200	861	1000	1000	1861	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
MINIMUM	2200	861	1000	1000	1861	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
AVERAGE	2200	861	1000	1000	1861	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	
EVAPORATION LB. STEAM PER LB. STD. FUEL	2200	861	1000	1000	1861	6000	65700	88	3	223	7230	11	11	420	420	380	380	3	24	8500	44102	44102	

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-49; the proponent agency is USACE.

[illegible]

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)															PLANT NO.		MONTH		
For use of this form, see AR 420-49; the proponent agency is USACE.															1412		April 94		
HEADQUARTERS, FORT STEWART, GEORGIA 31313															BLDG. NO.		MONTH		
C-2															1412		April 94		
DATE	STEAM PRESSURE LB.	STEAM PRODUCED			TOTAL 1,000 LB.	WATER USED TO BOILER 1,000 LB.	FUEL USED LB. M.C.F.	OUTSIDE TEMP. AV.	FEEDWATER HEATER		MAXIMUM GAL.	BOILER		GAS TEMPERATURE		TEMP. H.W. SUPPLY	TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	N-4 AIR
		1,000 LB.	1,000 LB.	1,000 LB.					1,000 LB.	1,000 LB.		1,000 LB.	1,000 LB.	1,000 LB.	1,000 LB.				
1	220	1237	170	170	170	0.1	56	110	3	223	2270	13	114	118	198	6	21	N-4 AIR	
2	220	1206	166	166	166	0	65	223	3	223	2270	7			377	6	21	0.1 S/F	
3	220	1178	162	162	162	0	65	223	3	223	2270	7			377	6	21		
4	220	1213	167	167	167	11	66	223	3	223	2270	7			377	6	21		
5	220	1231	170	170	170	0	69	223	3	223	2270	7			377	6	21		
6	220	1199	165	165	165	2.7	69	223	3	223	2270	7			377	6	21		
7	220	1238	170	170	170	2.4	69	223	3	223	2270	7			377	6	21		
8	220	1224	169	169	169	0	69	223	3	223	2270	7			377	6	21		
9	220	1121	154	154	154	0	64	223	3	223	2270	7			377	6	21		
10	220	1138	157	157	157	30	61	223	3	223	2270	7			377	6	21		
11	220	1397	187	187	187	381	73	223	3	223	2270	7			377	6	21		
12	220	1807	244	244	244	132	71	223	3	223	2270	7			377	6	21		
13	220	1771	244	244	244	383	71	223	3	223	2270	7			377	6	21		
14	220	1508	202	202	202	258	75	223	3	223	2270	7			377	6	21		
15	220	1281	174	174	174	122	75	223	3	223	2270	7			377	6	21		
16	220	1311	180	180	180	5	75	223	3	223	2270	7			377	6	21		
17	220	1340	184	184	184	5	75	223	3	223	2270	7			377	6	21		
18	220	1340	184	184	184	5	75	223	3	223	2270	7			377	6	21		
19	220	1330	181	181	181	49	70	223	3	223	2270	7			377	6	21		
20	220	1713	234	234	234	97	76	223	3	223	2270	7			377	6	21		
21	220	2014	268	268	268	145	78	223	3	223	2270	7			377	6	21		
22	220	2012	271	271	271	152	75	223	3	223	2270	7			377	6	21		
23	220	1399	207	207	207	55	61	223	3	223	2270	7			377	6	21		
24	220	1433	196	196	196	92	67	223	3	223	2270	7			377	6	21		
25	220	1837	242	242	242	586	74	223	3	223	2270	7			377	6	21		
26	220	1937	278	278	278	191	75	223	3	223	2270	7			377	6	21		
27	220	1932	262	262	262	219	74	223	3	223	2270	7			377	6	21		
28	220	1540	210	210	210	890	74	223	3	223	2270	7			377	6	21		
29	220	1170	169	169	169	0	71	223	3	223	2270	7			377	6	21		
30	220	1130	160	160	160	18	75	223	3	223	2270	7			377	6	21		
31	220	1130	160	160	160	18	75	223	3	223	2270	7			377	6	21		
TOTAL	4110	42289	1819	1819	1819	4412	2087				45340				1136	180			
MAXIMUM	220	2034	268	268	268	840	78				27130				379	6			
AVERAGE	220	1130	170	170	170	5	56				3840				375	6			
EVAPORATION LB. STEAM PER LB. STD. FUEL	220	1410	6.06	6.06	6.06	19.2	69.6				15114				377	6			

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)															HEADQUARTERS FORT STEWART										PLANT		BLDG. NO.		MONTH																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
For use of this form, see AR 420-49; the proponent agency is USACE															FORT STEWART, GEORGIA 31313										C E P		1412		Feb 94																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
DATE		STEAM PRODUCTION		STEAM PRESSURE		BOILER		TOTAL		FUEL USED		WATER USED		FUEL USED		WATER USED		FUEL USED		WATER USED		FUEL USED		WATER USED		FUEL USED		WATER USED		FUEL USED		WATER USED		FUEL USED		WATER USED																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																														
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	31	32	33	34	35	36	37	38	39	40																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
1	200	1931	1931	254	638	17	100	110	111	112	113	114	115	116	117	118	119	120	121	122	123	124	125	126	127	128	129	130	131	132	133	134	135	136	137	138	139	140	141	142	143	144	145	146	147	148	149	150	151	152	153	154	155	156	157	158	159	160	161	162	163	164	165	166	167	168	169	170	171	172	173	174	175	176	177	178	179	180	181	182	183	184	185	186	187	188	189	190	191	192	193	194	195	196	197	198	199	200	201	202	203	204	205	206	207	208	209	210	211	212	213	214	215	216	217	218	219	220	221	222	223	224	225	226	227	228	229	230	231	232	233	234	235	236	237	238	239	240	241	242	243	244	245	246	247	248	249	250	251	252	253	254	255	256	257	258	259	260	261	262	263	264	265	266	267	268	269	270	271	272	273	274	275	276	277	278	279	280	281	282	283	284	285	286	287	288	289	290	291	292	293	294	295	296	297	298	299	300	301	302	303	304	305	306	307	308	309	310	311	312	313	314	315	316	317	318	319	320	321	322	323	324	325	326	327	328	329	330	331	332	333	334	335	336	337	338	339	340	341	342	343	344	345	346	347	348	349	350	351	352	353	354	355	356	357	358	359	360	361	362	363	364	365	366	367	368	369	370	371	372	373	374	375	376	377	378	379	380	381	382	383	384	385	386	387	388	389	390	391	392	393	394	395	396	397	398	399	400	401	402	403	404	405	406	407	408	409	410	411	412	413	414	415	416	417	418	419	420	421	422	423	424	425	426	427	428	429	430	431	432	433	434	435	436	437	438	439	440	441	442	443	444	445	446	447	448	449	450	451	452	453	454	455	456	457	458	459	460	461	462	463	464	465	466	467	468	469	470	471	472	473	474	475	476	477	478	479	480	481	482	483	484	485	486	487	488	489	490	491	492	493	494	495	496	497	498	499	500	501	502	503	504	505	506	507	508	509	510	511	512	513	514	515	516	517	518	519	520	521	522	523	524	525	526	527	528	529	530	531	532	533	534	535	536	537	538	539	540	541	542	543	544	545	546	547	548	549	550	551	552	553	554	555	556	557	558	559	560	561	562	563	564	565	566	567	568	569	570	571	572	573	574	575	576	577	578	579	580	581	582	583	584	585	586	587	588	589	590	591	592	593	594	595	596	597	598	599	600	601	602	603	604	605	606	607	608	609	610	611	612	613	614	615	616	617	618	619	620	621	622	623	624	625	626	627	628	629	630	631	632	633	634	635	636	637	638	639	640	641	642	643	644	645	646	647	648	649	650	651	652	653	654	655	656	657	658	659	660	661	662	663	664	665	666	667	668	669	670	671	672	673	674	675	676	677	678	679	680	681	682	683	684	685	686	687	688	689	690	691	692	693	694	695	696	697	698	699	700	701	702	703	704	705	706	707	708	709	710	711	712	713	714	715	716	717	718	719	720	721	722	723	724	725	726	727	728	729	730	731	732	733	734	735	736	737	738	739	740	741	742	743	744	745	746	747	748	749	750	751	752	753	754	755	756	757	758	759	760	761	762	763	764	765	766	767	768	769	770	771	772	773	774	775	776	777	778	779	780	781	782	783	784	785	786	787	788	789	790	791	792	793	794	795	796	797	798	799	800	801	802	803	804	805	806	807	808	809	810	811	812	813	814	815	816	817	818	819	820	821	822	823	824	825	826	827	828	829	830	831	832	833	834	835	836	837	838	839	840	841	842	843	844	845	846	847	848	849	850	851	852	853	854	855	856	857	858	859	860	861	862	863	864	865	866	867	868	869	870	871	872	873	874	875	876	877	878	879	880	881	882	883	884	885	886	887	888	889	890	891	892	893	894	895	896	897	898	899	900	901	902	903	904	905	906	907	908	909	910	911	912	913	914	915	916	917	918	919	920	921	922	923	924	925	926	927	928	929	930	931	932	933	934	935	936	937	938	939	940	941	942	943	944	945	946	947	948	949	950	951	952	953	954	955	956	957	958	959	960	961	962	963	964	965	966	967	968	969	970	971	972	973	974	975	976	977	978	979	980	981	982	983	984	985	986	987	988	989	990	991	992	993	994	995	996	997	998	999	1000

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)															HEADQUARTERS PORT STEWART		PLANT		BLDG. NO.		MONTH	
For use of this form, see AR 420-49; the proponent agency is USACE.															PORT STEWART, GEORGIA 31313		C.E.P.		1417		JAN 94	
DATE	STEAM PRODUCED				FUEL CONSUMED LBS.	EVAP. LBS. PER UNIT	OUTSIDE TEMP. AV.	FEEDWATER HEATER		%CO ₂	FLUE GAS TEMPERATURE		TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	REMARKS							
	STEAM PRESSURE LBS.	1 1,000 LBS.	2 1,000 LBS.	TOTAL 1,000 LBS.				TEMP. °F.	MAKUP GAL.		1 °F.	2 °F.				1 °F.	2 °F.					
1	200			1726	156		48	110	112		118	117	4	373	5.5011							
2	200	497		1072	1569	57	53		22970	7	420	420	6	374	4.4012							
3	200	700	895	1595	57		51		27360	7	420	420	6	376	4.4013							
4	200	900	968	1868	55		46		14670	7	420	420	3	378	4.4014							
5	200	600	1734	1774	55		40		15970	7	420	420	1	377	4.4015							
6	200		1850	1850	252		47		18570	7	420	420	6	375	4.4016							
7	200		1590	1590	219		56		24220	7	420	420	6	375	4.4017							
8	200		1608	1608	214		50		25780	7	420	420	6	372	4.4018							
9	200		2019	2019	268		37		26570	7	420	420	6	374	4.4019							
10	200		2040	2040	278		39		26270	7	420	420	6	372	4.4020							
11	200		1856	1856	242		50		27840	7	420	420	6	375	4.4021							
12	200		1690	1690	205		54		23680	7	420	420	6	374	4.4022							
13	200		1707	1707	213		49		22050	7	420	420	6	374	4.4023							
14	200		1808	1808	242		48		15020	7	420	420	6	373	4.4024							
15	200		1923	1923	261		36		31040	7	420	420	6	374	4.4025							
16	200		2135	2135	288		27		22970	7	420	420	6	372	4.4026							
17	200		1912	1912	255		48		17650	7	420	420	6	372	4.4027							
18	200		1974	1974	265		38		20720	7	420	420	6	372	4.4028							
19	200		2327	2327	305		30		21820	7	420	420	6	374	4.4029							
20	200		2223	2223	295		33		22130	7	420	420	6	375	4.4030							
21	200		2085	2085	281		35		18870	7	420	420	6	372	4.4031							
22	200		2038	2038	281		39		18690	7	420	420	6	372	4.4032							
23	200		1990	1990	268		35		16020	7	420	420	6	372	4.4033							
24	200		1800	1800	248		44		19140	7	420	420	6	375	4.4034							
25	200		1678	1678	221		54		17180	7	420	420	6	375	4.4035							
26	200		1561	1561	215		62		14130	7	420	420	6	375	4.4036							
27	200		1579	1579	197		53		17120	7	420	420	6	375	4.4037							
28	200		1520	1520	209		61		16330	7	420	420	6	375	4.4038							
29	200		1547	1547	178		57		17580	7	420	420	6	375	4.4039							
30	200		1721	1721	216		44		14480	7	420	420	6	377	4.4040							
31	200		1867	1867	244		45		17570	7	420	420	6	377	4.4041							
TOTAL	6820	2197	2597	5156	55950	628	1534		42660				186	11610	66349							
MAXIMUM	220	400	968	2227	305		64		27840				6	378	5800							
MINIMUM	220	497	734	1520	55		27		14670				6	372	1113							
AVERAGE	220	545	866	1764	1805	228.6	46		20197				6	375	2140							
EVAPORATION LBS. STEAM PER LB. STD. FUEL																						

SEE REVERSE SIDE FOR INSTRUCTIONS

PREPARED BY

DATE

APPROVED BY

DATE

POST ENGINEER

DATE

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant) For use of this form, see AR 420-49; the proponent agency is USACE.

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)													HEADQUARTERS FORT STEWART				FORT STEWART, GEORGIA 31313				PLANT				BLDG. NO.				MONTH	
For use of this form, see AR 420-49; the proponent agency is USACE.													CENTRAL ENERGY PLANT				1412				NOVEMBER 1973									
DATE	STEAM PRODUCED						WATER USED TONS	WATER USED 1,000 LB.	FUEL USED TONS	FUEL USED 1,000 LB.	WATER GAS USED TONS	WATER GAS USED 1,000 LB.	OUTSIDE TEMP. °F.	FEEDWATER HEATER		BOILER		FLUE GAS TEMPERATURE				TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK							
	STEAM PRESSURE		1,000 LB.		1,000 LB.									TEMP. °F.	MAKUP GAL.	1	2	1	2	1	2			1	2	TEMP. °F.	SUPPLY			
	LB.	(11)	1,000 LB.	(12)	1,000 LB.	(13)																						1,000 LB.	(14)	1,000 LB.
1	220	600	752				1352			60	11350	43	3.0	220	1980	7.4	7.4	140	119	422	422	375	3	DR						
2	220	700	851				1551			1300	11350	46	3.0	220	23710	7.4	7.4			422	422	377	3	DR						
3	220	700	809				1509			4570	11350	58	3.0	220	23970	7.4	7.4			422	422	377	3	DR						
4	220	700	820				1520			20	11350	66	3.0	220	23280	7.4	7.4			422	422	372	3	DR						
5	220	700	802				1502			4790	11350	67	3.0	220	19380	7.4	7.4			422	422	373	3	FW						
6	220	700	798				1498			2070	11350	63	3.2	222	9580	7.4	7.4			422	422	374	3	DR						
7	220	700	884				1584			3190	11350	47	3.0	222	15800	7.4	7.4			422	422	372	3	FW						
8	220	800	889				1689			3230	11350	47	3.0	222	20750	7.4	7.4			422	422	373	3	FW						
9	220	800	925				1725			3240	11350	46	3.0	222	18250	7.4	7.4			422	422	372	3	DR						
10	220	800	816				1616			3120	11350	48	3.1	222	10340	7.4	7.4			422	422	373	3	DR						
11	220	800	833				1633			4680	11350	48	3.0	220	24770	7.4	7.4			422	422	374	3	DR						
12	220	800	838				1638			1480	11350	54	3.0	220	14190	7.4	7.4			422	422	374	3	FW						
13	220	700	842				1542			2430	11350	67	3.0	220	17460	7.4	7.4			422	422	374	3	FW						
14	220	700	770				1470			5350	11350	74	3.0	220	24460	7.4	7.4			422	422	374	3	FW						
15	220	700	787				1487			2050	11350	75	3.0	220	20310	7.4	7.4			422	422	374	3	FW						
16	220	700	772				1472			4030	11350	73	3.0	220	16900	7.4	7.4			422	422	374	3	FW						
17	220	700	729				1429			3420	11350	73	3.0	220	14650	7.4	7.4			422	422	375	3	DR						
18	220		1031				1471		50	1700	11350	70	3.0	220	12120		7.5			422	421	374	3	FW						
19	220		501				1339		150	3820	162	69	3.2	222	5870		7.5			422	421	373	3	FW						
20	220	700	828				1528			108190		56	3.0	220	13190	7.4	7.4			422	422	374	3	FW						
21	220	800	893				1693			1205800		50	3.0	220	11260	7.4	7.4			422	422	373	3	FW						
22	220	800	951				1751			1156160		56	3.1	221	10090	7.4	7.4			422	422	373	3	FW						
23	220	800	888				1668			1108170		58	3.0	221	11110	7.4	7.4			422	422	373	3	FW						
24	220	800	919				1619			1013580		60	3.0	220	14170	7.4	7.4			422	422	372	3	FW						
25	220	800	862				1661			1114400		61	3.0	220	12560	7.4	7.4			422	422	374	3	FW						
26	220	800	876				1676			1124280		58	3.0	220	15740	7.4	7.4			422	422	373	3	FW						
27	220	800	826				1626			1110000		63	3.0	220	12950	7.4	7.4			422	422	374	3	FW						
28	220	800	842				1692			1133920		50	3.0	220	12990	7.4	7.4			422	422	373	3	FW						
29	220	800	989				1789			1228540		46	3.0	220	12610	7.4	7.4			422	422	374	3	FW						
30	220	800	991				1791			1214330		50	3.0	220	11060	7.4	7.4			422	422	372	3	FW						
31															570															
TOTAL	6600	21000	25264	1278			47542		200	1286010	20462	1742	90.6	6614	47760	207.2	22.3			11816	12659	841	11202							
MAXIMUM	220	800	1031	838			1751		150	1228540	11350	75	3.2	222	23770	7.4	7.5			421	421	421	375							
MINIMUM	220	600	501	440			1339		50	20	162	43	3.0	220	9580	7.4	7.4			421	421	421	372							
AVERAGE	220	750	842	639			1585		150	43200	16761	50	3.02	220.5	15922	7.4	7.4			422	422	420.5	373							
EVAPORATION LB. STEAM PER LB. STD. FUEL																														

REMARKS: W660: 72, NO. 2 OIL: 113.4, 36, N.G: 534.47

PREPARED BY: [Signature]

DATE: 20 Dec 93

APPROVED BY: Randy A. Pauls

DATE: 20 Dec 93

POST ENGINEER: [Signature]

DATE: 20 Dec 93

FORM 3057

For use of this form, see AR 420-49; the proponent agency is USACE

For use of this form, see AR 420-49; the proponent agency is USACE

EVAPORATION LB. STEAM PER LB. STD. FUEL	FUEL USED DURING MONTH (STANDARD TONS)	REMARKS
	722.81	7180

Wood: 1949.4, 014: 90.13, NAT. GAS: 722826
* Rec'd 11:55:15 013 64. NAT. GAS: 1233

SEE REVERSE SIDE	PREPARED BY	DATE	APPROVED BY	DATE	POST ENGINEER	DATE

FOR INSTRUCTIONS

FORM 100-1

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)																										
For use of this form, see AR 420-49; the proponent agency is USACE.																										
DATE	STEAM PRODUCED					WATER TONS BOILER	FUEL USED GAL.	NAT GAS USED GAL.	OUTSIDE TEMP. AV.	FEEDWATER HEATER			BOILER			%CO2	FLUE GAS TEMPERATURE			TEMP. H.W. SUPPLY	TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	JUNE 1993			
	LB.	1,000 LB.		3	TOTAL					PRESS. LB.	TEMP. °F.	MAKEUP GAL.	1	2	3		1	2	3					1	2	3
		1	2																							
1	220	996	722	1698	71	1518	818160	82	3.2	223	8000	7.5	7.4	421	422	422	422	422	373	6	120					
2	220	660	894	1554	71	1120	881720	81	3.2	223	8610	7.6	7.4	420	422	422	422	422	373	6	120					
3	220	1152	681	1833	68	1555	701230	81	3.3	224	7730	7.4	7.4	422	422	422	422	422	373	6	120					
4	220	1201	652	1853	67	1665	653340	84	3.2	223	8560	7.4	7.4	422	422	422	422	422	374	6	120					
5	220	1059	783	1842	71	684	741570	86	3.3	224	7610	7.5	7.4	421	422	422	422	422	375	6	120					
6	220	959	778	1737	72	600	61750	83	3.3	224	7600	7.5	7.4	421	422	422	422	422	375	6	120					
7	220	952	816	1768	70	600	61750	83	3.1	222	10200	7.5	7.4	421	422	422	422	422	374	6	120					
8	220	1002	746	1748	51	600	63650	84	3.1	222	10600	7.4	7.4	422	422	422	422	422	374	6	120					
9	220	977	784	1755	54	550	63980	93	3.2	223	8590	7.5	7.4	421	422	422	422	422	374	6	120					
10	220	1013	716	1729	100	550	578030	84	3.2	223	9200	7.4	7.4	422	422	422	422	422	374	6	120					
11	220	1025	715	1740	91	600	559460	84	3.2	223	8860	7.4	7.4	421	422	422	422	422	374	6	120					
12	220	999	749	1748	100	400	582570	84	3.2	223	9080	7.5	7.4	421	422	422	422	422	374	6	120					
13	220	938	750	1748	79	300	61330	81	3.3	224	7880	7.5	7.6	7.4	421	420	422	422	374	6	120					
14	220	821	590	1702	71	0	54220	76	3.0	220	11400	7.5	5.6	7.5	421	420	421	421	373	6	120					
15	220	983	691	1674	65	100	573650	77	3.3	224	7560	7.4	7.4	421	422	422	422	422	373	6	120					
16	220	1043	676	1713	74	100	55000	78	3.1	221	10910	7.4	7.4	422	422	422	422	422	374	6	120					
17	220	939	712	1651	66	200	55000	77	3.1	221	10850	7.5	7.4	421	422	422	422	422	373	6	120					
18	220	942	684	1626	77	150	52820	77	3.2	222	9320	7.5	7.4	421	422	422	422	422	373	6	120					
19	220	890	826	1652	63	200	53250	76	3.2	222	9350	7.5	7.4	421	422	422	422	422	373	6	120					
20	220	817	762	1599	69	200	67820	79	3.2	223	8700	7.5	7.4	421	422	422	422	422	374	6	120					
21	220	869	799	1668	70	200	68410	84	3.1	221	10800	7.5	7.4	421	422	422	422	422	374	6	120					
22	220	921	814	1735	63	200	66480	84	3.0	220	15040	7.5	7.4	421	422	422	422	422	374	6	120					
23	220	925	804	1729	67	200	64570	87	3.0	220	12100	7.5	7.4	421	422	422	422	422	376	6	120					
24	220	907	774	1681	72	190	64230	78	3.1	222	5770	7.5	7.4	421	422	422	422	422	373	6	120					
25	220	956	806	1762	60	100	71650	80	3.0	220	12310	7.5	7.4	421	422	422	422	422	374	6	120					
26	220	877	778	1655	69	100	62450	85	3.0	220	11900	7.5	7.4	421	422	422	422	422	375	6	120					
27	220	910	765	1679	64	100	58970	85	3.0	220	12960	7.5	7.4	421	422	422	422	422	375	6	120					
28	220	917	762	1679	65	100	59080	87	3.0	220	13050	7.5	7.4	421	422	422	422	422	376	6	120					
29	220	912	756	1668	64	100	59170	86	3.0	220	14700	7.5	7.4	421	422	422	422	422	376	6	120					
30	220	934	754	1685	65	200	63870	84	3.0	220	14900	7.5	7.4	421	422	422	422	422	375	6	120					
31	220	951	749	1749	529	73	450	63605	82	3.14	222	10037	7.5	7.4	421	422	422	422	374	6	120					
TOTAL	6600	28532	20236	57228	2200	13182	7181660	2487	94.1	6657	30180	224.5	222.1	126.4	2106	126.6	1123.1	180								
MAXIMUM	220	1152	816	1853	104	1665	88270	93	3.3	224	17080	7.6	7.6	7.5	422	422	422	422	377	6						
MINIMUM	220	660	590	1554	60	100	52270	76	3.0	220	7600	7.4	7.4	7.4	420	420	421	421	373	6						
AVERAGE	220	951	749	1749	529	73	450	63605	82	3.14	222	10037	7.5	7.4	421	422	422	422	374	6						
EVAPORATION LB. STEAM PER LB. STD. FUEL																										
FUEL USED DURING MONTH (STANDARD TONS)																										
WOOD: 792, OIL: 73.13, NAT. GAS: 374.54																										
REMARKS: 3220																										
PREPARED BY: [Signature]																										
DATE: 4/26/93																										
APPROVED BY: [Signature]																										
DATE: 4/26/93																										
POST ENGINEER																										
No. 7054																										

27/93

For use of this term, see AR 420.49; the proponent agency is the Corps of Engineers.

For use of this term, see AR 420-49; the proponent agency is the Corps of Engineers.

SEE REVERSE SIDE FOR INSTRUCTIONS	PREPARED BY <i>W. Edgar L. Brown</i>		DATE <i>7 Jan 93</i>	APPROVED BY <i>W. Edgar L. Brown</i>	DATE <i>8 Jan 93</i>	POST ENGINEER DAVID A. FAGAN, LTC, EN, DEH	DATE <i>6/78/93</i>
	WOOD: 168264, OIL: 158.58 NAT. GAS: 380.97 * RECLAIMED OIL F.S.: 12 265, NO. 2 OIL: 16318						

DA FORM 3967
NOV 72

DA FORM 1 NOV 72 3967

REPLACES DA FORM 5-90, 1 JUN 50, WHICH WILL BE USED.

A.5-96

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-49; the proponent agency is USACE.

INSTALLATION										PLANT		BLDG. NO.		MONTH								
HEADQUARTERS FORT STEWART FORT STEWART, GEORGIA 31313										CENTRAL ENERGY PLANT		1412		MAR 1993								
DATE	STEAM PRODUCED			WATER TONS BOILER	OIL FUEL USED GAL	NAT. GAS USED GAL	OUTSIDE TEMP. °F	FEEDWATER HEATER		PRESS. LB.	TEMP. °F	MAKUP GAL	BOILER			%CO2	FLUE GAS TEMPERATURE			TEMP. H.W. SUPPLY °F	TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT CHECK
	STEAM PRESSURE PSI	1 1000LB.	2 1000LB.					3 1000LB.	1 1000LB.				2 1000LB.	3 1000LB.	1 1000LB.		2 1000LB.	3 1000LB.	1 1000LB.			
1	220	125	1657	206	1168	11490	47	3.0	220	18040	7.6	7.4	140	119	118	370	6	ELB				
2	220	120	430	51	483	72630	49	3.0	220	16740	7.6	7.4	140	119	118	370	6	ELB				
3	220	900		615	487	74000	58	3.0	220	14370	7.4	7.5	140	119	118	370	6	ELB				
4	220	800	80	660	150	89200	56	3.0	220	16950	7.4	7.5	140	119	118	370	6	ELB				
5	220	71	1683	211	1100	53370	51	3.0	220	16710	7.6	7.4	140	119	118	370	6	ELB				
6	220	1730			2012	10020	50	3.0	220	14890	7.4	7.4	140	119	118	370	6	ELB				
7	220	1707			227	10020	53	3.0	220	18500	7.4	7.4	140	119	118	370	6	ELB				
8	220	1552			199	12360	53	3.0	220	21990	7.4	7.4	140	119	118	370	6	ELB				
9	220	47	1327		181	436	35080	63	3.0	220	18800	7.6	7.4	140	119	118	370	6	ELB			
10	220	170	1368		188	360	108780	68	3.0	220	18830	7.6	7.4	140	119	118	370	6	ELB			
11	220	706	1415		194	490	72530	60	3.0	220	14170	7.6	7.4	140	119	118	370	6	ELB			
12	220	1780			130	400	9360	56	3.0	220	11060	7.4	7.4	140	119	118	370	6	ELB			
13	220	557	1984		130	200	44860	46	3.0	220	13390	7.5	7.4	140	119	118	370	6	ELB			
14	220	1984			158	440	100	34	3.4	224	6120	7.4	7.4	140	119	118	370	6	ELB			
15	220	2028			163	460	8080	36	3.2	223	9890	7.4	7.4	140	119	118	370	6	ELB			
16	220	1916			155	470	16170	47	3.2	223	9730	7.4	7.4	140	119	118	370	6	ELB			
17	220	1648			222	270	3159	57	3.4	224	1001	7.4	7.4	140	119	118	370	6	ELB			
18	220	1717			230	552	21901	49	3.4	224	1095	7.4	7.4	140	119	118	370	6	ELB			
19	220	1842			231	1354	43860	42	3.3	223	5530	7.4	7.4	140	119	118	370	6	ELB			
20	220	1440			180	1051	113640	50	3.1	221	9830	7.4	7.4	140	119	118	370	6	ELB			
21	220	1605			204	2112	8210	58	3.0	220	12150	7.4	7.4	140	119	118	370	6	ELB			
22	220	1737			204	2112	2300	62	3.0	220	14620	7.4	7.4	140	119	118	370	6	ELB			
23	220	1702			211	1427	25780	64	3.0	220	13280	7.4	7.4	140	119	118	370	6	ELB			
24	220	1689			128	170	7300	66	3.2	222	8670	7.4	7.4	140	119	118	370	6	ELB			
25	220	1687			124	470	16160	72	3.1	221	10170	7.4	7.4	140	119	118	370	6	ELB			
26	220	1761			133	500	11480	56	3.0	220	12720	7.4	7.4	140	119	118	370	6	ELB			
27	220	1715			130	300	22100	62	3.1	221	10550	7.4	7.4	140	119	118	370	6	ELB			
28	220	1714			132	230	9850	64	3.2	222	9700	7.4	7.4	140	119	118	370	6	ELB			
29	220	1698			131	160	15300	65	3.0	220	15510	7.4	7.4	140	119	118	370	6	ELB			
30	220	1698			223	220	13270	68	3.0	220	12660	7.4	7.4	140	119	118	370	6	ELB			
31	220	1629			200	1471	16850	64	3.0	223	8830	7.4	7.4	140	119	118	370	6	ELB			
TOTAL	6820	2896	46765	2275	51936	5086	373600	1732	95.8	6851	386400	67.9	222.5	22.0	378.5	126.5	11470	186				
MAXIMUM	220	900	2028	1000	2028	231	2112	91820	72	3.4	224	2190	7.6	7.5	422	422	422	370	6			
MINIMUM	220	47	80	615	1374	11	150	100	34	3.0	220	1001	7.4	7.4	420	420	420	370	6			
AVERAGE	220	322	1557	758	1675	170	712	120518	56	3.1	221	1247	7.54	7.47	420.6	421.8	421.3	370	6			

REMARKS

FUEL USED DURING MONTH (STANDARD TONS)

EVAPORATION LB. STEAM PER LB. STD. FUEL

SEE REVERSE SIDE
FOR INSTRUCTIONS

PREPARED BY

DATE

10 Dec 93

APPROVED BY

DATE

POST ENGINEER

DATE

*Reclaimed Oil From F.S. = 15,889 G.; No. 2 Oil 6117 qt.

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-49; the proponent agency is USACE.

DATE	STEAM PRODUCED										WOOD TONS	OIL FUEL USED GAL	NATURAL GAS USED CU. FT.	OUTSIDE TEMP. AV.	FEEDWATER HEATER		%CO ₂			FLUE GAS TEMPERATURE						TUBES CLEANED NUMBER OF TIMES	PREVENT MAINT. CHECK	DATE																								
	STEAM PRESSURE		BOILER			TOTAL	1000 LB.	1000 LB.	1000 LB.	1000 LB.					1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.				1000 LB.	1000 LB.	1000 LB.																					
	LB.	PSI	1	2	3																											1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3
1	220	1697	199	2044	11010	54	3.2	222	9170	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
2	220	1917	229	2089	13390	41	3.0	220	13540	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
3	220	1939	259	504	26380	42	3.0	220	13330	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
4	220	1817	259	1817	10020	48	3.1	221	10340	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
5	220	1754	242	1754	7650	49	3.1	220	13000	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
6	220	1738	226	1738	57740	49	3.2	222	8930	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
7	220	1847	254	1847	12220	45	3.0	220	12480	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
8	220	1898	261	1898	25230	45	3.0	220	11700	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
9	220	1897	261	1897	4910	48	3.0	220	11550	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
10	220	1871	258	1871	9400	50	3.0	220	13350	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
11	220	1723	229	1723	10640	54	3.0	220	12480	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
12	220	1804	223	1804	6700	62	3.0	220	13510	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
13	220	1960	243	1960	16690	50	3.0	220	14130	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
14	220	2033	249	1723	8980	47	3.0	220	13920	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
15	220	2040	251	1723	9640	48	3.0	220	14010	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
16	220	1875	259	1723	3080	58	3.0	220	18210	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
17	220	2024	280	1763	2289	47	3.0	220	16310	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
18	220	1960	255	1763	8911	40	3.0	220	13790	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
19	220	2108	260	1802	4890	37	3.0	220	16060	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
20	220	1905	262	1180	11950	48	3.0	220	15080	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
21	220	1658	228	9420	59	3.0	220	16030	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
22	220	1481	199	27140	63	3.0	220	16000	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
23	220	1660	229	10600	52	3.0	220	17780	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
24	220	1816	250	8490	47	3.0	220	18450	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
25	220	1916	264	11600	42	3.0	220	17840	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
26	220	200	200	845	11472	45	3.0	220	15420	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
27	220	1873	255	10248	44	3.0	220	14460	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
28	220	1695	233	57250	44	3.0	220	16250	7.4	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119	119																									
29																																																				
30																																																				
31																																																				
TOTAL	6160	988	5006	845	51849	6888	28020	61070	1358	584.5	6165	40679	30.2	207.4	7.4	1682	11814	422	10380	168																																
MAXIMUM	220	800	2108	845	2108	280	11472	9620	63	3.2	222	18450	7.6	7.6	7.4	422	422	422	370	6																																
MINIMUM	220	30	1200	845	1481	28	500	4840	37	3.0	220	9330	7.4	7.4	7.4	420	420	422	370	6																																
AVERAGE	220	247	1786	845	1852	246	2335	21824	49	3.0	220.3	14317	7.55	7.41	7.4	420.5	421.9	422	370	6																																
VAPORATION LB. STEAM PER LB. STD. FUEL.																																																				
WOOD: 2477.68, OIL: 155.49, NAT. GAS: 25.2																																																				
FUEL USED DURING MONTH (STANDARD TONS)																																																				
REMARKS: 400 930																																																				
* = RECLATHED OIL FROM F.S. = 16548 GALL. NO. 2 OIL = 11472 G-4																																																				
APPROVED BY																																																				
DATE																																																				
POST ENGINEER																																																				
DATE																																																				
SEE REVERSE SIDE FOR INSTRUCTIONS																																																				

A.5-98

FACILITIES ENGINEERING OPERATING LOG (Boiler Plant)

For use of this form, see AR 420-49; the proponent agency is USACE.

INSTALLATION										HEADQUARTERS FORT STEWART FORT STEWART, GEORGIA 31313				PLANT CENTRAL ENERGY PLANT				BLDG. NO. 1412		MONTH JAN 1993	
DATE		STEAM PRODUCED		WATER USED		OIL FUEL USED		WATER		FEEDWATER HEATER		%CO2		FLUE GAS TEMPERATURE		TEMP. H.W. SUPPLY		TUBES CLEANED NUMBER OF TIMES		PREVENT MAINT. CHECK	
LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	1000 LB.	
1	220	1305	1305	177	150	12010	61	3.4	224	111	112	9460	7.4	119	117	422	370	6	HEB	121	
2	220	1458	1458	197	200	8310	52	3.1	221	10430	7.4	114	117	422	370	6	HEB	121	121		
3	220	1539	1539	208	200	18080	51	3.0	220	14420	7.4	114	117	422	370	6	HEB	121	121		
4	220	1211	1211	250	170	145060	59	3.4	224	6100	7.4	114	117	422	370	6	HEB	121	121		
5	220	1164	1164	158	150	7890	67	3.1	221	9640	7.4	114	117	422	370	6	HEB	121	121		
6	220	1179	1179	160	150	5826	66	3.1	221	10480	7.4	114	117	422	370	6	HEB	121	121		
7	220	1198	1198	20	1053	41540	60	3.0	220	11430	7.4	114	117	422	370	6	HEB	121	121		
8	220	1247	1247	143	1700	4948	65	3.0	220	11000	7.4	114	117	422	370	6	HEB	121	121		
9	220	1281	1281	140	2190	5030	57	3.1	221	9920	7.4	114	117	422	370	6	HEB	121	121		
10	220	1578	1578	184	1943	13390	47	3.0	220	16570	7.4	114	117	422	370	6	HEB	121	121		
11	220	1652	1652	206	1204	1940	49	3.2	223	9230	7.4	114	117	422	370	6	HEB	121	121		
12	220	1627	1627	220	200	11540	51	3.1	221	10850	7.4	114	117	422	370	6	HEB	121	121		
13	220	1469	1469	199	170	6350	60	3.0	220	11550	7.4	114	117	422	370	6	HEB	121	121		
14	220	1602	1602	217	200	540	50	3.1	221	10170	7.4	114	117	422	370	6	HEB	121	121		
15	220	1691	1691	229	210	10460	47	3.1	221	9770	7.4	114	117	422	370	6	HEB	121	121		
16	220	1676	1676	230	200	10090	46	3.1	221	10350	7.4	114	117	422	370	6	HEB	121	121		
17	220	1657	1657	225	200	12060	49	3.0	220	11180	7.4	114	117	422	370	6	HEB	121	121		
18	220	1629	1629	221	180	4750	52	3.1	221	9600	7.4	114	117	422	370	6	HEB	121	121		
19	220	1646	1646	224	170	7980	51	3.0	220	11750	7.4	114	117	422	370	6	HEB	121	121		
20	220	1850	1850	249	366	13860	43	3.0	220	11790	7.4	114	117	422	370	6	HEB	121	121		
21	220	1565	1565	189	1593	3150	59	3.3	224	6840	7.4	114	117	422	370	6	HEB	121	121		
22	220	917	917	250	193	1485	351830	60	3.3	224	7260	7.4	114	117	422	370	6	HEB	121	121	
23	220	1511	1511	184	1429	19460	51	3.0	220	11100	7.4	114	117	422	370	6	HEB	121	121		
24	220	1515	1515	184	1380	26380	57	3.2	222	9130	7.4	114	117	422	370	6	HEB	121	121		
25	220	1757	1757	238	200	4970	43	3.1	221	10330	7.4	114	117	422	370	6	HEB	121	121		
26	220	1857	1857	252	220	17180	40	3.0	220	10960	7.4	114	117	422	370	6	HEB	121	121		
27	220	1914	1914	260	180	13670	44	3.1	221	10470	7.4	114	117	422	370	6	HEB	121	121		
28	220	1704	1704	231	206	17360	47	3.1	221	9710	7.4	114	117	422	370	6	HEB	121	121		
29	220	1603	1603	217	210	11510	52	3.1	221	10680	7.4	114	117	422	370	6	HEB	121	121		
30	220	1808	1808	211	224	11850	48	3.0	220	11010	7.4	114	117	422	370	6	HEB	121	121		
31	220	1807	1807	244	240	1740	46	3.1	221	10800	7.4	114	117	422	370	6	HEB	121	121		
TOTAL	6820	47637	520	213	48370	6207	20537	83039	1630	96.2	6855	32430	2294	22.8	15.2	13082	1260	11470	186		
MAXIMUM	220	1914	250	193	1914	260	2224	351830	67	3.5	225	16570	7.4	7.6	7.6	422	420	370	6		
MINIMUM	220	917	20	20	1164	100	150	540	40	3.0	220	6100	7.4	7.6	7.6	422	420	370	6		
AVERAGE	220	1537	173	107	1560	200	662	26786	53	3.1	221	10462	7.4	7.6	7.6	422	420	370	6		
FUEL USED DURING MONTH (STANDARD TONS)																					
WOOD: 2235.24, OIL: 115.37, NAT. GAS: 34.24																					
REMARKS: 204080																					
APPROVED BY: <i>William T. Rame</i> DATE: 10 Feb. 93																					
POST ENGINEER: <i>William T. Rame</i> DATE: 10 Feb. 93																					

SEE REVERSE SIDE
FOR INSTRUCTIONS

No. 2014: 5736

MAKE-UP WATER DATA

A.5-99

HTW System Makeup Water

Month	Year	WS Makeup Gal(1)	Days/ Month	Avg WS Makeup Gal/Day	Max WS Makeup Gal/Day	Min WS Makeup Gal/Day	Max WS Makeup Gal/Min	Avg WS Makeup Gal/Min	Min WS Makeup Gal/Min
1	93	324080	31	10454	16570	6100	11.5	7.3	4.2
2	93	400920	28	14319	18450	8930	12.8	9.9	6.2
3	93	386430	31	12465	21990	1001	15.3	8.7	0.7
4	93	425830	30	14194	25710	8140	17.9	9.9	5.7
5	93	258830	31	8349	14710	4980	10.2	5.8	3.5
6	93	312260	30	10409	19070	7600	13.2	7.2	5.3
7	93	388480	31	12532	16000	7630	11.1	8.7	5.3
8	93	432570	31	13954	26530	8970	18.4	9.7	6.2
9	93	358820	30	11961	17160	6310	11.9	8.3	4.4
10	93	391750	31	12637	19420	7500	13.5	8.8	5.2
11	93	477570	30	15919	23970	9580	16.6	11.1	6.7
12	93	531190	31	17135	27800	9850	19.3	11.9	6.8
1	94	626020	31	20194	27840	14630	19.3	14.0	10.2
2	94	551230	28	19687	26080	14200	18.1	13.7	9.9
3	94	793890	31	25609	31750	17320	22.0	17.8	12.0
4	94	453420	30	15114	27130	3840	18.8	10.5	2.7
5	94	309740	31	9992	14070	5510	9.8	6.9	3.8
6	94	352590	30	11753	17920	4580	12.4	8.2	3.2
7	94	540670	31	17441	25130	10620	17.5	12.1	7.4
8	94	404010	31	13033	19920	5240	13.8	9.1	3.6
9	94	246270	30	8209	17800	1390	12.4	5.7	1.0
10	94	136380	31	4399	12550	900	8.7	3.1	0.6
11	94	442980	30	14766	23010	1910	16.0	10.3	1.3
12	94	419160	31	13521	20800	7830	14.4	9.4	5.4
1	95	403420	31	13014	17980	8370	12.5	9.0	5.8
2	95	445340	28	15905	25150	11150	17.5	11.0	7.7
3	95	360940	31	11643	18680	7520	13.0	8.1	5.2
4	95	274470	30	9149	14330	5480	10.0	6.4	3.8
5	95	206480	31	6661	11300	2290	7.8	4.6	1.6
6	95	224250	30	7475	11450	4920	8.0	5.2	3.4
7	95	254190	31	8200	11360	3470	7.9	5.7	2.4
8	95	237210	31	7652	10490	5420	7.3	5.3	3.8
9	95	216450	30	7215	11980	3780	8.3	5.0	2.6
10	95	206690	31	6667	12230	3980	8.5	4.6	2.8
11	95	261230	30	8708	16220	2280	11.3	6.0	1.6
12	95	259510	31	8371	12610	4110	8.8	5.8	2.9
3 Yr		Min		4399	10490	900	7.3	3.1	0.6
		Avg		12186	19032	6593	13.2	8.5	4.6
		Max		25609	31750	17320	22.0	17.8	12.0
1993		Min		8349	14710	1001	10.2	5.8	0.7
		Avg		12861	20615	7216	14.3	8.9	5.0
		Max		17135	27800	9850	19.3	11.9	6.8
1994		Min		4399	12550	900	8.7	3.1	0.6
		Avg		14477	22000	7331	15.3	10.1	5.1
		Max		25609	31750	17320	22.0	17.8	12.0
1995		Min		6661	10490	2280	7.3	4.6	1.6
		Avg		9222	14482	5231	10.1	6.4	3.6
		Max		15905	25150	11150	17.5	11.0	7.7

(1) Source is Fort Stewart Boiler Operating Logs.
WS - Water softener makeup water from meter readings.

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM	-- ANNUAL STATS --	
	1	12340			8.6		AVG GPM	6.4
	2	14200			9.9		MIN GPM	1.6
	3	11070			7.7		MAX GPM	17.5
	4	16470			11.4		STD DEV	2.5
	5	14790			10.3		VARIANC	6.0
	6	8750			6.1		FREQUENCY:	
	7	11670			8.1		GPM	NO. DAYS
	8	11310			7.9		0	0
	9	10650			7.4		1	0
	10	12070			8.4		2	3
	11	8370			5.8		3	15
	12	10090			7.0		4	31
	13	15170			10.5		5	62
JAN	14	13320			9.3		6	81
	15	15450		13014	10.7	9.0	7	55
	16	15060			10.5		8	40
	17	15040			10.4		9	22
	18	13900			9.7		10	20
	19	17980			12.5		11	18
	20	14010			9.7		12	8
	21	9440			6.6		13	7
	22	12120			8.4		14	1
	23	16140			11.2		15	0
	24	13080			9.1		16	0
	25	14830			10.3		17	0
	26	13280			9.2		18	0
	27	14760			10.3		19	2
	28	11050			7.7		20	0
	29	11390			7.9		21	0
	30	11720			8.1		22	0
	31	13900	403420		9.7		23	0
*	1	14140			9.8		24	0
*	2	15460			10.7		25	0
	3	14990			10.4			
	4	16660			11.6			
	5	16630			11.5			
	6	12940			9.0			
	7	17370			12.1			
	8	17540			12.2			
	9	19240			13.4			
	10	17320			12.0			
	11	15500			10.8			
	12	14720			10.2			
FEB	13	11430			7.9			
	14	18050		15905	12.5	11.0		
	15	25150			17.5			
	16	14280			9.9			
	17	12940			9.0			
	18	11150			7.7			
	19	17920			12.4			
	20	11550			8.0			
	21	15790			11.0			
	22	13680			9.5			
*	23	17120			11.9			
*	24	14610			10.1			
*	25	16360			11.4			
*	26	15940			11.1			
*	27	24830			17.2			
	28	12030	445340		8.4			

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
MAR	1	18680			13.0	
	2	13870			9.6	
	3	7820			5.4	
	4	11000			7.6	
	5	13170			9.1	
	6	10400			7.2	
	7	9140			6.3	
	8	11970			8.3	
	9	14280			9.9	
	10	7520			5.2	
	11	11230			7.8	
	12	14350			10.0	
	13	12910			9.0	
	14	9820			6.8	
	15	12110		11643	8.4	8.1
	16	11250			7.8	
	17	13110			9.1	
	18	9570			6.6	
	19	9070			6.3	
	20	8530			5.9	
	21	9400			6.5	
	22	13730			9.5	
	23	12560			8.7	
	24	14620			10.2	
	25	11200			7.8	
	26	13030			9.0	
	27	11740			8.2	
	28	12100			8.4	
	29	10120			7.0	
	30	8060			5.6	
	31	14580	360940		10.1	
APR	1	14330			10.0	
	2	9910			6.9	
	3	11410			7.9	
	4	11550			8.0	
	5	9830			6.8	
	6	12590			8.7	
	7	9140			6.3	
	8	10320			7.2	
	9	10890			7.6	
	10	10450			7.3	
	11	7720			5.4	
	12	7590			5.3	
	13	11020			7.7	
	14	10580			7.3	
	15	6900		9149	4.8	6.4
	16	8440			5.9	
	17	7340			5.1	
	18	8490			5.9	
	19	8670			6.0	
	20	9790			6.8	
	21	7940			5.5	
	22	10940			7.6	
	23	8580			6.0	
	24	10600			7.4	
	25	7940			5.5	
	26	5740			4.0	
	27	6000			4.2	
	28	6450			4.5	
	29	7840			5.4	
	30	5480	274470		3.8	

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	5980			4.2	
	2	6010			4.2	
	3	8030			5.6	
	4	5320			3.7	
	5	4060			2.8	
	6	4220			2.9	
	7	3010			2.1	
	8	6450			4.5	
	9	3750			2.6	
	10	8950			6.2	
	11	8110			5.6	
	12	8800			6.1	
	13	6440			4.5	
	14	10390			7.2	
MAY	15	2290		6661	1.6	4.6
	16	11300			7.8	
	17	7640			5.3	
	18	5090			3.5	
	19	7570			5.3	
	20	7480			5.2	
	21	7700			5.3	
	22	6610			4.6	
	23	5550			3.9	
	24	7630			5.3	
	25	8710			6.0	
	26	4480			3.1	
	27	6470			4.5	
	28	8600			6.0	
	29	6160			4.3	
	30	7890			5.5	
	31	5790	206480		4.0	
	1	7500			5.2	
	2	6180			4.3	
	3	5920			4.1	
	4	8410			5.8	
	5	7600			5.3	
	6	9190			6.4	
	7	8430			5.9	
	8	5840			4.1	
	9	5910			4.1	
	10	5520			3.8	
	11	8310			5.8	
	12	9230			6.4	
	13	11450			8.0	
	14	6480			4.5	
JUN	15	5440		7475	3.8	5.2
	16	7380			5.1	
	17	8080			5.6	
	18	7860			5.5	
	19	5700			4.0	
	20	5630			3.9	
	21	6830			4.7	
	22	9310			6.5	
	23	9960			6.9	
	24	7900			5.5	
	25	7090			4.9	
	26	6240			4.3	
	27	8960			6.2	
	28	9520			6.6	
	29	7460			5.2	
	30	4920	224250		3.4	

1995 DAILY MAKEUP WATER

MONT	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	4430			3.1	
	2	10620			7.4	
	3	3470			2.4	
	4	6990			4.9	
	5	6240			4.3	
	6	7810			5.4	
	7	7480			5.2	
	8	8010			5.6	
	9	9520			6.6	
	10	8050			5.6	
	11	6780			4.7	
	12	9470			6.6	
	13	4470			3.1	
JUL	14	5610			3.9	
	15	8480		8200	5.9	5.7
	16	8390			5.8	
	17	7710			5.4	
	18	7640			5.3	
	19	9320			6.5	
	20	9930			6.9	
	21	9370			6.5	
	22	9080			6.3	
	23	7480			5.2	
	24	8180			5.7	
	25	11360			7.9	
	26	11130			7.7	
	27	9760			6.8	
	28	10420			7.2	
	29	8090			5.6	
	30	9080			6.3	
	31	9820	254190		6.8	
	1	8710			6.0	
	2	9470			6.6	
	3	9580			6.7	
	4	7020			4.9	
	5	10200			7.1	
	6	8420			5.8	
	7	10430			7.2	
	8	7210			5.0	
	9	5910			4.1	
	10	7260			5.0	
	11	6470			4.5	
	12	8320			5.8	
	13	6970			4.8	
AUG	14	6640			4.6	
	15	8410		7652	5.8	5.3
	16	7340			5.1	
	17	6900			4.8	
	18	7630			5.3	
	19	6560			4.6	
	20	5820			4.0	
	21	8020			5.6	
	22	5420			3.8	
	23	5720			4.0	
	24	6840			4.8	
	25	10490			7.3	
	26	7220			5.0	
	27	8840			6.1	
	28	8430			5.9	
	29	7290			5.1	
	30	6740			4.7	
	31	6930	237210		4.8	

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
SEP	1	6230			4.3	
	2	7940			5.5	
	3	8070			5.6	
	4	7700			5.3	
	5	7500			5.2	
	6	8860			6.2	
	7	5560			3.9	
	8	10300			7.2	
	9	7020			4.9	
	10	8560			5.9	
	11	6130			4.3	
	12	6120			4.3	
	13	6990			4.9	
	14	11980			8.3	
	15	6280		7215	4.4	5.0
	16	8570			6.0	
	17	7990			5.5	
	18	8650			6.0	
	19	8510			5.9	
	20	9720			6.8	
	21	7250			5.0	
	22	6760			4.7	
	23	4550			3.2	
	24	6280			4.4	
	25	6330			4.4	
	26	3780			2.6	
	27	4080			2.8	
	28	7400			5.1	
	29	5020			3.5	
	30	6320	216450		4.4	
OCT	1	4280			3.0	
	2	4230			2.9	
	3	6570			4.6	
	4	6580			4.6	
	5	6180			4.3	
	6	5740			4.0	
	7	7050			4.9	
	8	6500			4.5	
	* 9	5970			4.1	
	10	10080			7.0	
	11	12230			8.5	
	12	6710			4.7	
	13	7390			5.1	
	* 14	11110			7.7	
	15	7610		6667	5.3	4.6
	16	8260			5.7	
	17	5620			3.9	
	18	6820			4.7	
	19	7070			4.9	
	20	7160			5.0	
	21	7740			5.4	
	22	7410			5.1	
	23	6120			4.3	
	24	4970			3.5	
	25	5040			3.5	
	26	5710			4.0	
	27	6750			4.7	
	28	4370			3.0	
	29	3980			2.8	
	30	6330			4.4	
	31	5110	206690		3.5	

1995 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	4020			2.8	
	2	5090			3.5	
	3	3730			2.6	
	4	7330			5.1	
	5	2280			1.6	
	6	7650			5.3	
	7	2440			1.7	
	8	3700			2.6	
	9	9110			6.3	
	10	10140			7.0	
	11	5410			3.8	
	12	6830			4.7	
	13	10080			7.0	
NOV	14	9320			6.5	
	15	12200		8708	8.5	6.0
	16	13450			9.3	
	17	16220			11.3	
	18	14560			10.1	
	19	10130			7.0	
	20	13380			9.3	
	21	14530			10.1	
	22	14460			10.0	
	23	10020			7.0	
	24	7950			5.5	
	25	11720			8.1	
	26	4100			2.8	
	27	4450			3.1	
	28	10070			7.0	
	29	9450			6.6	
	30	7410	261230		5.1	
	1	7430			5.2	
	2	9300			6.5	
	3	10090			7.0	
	4	8930			6.2	
	5	9170			6.4	
	6	6500			4.5	
	7	9930			6.9	
	8	7770			5.4	
	9	7430			5.2	
	10	9410			6.5	
	11	9100			6.3	
	12	8010			5.6	
	13	9780			6.8	
DEC	14	9470			6.6	
	15	10930		8371	7.6	5.8
	16	8650			6.0	
	17	9770			6.8	
	18	8500			5.9	
	19	6790			4.7	
	20	7300			5.1	
	21	7620			5.3	
	22	4110			2.9	
	23	6220			4.3	
	24	7180			5.0	
	25	4420			3.1	
	26	5050			3.5	
	27	7010			4.9	
	28	9310			6.5	
	29	10690			7.4	
	30	11030			7.7	
	31	12610	259510		8.8	

1994 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM	-- ANNUAL STATS --	
JAN	1	19660	20194	14.0	13.7	14.0	AVG GPM	10.0
	2	22970			16.0		MIN GPM	0.6
	3	27360			19.0		MAX GPM	22.0
	4	14630			10.2		STD DEV	4.7
	5	15970			11.1		VARIANC	22.1
	6	19580			13.6		FREQUENCY:	
	7	24220			16.8		GPM	NO. DAYS
	8	25780			17.9		0	0
	9	26590			18.5		1	5
	10	26270			18.2		2	18
	11	27840			19.3		3	3
	12	22680			15.8		4	9
	13	22050			15.3		5	9
	14	15020			10.4		6	25
	15	21080			14.6		7	35
	16	22930			15.9		8	36
	17	17550			12.2		9	25
	18	20730			14.4		10	25
	19	23850			16.6		11	24
	20	22130			15.4		12	25
	21	18870			13.1		13	28
	22	18690			13.0		14	21
	23	16020			11.1		15	16
	24	19140			13.3		16	18
	25	17180			11.9		17	14
	26	14130			9.8		18	8
	27	17120			11.9		19	10
	28	16350			11.4		20	7
	29	17580			12.2		21	1
	30	14480			10.1		22	2
	31	17570			12.2		23	1
FEB	1	14200	626020	19687	9.9	13.7	24	0
	2	17160			11.9		25	0
	3	17440			12.1			
	4	15090			10.5			
	5	15960			11.1			
	6	20770			14.4			
	7	15340			10.7			
	8	17870			12.4			
	9	19420			13.5			
	10	18420			12.8			
	11	20090			14.0			
	12	19010			13.2			
	13	18160			12.6			
	14	21660			15.0			
	15	20380			14.2			
	16	23820			16.5			
	17	20440			14.2			
	18	16770			11.6			
	19	20080			13.9			
	20	25150			17.5			
	21	21440			14.9			
	22	21490			14.9			
	23	26080			18.1			
	24	22740			15.8			
	25	21170			14.7			
	26	21720			15.1			
	27	19240			13.4			
	28	20120			14.0			

1994 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	25100			17.4	
	2	20320			14.1	
	3	23790			16.5	
	4	22910			15.9	
	5	17320			12.0	
	6	25540			17.7	
	7	23860			16.6	
	8	22170			15.4	
	9	20290			14.1	
	10	26490			18.4	
	11	28540			19.8	
	12	23920			16.6	
	13	23450			16.3	
	14	27460			19.1	
MAR	15	25260		25609	17.5	17.8
	16	26090			18.1	
	17	26040			18.1	
	18	23560			16.4	
	19	24360			16.9	
	20	29390			20.4	
	21	28510			19.8	
	22	26570			18.5	
	23	28150			19.5	
	24	27000			18.8	
	25	31750			22.0	
	26	24160			16.8	
	27	27560			19.1	
	28	31250			21.7	
	29	31630			22.0	
	30	28450			19.8	
	31	23000	793890		16.0	
	1	22740			15.8	
	2	27130			18.8	
	3	22670			15.7	
	4	22190			15.4	
	5	23930			16.6	
	6	24730			17.2	
	7	24140			16.8	
	8	20050			13.9	
	9	22500			15.6	
	10	21360			14.8	
	11	25540			17.7	
	12	16220			11.3	
	13	24130			16.8	
	14	10810			7.5	
APR	15	4740		15114	3.3	10.5
	16	4500			3.1	
	17	10250			7.1	
	18	10280			7.1	
	19	13500			9.4	
	20	10280			7.1	
	21	8250			5.7	
	22	3840			2.7	
	23	4600			3.2	
	24	10260			7.1	
	25	9830			6.8	
	26	10130			7.0	
	27	10010			7.0	
	28	7180			5.0	
	29	13110			9.1	
	30	14520	453420		10.1	

1994 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	9870			6.9	
	2	14070			9.8	
	3	7580			5.3	
	4	9980			6.9	
	5	11910			8.3	
	6	7940			5.5	
	7	12030			8.4	
	8	9730			6.8	
	9	8760			6.1	
	10	9730			6.8	
	11	11390			7.9	
	12	8350			5.8	
	13	9510			6.6	
	14	11480			8.0	
MAY	15	8280		9992	5.8	6.9
	16	5680			3.9	
	17	10250			7.1	
	18	7530			5.2	
	19	9460			6.6	
	20	11870			8.2	
	21	12320			8.6	
	22	11510			8.0	
	23	8470			5.9	
	24	12550			8.7	
	25	9700			6.7	
	26	10950			7.6	
	27	10170			7.1	
	28	7960			5.5	
	29	9910			6.9	
	30	8850			6.1	
	31	11950	309740		8.3	
	1	7550			5.2	
	2	13240			9.2	
	3	10770			7.5	
	4	10470			7.3	
	5	8960			6.2	
	6	9080			6.3	
	7	11300			7.8	
	8	9000			6.3	
	9	4580			3.2	
	10	8000			5.6	
	11	9520			6.6	
	12	11130			7.7	
	13	12140			8.4	
	14	9190			6.4	
JUN	15	12370		11753	8.6	8.2
	16	11090			7.7	
	17	14450			10.0	
	18	11890			8.3	
	19	11050			7.7	
	20	14080			9.8	
	21	14310			9.9	
	22	17920			12.4	
	23	9720			6.8	
	24	15530			10.8	
	25	14020			9.7	
	26	15320			10.6	
	27	14220			9.9	
	28	14180			9.8	
	29	12200			8.5	
	30	15310	352590		10.6	

1994 DAILY MAKEUP WATER

MONT	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	12920			9.0	
	2	15930			11.1	
	3	12250			8.5	
	4	12760			8.9	
	5	13570			9.4	
	6	10620			7.4	
	7	21960			15.3	
	8	14500			10.1	
	9	18370			12.8	
	10	15400			10.7	
	11	17130			11.9	
	12	17310			12.0	
	13	25130			17.5	
	14	21390			14.9	
JUL	15	13200		17441	9.2	12.1
	16	18480			12.8	
	17	17870			12.4	
	18	18070			12.5	
	19	20870			14.5	
	20	18490			12.8	
	21	21440			14.9	
	22	17360			12.1	
	23	17800			12.4	
	24	15020			10.4	
	25	20240			14.1	
	26	18840			13.1	
	27	17160			11.9	
	28	19530			13.6	
	29	16960			11.8	
	30	23240			16.1	
	31	16860	540670		11.7	
	1	19920			13.8	
	2	17770			12.3	
	3	18120			12.6	
	4	19050			13.2	
	5	13080			9.1	
	6	13540			9.4	
	7	16090			11.2	
	8	17210			12.0	
	9	16420			11.4	
	10	12430			8.6	
	11	17110			11.9	
	12	14850			10.3	
	13	15990			11.1	
	14	15020			10.4	
AUG	15	18590		13033	12.9	9.1
	16	17880			12.4	
	17	13990			9.7	
	18	11160			7.8	
	19	5240			3.6	
	20	9080			6.3	
	21	10430			7.2	
	22	9310			6.5	
	23	6640			4.6	
	24	11450			8.0	
	25	8500			5.9	
	26	5730			4.0	
	27	9470			6.6	
	28	11630			8.1	
	29	12460			8.7	
	30	8540			5.9	
	31	7310	404010		5.1	

1994 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
SEP	1	6740			4.7	
	2	10850			7.5	
	3	7990			5.5	
	4	7390			5.1	
	5	5060			3.5	
	6	17800			12.4	
	7	9440			6.6	
	8	10420			7.2	
	9	8540			5.9	
	10	8200			5.7	
	11	8060			5.6	
	12	8320			5.8	
	13	5600			3.9	
	14	2070			1.4	
	15	6840		8209	4.8	5.7
	16	6950			4.8	
	17	7080			4.9	
	18	6980			4.8	
	19	9150			6.4	
	20	8690			6.0	
	21	8030			5.6	
	22	9870			6.9	
	23	9440			6.6	
	24	9970			6.9	
	25	1390			1.0	
	26	9570			6.6	
	27	9170			6.4	
	28	10480			7.3	
	29	8210			5.7	
	30	7970	246270		5.5	
OCT	1	7050			4.9	
	2	9190			6.4	
	3	10300			7.2	
	4	6730			4.7	
	5	8520			5.9	
	6	12550			8.7	
	7	11210			7.8	
	8	10010			7.0	
	9	9920			6.9	
	10	9460			6.6	
	11	2120			1.5	
	12	900			0.6	
	13	1600			1.1	
	14	1260			0.9	
	15	2660		4399	1.8	3.1
	16	2470			1.7	
	17	1840			1.3	
	18	2330			1.6	
	19	2140			1.5	
	20	1900			1.3	
	21	1730			1.2	
	22	3020			2.1	
	23	1390			1.0	
	24	2520			1.8	
	25	1950			1.4	
	26	2320			1.6	
	27	1830			1.3	
	28	1870			1.3	
	29	2140			1.5	
	30	950			0.7	
	31	2500	136380		1.7	

1994 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	4120			2.9	
	2	1910			1.3	
	3	13180			9.2	
	4	16220			11.3	
	5	15080			10.5	
	6	14900			10.3	
	7	12210			8.5	
	8	15360			10.7	
	9	18450			12.8	
	10	16470			11.4	
	11	13860			9.6	
	12	14480			10.1	
	13	13250			9.2	
	14	19840			13.8	
NOV	15	22030		14766	15.3	10.3
	16	11030			7.7	
	17	23010			16.0	
	18	12580			8.7	
	19	18870			13.1	
	20	18640			12.9	
	21	14180			9.8	
	22	17650			12.3	
	23	18870			13.1	
	24	13150			9.1	
	25	12510			8.7	
	26	13890			9.6	
	27	12370			8.6	
	28	14820			10.3	
	29	13580			9.4	
	30	16470	442980		11.4	
	1	16310			11.3	
	2	17750			12.3	
	3	12720			8.8	
	4	13390			9.3	
	5	16600			11.5	
	6	18870			13.1	
	7	10970			7.6	
	8	11670			8.1	
	9	10380			7.2	
	10	14540			10.1	
	11	11660			8.1	
	12	15560			10.8	
	13	8080			5.6	
DEC	14	10740			7.5	
	15	10810		13521	7.5	9.4
	16	13500			9.4	
	17	10170			7.1	
	18	10410			7.2	
	19	10490			7.3	
	20	19250			13.4	
	21	19410			13.5	
	22	15300			10.6	
	23	7830			5.4	
	24	10840			7.5	
	25	12690			8.8	
	26	9980			6.9	
	27	17900			12.4	
	28	16480			11.4	
	29	20800			14.4	
	30	9540			6.6	
	31	14520	419160		10.1	

1993 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM		
JAN	1	9460			6.6		-- ANNUAL STATS --	
	2	10430			7.2		AVG GPM	8.9
	3	14420			10.0		MIN GPM	0.7
	4	6100			4.2		MAX GPM	19.3
	5	9640			6.7		STD DEV	2.9
	6	10480			7.3		VARIANC	8.3
	7	11430			7.9		FREQUENCY:	
	8	11100			7.7		GPM	NO. DAYS
	9	9920			6.9		0	0
	10	16570			11.5		1	2
	11	8230			5.7		2	0
	12	10850			7.5		3	1
	13	11550			8.0		4	4
	14	10170			7.1		5	12
	15	9770		10454	6.8	7.3	6	27
	16	10350			7.2		7	44
	17	11180			7.8		8	60
	18	9600			6.7		9	54
	19	11750			8.2		10	54
	20	11790			8.2		11	34
	21	6840			4.8		12	22
	22	7260			5.0		13	23
	23	11100			7.7		14	7
	24	9130			6.3		15	6
	25	10330			7.2		16	4
	26	11960			8.3		17	6
	27	10470			7.3		18	2
	28	9710			6.7		19	2
	29	10680			7.4		20	1
	30	11010			7.6		21	0
	31	10800	324080		7.5		22	0
FEB	1	9170			6.4		23	0
	2	13540			9.4		24	0
	3	13330			9.3		25	0
	4	10340			7.2			
	5	13000			9.0			
	6	8930			6.2			
	7	12480			8.7			
	8	11700			8.1			
	9	11550			8.0			
	10	13350			9.3			
	11	12680			8.8			
	12	13510			9.4			
	13	14130			9.8			
	14	13920		14319	9.7	9.9		
	15	14040			9.8			
	16	18210			12.6			
	17	16830			11.7			
	18	13790			9.6			
	19	16060			11.2			
	20	15080			10.5			
	21	16030			11.1			
	22	16000			11.1			
	23	17780			12.3			
	24	18450			12.8			
	25	17890			12.4			
	26	18420			12.8			
	27	14460			10.0			
	28	16250	400920		11.3			

1993 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	18040			12.5	
	2	16750			11.6	
	3	14370			10.0	
	4	16950			11.8	
	5	16710			11.6	
	6	14800			10.3	
	7	18500			12.8	
	8	21990			15.3	
	9	18800			13.1	
	10	18830			13.1	
	11	14170			9.8	
	12	11060			7.7	
	13	13390			9.3	
MAR	14	6120			4.3	
	15	9890		12465	6.9	8.7
	16	9730			6.8	
	17	1000			0.7	
	18	1100			0.8	
	19	5530			3.8	
	20	9830			6.8	
	21	12150			8.4	
	22	14630			10.2	
	23	13280			9.2	
	24	8670			6.0	
	25	10170			7.1	
	26	12720			8.8	
	27	10550			7.3	
	28	9700			6.7	
	29	15510			10.8	
	30	12660			8.8	
	31	8830	386430		6.1	
	1	11210			7.8	
	2	10680			7.4	
	3	12500			8.7	
	4	9920			6.9	
	5	13090			9.1	
	6	13340			9.3	
	7	8140			5.7	
	8	10130			7.0	
	9	12190			8.5	
	10	12720			8.8	
	11	12030			8.4	
	12	14470			10.0	
	13	14950			10.4	
APR	14	10090			7.0	
	15	13890		14194	9.6	9.9
	16	13900			9.7	
	17	15350			10.7	
	18	13760			9.6	
	19	16130			11.2	
	20	15670			10.9	
	21	15070			10.5	
	22	12290			8.5	
	23	25730			17.9	
	24	17530			12.2	
	25	18320			12.7	
	26	18150			12.6	
	27	21060			14.6	
	28	16190			11.2	
	29	12800			8.9	
	30	14530	425830		10.1	

1993 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
MAY	1	13080	258830	8349	9.1	5.8
	2	14710			10.2	
	3	14360			10.0	
	4	9040			6.3	
	5	8880			6.2	
	6	9600			6.7	
	7	8560			5.9	
	8	8050			5.6	
	9	11450			8.0	
	10	14050			9.8	
	11	8020			5.6	
	12	7630			5.3	
	13	5300			3.7	
	14	7960			5.5	
	15	6090			4.2	
	16	6380			4.4	
	17	6750			4.7	
	18	3880			2.7	
	19	8330			5.8	
	20	6890			4.8	
	21	10360			7.2	
	22	7540			5.2	
	23	6950			4.8	
	24	5900			4.1	
	25	6390			4.4	
	26	4980			3.5	
	27	8180			5.7	
	28	7010			4.9	
	29	9110			6.3	
	30	5570			3.9	
	31	7830			5.4	
JUN	1	8000	312260	10409	5.6	7.2
	2	8610			6.0	
	3	7730			5.4	
	4	8560			5.9	
	5	7600			5.3	
	6	7600			5.3	
	7	10380			7.2	
	8	10600			7.4	
	9	8590			6.0	
	10	9200			6.4	
	11	8860			6.2	
	12	9080			6.3	
	13	7880			5.5	
	14	11640			8.1	
	15	7560			5.3	
	16	10910			7.6	
	17	10850			7.5	
	18	9320			6.5	
	19	9350			6.5	
	20	8700			6.0	
	21	10800			7.5	
	22	19040			13.2	
	23	12100			8.4	
	24	9390			6.5	
	25	12310			8.5	
	26	11990			8.3	
	27	12960			9.0	
	28	13050			9.1	
	29	14700			10.2	
	30	14900			10.3	

1993 DAILY MAKEUP WATER

MONT	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	14560			10.1	
	2	10290			7.1	
	3	14220			9.9	
	4	14180			9.8	
	5	13620			9.5	
	6	13900			9.7	
	7	14670			10.2	
	8	13390			9.3	
	9	14630			10.2	
	10	12170			8.5	
	11	12960			9.0	
	12	14450			10.0	
	13	15640			10.9	
	14	13770			9.6	
JUL	15	14600		12532	10.1	8.7
	16	16030			11.1	
	17	14040			9.8	
	18	14160			9.8	
	19	13000			9.0	
	20	14240			9.9	
	21	10830			7.5	
	22	11320			7.9	
	23	7630			5.3	
	24	9840			6.8	
	25	8500			5.9	
	26	9750			6.8	
	27	10090			7.0	
	28	10370			7.2	
	29	11650			8.1	
	30	10470			7.3	
	31	9510	388480		6.6	
	1	10560			7.3	
	2	12220			8.5	
	3	10070			7.0	
	4	10050			7.0	
	5	8970			6.2	
	6	10750			7.5	
	7	10480			7.3	
	8	15120			10.5	
	9	13750			9.5	
	10	12340			8.6	
	11	12470			8.7	
	12	11780			8.2	
	13	11900			8.3	
	14	10400			7.2	
AUG	15	11780		13954	8.2	9.7
	16	10050			7.0	
	17	12320			8.6	
	18	11710			8.1	
	19	16480			11.4	
	20	11350			7.9	
	21	10950			7.6	
	22	14100			9.8	
	23	12340			8.6	
	24	15240			10.6	
	25	16510			11.5	
	26	18270			12.7	
	27	17960			12.5	
	28	21740			15.1	
	29	21140			14.7	
	30	26530			18.4	
	31	23240	432570		16.1	

1993 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
SEP	1	13990			9.7	
	2	11990			8.3	
	3	12520			8.7	
	4	10900			7.6	
	5	12610			8.8	
	6	15450			10.7	
	7	12290			8.5	
	8	9010			6.3	
	9	12550			8.7	
	10	10250			7.1	
	11	13230			9.2	
	12	12150			8.4	
	13	14510			10.1	
	14	13360			9.3	
	15	13840		11961	9.6	8.3
	16	12930			9.0	
	17	8570			6.0	
	18	12550			8.7	
	19	10440			7.3	
	20	6310			4.4	
	21	11060			7.7	
	22	10510			7.3	
	23	9220			6.4	
	24	8430			5.9	
	25	17800			12.4	
	26	15760			10.9	
	27	10750			7.5	
	28	10540			7.3	
	29	17160			11.9	
	30	8140	358820		5.7	
OCT	1	12050			8.4	
	2	9800			6.8	
	3	13030			9.0	
	4	9870			6.9	
	5	10180			7.1	
	6	17930			12.5	
	7	11340			7.9	
	8	9940			6.9	
	9	12920			9.0	
	10	12930			9.0	
	11	11560			8.0	
	12	13700			9.5	
	13	11490			8.0	
	14	9810			6.8	
	15	11030		12637	7.7	8.8
	16	10470			7.3	
	17	13630			9.5	
	18	12970			9.0	
	19	16120			11.2	
	20	16440			11.4	
	21	16250			11.3	
	22	9730			6.8	
	23	12270			8.5	
	24	11200			7.8	
	25	7500			5.2	
	26	13800			9.6	
	27	13280			9.2	
	28	13230			9.2	
	29	13790			9.6	
	30	14070			9.8	
	31	19420	391750		13.5	

1993 DAILY MAKEUP WATER

MONTH	DAY	GAL/DAY	TOTAL	AVG GPD	GAL/MIN	AVG GPM
	1	19980			13.9	
	2	23710			16.5	
	3	23970			16.6	
	4	23280			16.2	
	5	19300			13.4	
	6	9580			6.7	
	7	15810			11.0	
	8	20750			14.4	
	9	18250			12.7	
	10	10340			7.2	
	11	24770			17.2	
	12	14190			9.9	
	13	17460			12.1	
	14	24400			16.9	
NOV	15	20310		15919	14.1	11.1
	16	16900			11.7	
	17	14650			10.2	
	18	12120			8.4	
	19	9870			6.9	
	20	13190			9.2	
	21	11260			7.8	
	22	10090			7.0	
	23	11110			7.7	
	24	14170			9.8	
	25	12560			8.7	
	26	15940			11.1	
	27	12950			9.0	
	28	12990			9.0	
	29	12610			8.8	
	30	11060	477570		7.7	
	1	15770			11.0	
	2	9850			6.8	
	3	15310			10.6	
	4	14900			10.3	
	5	13840			9.6	
	6	12440			8.6	
	7	12290			8.5	
	8	11900			8.3	
	9	10640			7.4	
	10	15020			10.4	
	11	13230			9.2	
	12	17440			12.1	
	13	18190			12.6	
	14	17800			12.4	
DEC	15	24350		17135	16.9	11.9
	16	13560			9.4	
	17	14870			10.3	
	18	14830			10.3	
	19	16290			11.3	
	20	17460			12.1	
	21	18540			12.9	
	22	16060			11.2	
	23	17860			12.4	
	24	19890			13.8	
	25	17650			12.3	
	26	22880			15.9	
	27	21180			14.7	
	28	27800			19.3	
	29	26840			18.6	
	30	21960			15.3	
	31	20550	531190		14.3	

A.6 ANALYSIS OF HTW AND DHW SAMPLES

Telephone Call Confirmation

Date: April 29, 1996

Project Number: 694-1331-002

Project Name: Fort Stewart HTW Study

Received: _____ **Placed:** by W. T. Todd

Local: _____ **Long Dist.:** 303-674-9897

Conversed with: John Tiangco

of Puckorius & Assoc. Water & Environmental Mgmt. Consultants

Regarding: Fort Stewart Boiler and HTW System Water Quality

To control general corrosion the pH and causticity should be kept high within the control range. Causticity is related to pH. Low pH is acidic and high pH is basic. Morpholine is added to the make-up water to raise the pH.

To control pitting corrosion the sulfite should be kept high within the control range. Sodium sulfite is added to the make-up water to tie up the oxygen. The high sulfite in the boiler is probably due to trying to control the HTW system sulfite with boiler feed water treatment. They recommend separate chemical feed systems. High sulfite levels do not adversely affect the system, however, it is a waste of chemicals.

The total dissolved solids (TDS) is mostly sodium which is benign. TDS is directly related to quantity of blowdown so they could reduce their blowdown by approximately 50 percent. Causticity goes up when blow down is reduced. Probably due to high alkalinity in the make-up water. When blow down is reduced the alkalinity, pH and causticity cycle up within the boiler. He thinks a de-alkalizer (similar to a water softener) would remove the bad alkalinity from the make-up water and would solve this problem. The cost would be similar to a water softener.

Water hardness is mostly calcium and some magnesium. Water softener removes most of the calcium and magnesium from make-up water. Phosphate is added to the make-up water to tie up any remaining calcium and magnesium.

Distribution: Fort Stewart File **By:** William T. Todd, PE

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 BOILER 4

Sample Number XCSTEWBW Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued 08/25/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... BW From Boiler 4 Pretreatment..... Resin Feedwater Temp (F)..... 212 Feedwater Deoxygenation Method(s): Mechanical..... Oxygen Scavenger..... Sodium Sulfite Boiler Type..... Water Tube Steam Gauge Pressure (PSIG)..... 220 Boiler Horsepower..... Boiler Output (PPH)..... 93,000 Boiler Treatment: pH Control..... Phosphate..... sodium hexametaphosphate Dispersant..... Condensate pH Control..... morpholine			
Boiler Water Analysis Report							
Test Description	P&A	Plant	Control				
Specific Sx Description							
Total Hardness, ppm CaCO ₃	12						
Filt Ortho Phos, ppm PO ₄	23	35	30 - 60				
Polymer, ppm			N/A				
Sulfite, ppm Na ₂ SO ₃	549	800	20 - 40				
P Alkalinity, ppm CaCO ₃	360						
Causticity, ppm OH ⁻	120	115	20 - 200				
pH	11.3	11.3					
Neut Conductivity, nmhos	2000	2200					
Total Diss Solids, ppm	1400	1540	3000 - 3500				

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Test agreement is good overall noting only a minor discrepancy for phosphate. Sulfite difference is normal since sulfite will degrade over time.
2. Results show that phosphate is below the control range. Sulfite is significantly overdosed while causticity is within range. Blowdown is excessive based on low TDS.

continued...

RECOMMENDATIONS:

1. Reduce blowdown to allow TDS to rise into range. This can include bottom blowdown when boiler loads are light. Treatment levels will rise proportional to the rise in TDS when chemicals are fed at a constant rate so feedrates may need adjustment to keep chemical levels within their control ranges.
2. If phosphate level does not come up sufficiently by reducing blowdown, increase the phosphate dosage.
3. Reduce sulfite dosage to allow level to drop into range.

REPORT PREPARED BY: J. Tiangco

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BLDG 1412 HIGH TEMP SYSTEM

Sample Number XFSTEWHT Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued . 08/25/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... Water From Cascade Heater System Type..... Hot Water Boiler Steam Gauge Pressure (PSIG)..... Boiler Horsepower..... Boiler Output (BTU/HR)..... Hot Water Temp (F)..... Hot Water pH Control..... Oxygen Scavenger..... Sodium Sulfite <div style="text-align: center;">Comments</div>			
High Temperature Water Analysis Report							
Test Description		P&A	Plant	Control			
Specific Sx Description							
Total Hardness, ppm CaCO ₃		(1)		(2)			
Total Iron, ppm Fe		<0.05					
pH		9.2	8.9	9.3 - 9.9			
Sulfite, ppm Na ₂ SO ₃		<2	30	0 - 40			
As Rcvd Cond, mmhos		220	0-200				

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Test agreement for pH is good. It is not clear what the plant means in reporting conductivity and TDS as 0-200. Sulfite difference is normal since sulfite will degrade over time.
2. Results shows only a trace of iron indicating good mild steel corrosion protection. The pH is within the control range.

RECOMMENDATIONS:

1. Please explain your rationale for reporting conductivity/TDS as 0-200. Other than that, no changes recommended at this time.

REPORT PREPARED BY: J. Tiangco & D.J. Robinette

BOILER SYSTEM WATER ANALYSIS PROGRAM
FORT STEWART BLDG 1412 HIGH TEMP SYSTEM

Sample Number XFSTEWHT Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued . 08/25/95				Specific Installation Information Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314-5000 Phone..... (912) 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... Water From Cascade Heater System Type..... Hot Water Boiler Steam Gauge Pressure (PSIG)..... Boiler Horsepower..... Boiler Output (BTU/HR)..... Hot Water Temp (F)..... Hot Water pH Control..... Oxygen Scavenger..... Sodium Sulfite	
High Temperature Water Analysis Report					
Test Description	P&A	Plant	Control		
Specific Sx Description					
Total Hardness, ppm CaCO ₃	<1			<2	
Total Iron, ppm Fe	<0.05				
pH	9.2	8.9		9.3 - 9.9	
Sulfite, ppm Na ₂ SO ₃	<2	30		0 - 40	
As Rcvd Cond, mhos	220	0-200			

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Test agreement for pH is good. It is not clear what the plant means in reporting conductivity and TDS as 0-200. Sulfite difference is normal since sulfite will degrade over time.
2. Results shows only a trace of iron indicating good mild steel corrosion protection. The pH is within the control range.

RECOMMENDATIONS:

1. Please explain your rationale for reporting conductivity/TDS as 0-200. Other than that, no changes recommended at this time.

REPORT PREPARED BY: J. Tiangco & D.J. Robinette

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 MAKEUP WATER

<p>Sample Number xestewmu Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued . 08/25/95</p>	<p style="text-align: center;">Specific Installation Information</p> <p>Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314 Phone..... () 767-8931</p>		
<p>Makeup /Water Analysis Report</p>			
Test Description	P&A	Plant	Control
Specific Sx Description	Sample not full. Clear.		
Total Hardness, ppm CaCO_3	(1)	0-2	(2)
As Rcvd Cond, mhos	245	150	
Total Diss Solids, ppm	170	105	
Total Iron, ppm Fe	0.1		
pH	7.3		
M Alkalinity, ppm CaCO_3	121		

Building Sample Is From..... Central Energy Plant
 Description Of Sample..... Make-up water
 Pretreatment.....

Comments

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. Test agreement for conductivity/TDS is poor. Hardness results agree well.
2. Results show a sample that is soft and low in iron - a good quality makeup water. The M-alkalinity is naturally high and a dealkalizer would probably allow operations to run higher cycles of concentration. The payback would be reduced energy, water, and chemical consumption.

RECOMMENDATIONS:

1. Calibrate your conductivity meter and make sure that the sample cup has been thoroughly flushed before taking a reading. No other changes recommended at this time.

REPORT PREPARED BY: J. Tiangco

A.6-B

BOILER SYSTEM WATER ANALYSIS PROGRAM

FORT STEWART BUILDING 1412 CONDENSATE

Sample Number XDSTWCN Date Sampled 07/18/95 Date Received 08/14/95 Date Analyzed 08/17/95 Date Report Issued . 08/25/95	<h3 style="text-align: center;">Specific Installation Information</h3> Post..... Fort Stewart City/State/Zip..... Fort Stewart, GA 31314 Phone..... () 767-8931 Building Sample is From..... Central Energy Plant Description of Sample..... Condensate Condensate pH Control..... Morpholine		
<h3>Condensate Water Analysis Report</h3>			
Test Description	P&A	Plant	Control
Specific Sx Description	Sample not full. Clear.		
Total Hardness, ppm CaCO_3	(2)	0-2	(2)
As Rcvd Cond, mmhos	42	0-100	(35)
Total Diss Solids, ppm	29	0-100	
Total Iron, ppm Fe	0.1		
pH	8.7	8.7	7.5 - 8.8
K Alkalinity, ppm CaCO_3	59		
Carbon Dioxide, ppm CO_2	(1)		

Comments

NOTE: REMARKS AND RECOMMENDATIONS REFLECT CONDITIONS AT TIME OF SAMPLING AND MAY NOT APPLY TO CURRENT CONDITIONS.

REMARKS:

1. It is not clear what the plant is trying to report for conductivity/TDS using "0-100". Test agreement for pH is good however.
2. Results show that the sample exceeds conductivity purity criteria however the iron level is acceptably low and the pH is within the control range.

RECOMMENDATIONS:

1. The small amount of contamination evidenced in the conductivity could be due to sampling error. Make sure that sample containers and sample lines are thoroughly flushed out before drawing a sample. If conductivity remains high, further troubleshooting should be undertaken.
2. No changes necessary for pH control.

REPORT PREPARED BY: J. Tiangco & D.J. Robinette

ANALYSIS OF DHW SAMPLES

Fort Stewart Hot Water Generators
Water Analysis Data - Number of SD Above or Below AVG
Filename: WATRANAL.WQ1

	Bldg	°F	#SD	Cond	#SD	pH	#SD	PO4	#SD	SO4	#SD	Fe	#SD	#SD≥1	PREMIER	RANK
	AVG	131		252		7.80		0.19		5		0.03				
	SD	21.3		16.5		0.17		0.08		3.5		0.04				
	206	80	0.0	250	0.1	8.10	1.8	0.13	0.0	2	0.0	0.27	6.1	(2)		
-	207	124	0.0	236	1.0	7.80	0.0	0.22	0.3	2	0.0	0.09	1.6	(2)		
	208	113	0.0	238	0.9	8.15	2.1	0.19	0.0	1	0.0	0.03	0.1	1		
-	212	131	0.0	227	1.5	8.10	1.8	0.21	0.2	-	0.0	0.02	0.0	(2)		
	213	120	0.0	229	1.4	7.75	0.0	0.13	0.0	-	0.0	0.01	0.0	1		
	215	137	0.3	227	1.5	7.80	0.0	0.13	0.0	-	0.0	0.04	0.4	1		
	216	110	0.0	227	1.5	7.85	0.3	0.07	0.0	-	0.0	--	0.0	1		
	218	124	0.0	236	1.0	7.80	0.0	0.12	0.0	-	0.0	0.01	0.0	1		
	302	137	0.3	237	0.9	7.65	0.0	0.14	0.0	-	0.0	0.02	0.0	0		
	439	139	0.4	246	0.4	7.75	0.0	0.12	0.0	7	0.6	0.02	0.0	0		
	440	114	0.0	243	0.6	7.95	0.9	0.17	0.0	9	1.1	0.02	0.0	1		
	501	134	0.2	243	0.6	7.85	0.3	0.18	0.0	12	2.0	0.03	0.1	1		
-	503	122	0.0	243	0.6	8.00	1.2	0.17	0.0	13	2.3	0.03	0.1	(2)		
-	504	158	1.3	239	0.8	8.05	1.5	0.14	0.0	10	1.4	0.01	0.0	(3)		
-	512	145	0.7	242	0.6	7.55	0.0	0.16	0.0	11	1.7	0.01	0.0	1		
	514	126	0.0	244	0.5	7.85	0.3	0.18	0.0	9	1.1	0.02	0.0	1		
	515	123	0.0	236	1.0	7.70	0.0	0.18	0.0	1	0.0	0.02	0.0	1		
-	516	145	0.7	242	0.6	7.70	0.0	0.29	1.2	5	0.0	--	0.0	1		
-	517	175	2.1	244	0.5	7.70	0.0	0.28	1.1	8	0.9	--	0.0	(2)		
-	518	183	2.5	234	1.1	7.70	0.0	0.36	2.1	9	1.1	--	0.0	(4)		
-	608	127	0.0	240	0.7	7.60	0.0	0.31	1.5	11	1.7	0.01	0.0	(2)		
	610	115	0.0	230	1.3	7.75	0.0	0.18	0.0	7	0.6	0.12	2.3	(2)		
	620	112	0.0	240	0.7	7.75	0.0	0.17	0.0	3	0.0	--	0.0	0		
	621	91	0.0	244	0.5	7.85	0.3	0.16	0.0	3	0.0	0.02	0.0	0		
	622	85	0.0	244	0.5	7.60	0.0	0.05	0.0	2	0.0	0.02	0.0	0		
	623	109	0.0	238	0.9	7.65	0.0	0.09	0.0	5	0.0	--	0.0	0		
	624	84	0.0	237	0.9	7.55	0.0	0.05	0.0	-	0.0	--	0.0	0		
	626	145	0.7	275	0.0	7.45	0.0	0.08	0.0	7	0.6	--	0.0	0		
	629	160	1.4	263	0.0	7.85	0.3	0.08	0.0	5	0.0	--	0.0	1		
	630	117	0.0	272	0.0	7.90	0.6	0.22	0.3	6	0.3	0.02	0.0	0		
	631	142	0.5	267	0.0	7.75	0.0	0.15	0.0	6	0.3	0.02	0.0	0		
	632	160	1.4	268	0.0	7.65	0.0	0.19	0.0	6	0.3	--	0.0	1		
	633	128	0.0	272	0.0	7.60	0.0	0.13	0.0	-	0.0	--	0.0	0		
	635	140	0.4	274	0.0	8.25	2.6	0.16	0.0	-	0.0	--	0.0	1		
	636	138	0.3	280	0.0	7.75	0.0	0.19	0.0	-	0.0	--	0.0	0		
	637	158	1.3	278	0.0	7.75	0.0	0.23	0.5	-	0.0	--	0.0	1		
-	642	154	1.1	278	0.0	7.70	0.0	0.29	1.2	10	1.4	--	0.0	(3)		
	701	152	1.0	272	0.0	7.75	0.0	0.12	0.0	7	0.6	--	0.0	1		
	702	143	0.6	277	0.0	7.85	0.3	0.10	0.0	9	1.1	--	0.0	1		
	708	131	0.0	265	0.0	7.70	0.0	0.10	0.0	6	0.3	--	0.0	0		
	712	135	0.2	279	0.0	7.65	0.0	0.22	0.3	9	1.1	--	0.0	1		
	713	133	0.1	271	0.0	7.70	0.0	0.27	1.0	8	0.9	0.03	0.1	1		
	714	137	0.3	267	0.0	7.70	0.0	0.27	1.0	7	0.6	0.01	0.0	1		
	715	135	0.2	263	0.0	7.80	0.0	0.36	2.1	5	0.0	--	0.0	1		
	717	131	0.0	263	0.0	7.75	0.0	0.26	0.8	4	0.0	--	0.0	0		
	718	124	0.0	260	0.0	7.65	0.0	0.33	1.7	2	0.0	--	0.0	1		
	719	112	0.0	265	0.0	7.85	0.3	0.21	0.2	2	0.0	--	0.0	0		
-	720	130	0.0	281	0.0	8.25	2.6	0.29	1.2	7	0.6	0.03	0.1	(2)		
-	726	158	1.3	254	0.0	8.05	1.5	0.33	1.7	7	0.6	0.06	0.9	(3)		
	810	131	0.0	248	0.3	7.90	0.6	0.27	1.0	2	0.0	0.01	0.0	1		
	1540	95	0.0	248	0.3	7.95	0.9	0.27	1.0	2	0.0	0.09	1.6	(2)		
	1720	148	0.8	248	0.3	7.75	0.0	0.22	0.3	5	0.0	0.02	0.0	0		
	2125	120	0.0	245	0.4	7.85	0.3	0.30	1.3	-	0.0	0.02	0.0	1		

OVERFLOW



T.M.

**PREMIER WATER & ENERGY
TECHNOLOGY, INC.**

Reynolds, Smith & Hills, Inc.							
Potable Hot Water - Ft. Stewart, Ga.							
	Sample						
Location	Date	Conductivity	pH	PO4	SO4	Fe	
HTHW	10/4/95	185	9.05	2.65	20	0.09	
206	10/4/95	250	8.10	0.13	2	0.27	
207	10/4/95	236	7.80	0.22	2	0.09	
208	10/4/95	238	8.15	0.19	1	0.03	
212	10/4/95	227	8.10	0.21	<1	0.02	
213	10/4/95	229	7.75	0.13	<1	0.01	
215	10/4/95	227	7.80	0.13	<1	0.04	
216	10/4/95	227	7.85	0.07	<1	<.01	
218	10/4/95	236	7.80	0.12	<1	0.01	
302	10/4/95	237	7.65	0.14	<1	0.02	
439	10/3/95	246	7.75	0.12	7	0.02	*
440	10/3/95	243	7.95	0.17	9	0.02	*
501	10/3/95	243	7.85	0.18	12	0.03	*
503	10/3/95	243	8.00	0.17	13	0.03	*
504	10/3/95	239	8.05	0.14	10	0.01	*
512	10/3/95	242	7.55	0.16	11	0.01	*
514	10/2/95	244	7.85	0.18	9	0.02	*
515	10/2/95	236	7.70	0.18	1	0.02	
516	10/2/95	242	7.70	0.29	5	<.01	*
517	10/2/95	244	7.70	0.28	8	<.01	*
518	10/2/95	234	7.70	0.36	9	<.01	*
608	10/3/95	240	7.60	0.31	11	0.01	*
610	10/4/95	230	7.75	0.18	7	0.12	*
620	10/3/95	240	7.75	0.17	3	<.01	
621	10/3/95	244	7.85	0.16	3	0.02	
622	10/3/95	244	7.60	0.05	2	0.02	
623	10/3/95	238	7.65	0.09	5	<.01	
624	10/3/95	237	7.55	0.05	<1	<.01	
626	10/3/95	275	7.45	0.08	7	<.01	
629	10/3/95	263	7.85	0.08	5	<.01	
630	10/3/95	272	7.90	0.22	6	0.02	*
631	10/3/95	267	7.75	0.15	6	0.02	
632	10/3/95	268	7.65	0.19	6	<.01	
633	10/3/95	272	7.60	0.13	<1	<.01	
635	10/3/95	274	8.25	0.16	<1	<.01	

A.6 -12



T.M.

**PREMIER WATER & ENERGY
TECHNOLOGY, INC.**

Reynolds, Smith & Hills, Inc.							
Potable Hot Water - Ft. Stewart, Ga.							
	Sample						
Location	Date	Conductivity	pH	PO4	SO4	Fe	
636	10/3/95	280	7.75	0.19	<1	<.01	
637	10/3/95	278	7.75	0.23	<1	<.01	
642	10/3/95	278	7.70	0.29	10	<.01	*
701	10/3/95	272	7.75	0.12	7	<.01	*
702	10/3/95	277	7.85	0.10	9	<.01	*
708	10/3/95	265	7.70	0.10	6	<.01	
712	10/3/95	279	7.65	0.22	9	<.01	*
713	10/3/95	271	7.70	0.27	8	0.03	*
714	10/3/95	267	7.70	0.27	7	0.01	*
715	10/3/95	263	7.80	0.36	5	<.01	*
717	10/3/95	263	7.75	0.26	4	<.01	
718	10/3/95	260	7.65	0.33	2	<.01	
719	10/3/95	265	7.85	0.21	2	<.01	
720	10/3/95	281	8.25	0.29	7	0.03	*
726	10/3/95	254	8.05	0.33	7	0.06	*
810	10/3/95	248	7.90	0.27	2	0.01	
1540	10/3/95	248	7.95	0.27	2	0.09	
1720	10/3/95	248	7.75	0.22	5	0.02	
2125	10/3/95	245	7.85	0.30	<1	0.02	
2125 P	10/3/95	241	7.85	0.04	<1	0.01	
PO4 = Phosphate SO4 = Sulfate Fe = Iron The samples that are marked in the far right column with an asterisk indicate sufficient differences in readings to suspect the possibility of leakage in these units.							

Fort Stewart Hot Water Generators
Water Analysis Data - Sorted by Component & Ranked
Filename: WATRANAL.WQ1

Bldg	°F	Rk	Bldg	Cond	Rk	Bldg	pH	Rk	Bldg	PO4	Rk	Bldg	SO4	Rk	Bldg	Fe	Rk
518	183	1	212	227	1	635	8.25	1	715	0.36	1	503	13	1	206	0.27	1
517	175	2	215	227	1	720	8.25	1	518	0.36	1	501	12	2	610	0.12	2
629	160	3	216	227	1	208	8.15	2	718	0.33	2	608	11	3	1540	0.09	3
632	160	3	213	229	2	206	8.10	3	726	0.33	2	512	11	3	207	0.09	3
504	158	4	610	230	3	212	8.10	3	608	0.31	3	504	10	4	<u>726</u>	<u>0.06</u>	4
637	158	4	518	234	4	726	8.05	4	2125	0.30	4	642	10	4	215	0.04	5
726	158	4	218	236	5	504	8.05	4	642	0.29	5	702	9	5	720	0.03	6
642	154	5	207	236	5	<u>503</u>	<u>8.00</u>	5	720	0.29	5	440	9	5	208	0.03	6
<u>701</u>	<u>152</u>	6	<u>515</u>	<u>236</u>	5	<u>440</u>	<u>7.95</u>	6	516	0.29	5	518	9	5	501	0.03	6
1720	148	7	624	237	6	1540	7.95	6	517	0.28	6	514	9	5	713	0.03	6
512	145	8	302	237	6	810	7.90	7	1540	0.27	7	<u>712</u>	<u>9</u>	5	503	0.03	6
516	145	8	623	238	7	630	7.90	7	810	0.27	7	713	8	6	515	0.02	7
626	145	8	208	238	7	621	7.85	8	713	0.27	7	517	8	6	1720	0.02	7
702	143	9	504	239	8	719	7.85	8	<u>714</u>	<u>0.27</u>	7	626	7	7	621	0.02	7
631	142	10	620	240	9	629	7.85	8	717	0.26	8	610	7	7	622	0.02	7
635	140	11	608	240	9	702	7.85	8	637	0.23	9	714	7	7	514	0.02	7
439	139	12	516	242	10	216	7.85	8	1720	0.22	10	720	7	7	302	0.02	7
636	138	13	512	242	10	514	7.85	8	207	0.22	10	439	7	7	2125	0.02	7
215	137	14	440	243	11	2125	7.85	8	630	0.22	10	726	7	7	212	0.02	7
302	137	14	503	243	11	501	7.85	8	712	0.22	10	701	7	7	439	0.02	7
714	137	14	501	243	11	207	7.80	9	212	0.21	11	631	6	8	631	0.02	7
712	135	15	622	244	12	715	7.80	9	719	0.21	11	708	6	8	630	0.02	7
715	135	15	621	244	12	215	7.80	9	208	0.19	12	630	6	8	440	0.02	7
501	134	16	514	244	12	218	7.80	9	636	0.19	12	632	6	8	714	0.01	8
713	133	17	517	244	12	636	7.75	10	632	0.19	12	629	5	9	504	0.01	8
212	131	18	2125	245	13	717	7.75	10	514	0.18	13	623	5	9	512	0.01	8
708	131	18	439	246	14	631	7.75	10	501	0.18	13	516	5	9	213	0.01	8
717	131	18	1540	248	15	701	7.75	10	515	0.18	13	1720	5	9	218	0.01	8
810	131	18	810	248	15	213	7.75	10	610	0.18	13	715	5	9	810	0.01	8
720	130	19	1720	248	15	637	7.75	10	440	0.17	14	717	4	10	608	0.01	8
633	128	20	206	250	16	1720	7.75	10	620	0.17	14	621	3	11	712	--	9
608	127	21	726	254	17	439	7.75	10	503	0.17	14	620	3	11	708	--	9
514	126	22	718	260	18	620	7.75	10	635	0.16	15	207	2	12	702	--	9
207	124	23	717	263	19	610	7.75	10	621	0.16	15	1540	2	12	717	--	9
218	124	23	715	263	19	714	7.70	11	512	0.16	15	810	2	12	719	--	9
718	124	23	629	263	19	713	7.70	11	631	0.15	16	206	2	12	715	--	9
515	123	24	708	265	20	708	7.70	11	302	0.14	17	622	2	12	718	--	9
503	122	25	719	265	20	515	7.70	11	504	0.14	17	718	2	12	701	--	9
213	120	26	631	267	21	517	7.70	11	215	0.13	18	719	2	12	620	--	9
2125	120	26	714	267	21	518	7.70	11	213	0.13	18	515	1	13	623	--	9
630	117	27	632	268	22	642	7.70	11	633	0.13	18	208	1	13	624	--	9
610	115	28	713	271	23	516	7.70	11	206	0.13	18	2125	-	14	518	--	9
440	114	29	633	272	24	718	7.65	12	218	0.12	19	216	-	14	216	--	9
208	113	30	630	272	24	302	7.65	12	439	0.12	19	218	-	14	516	--	9
620	112	31	701	272	24	623	7.65	12	701	0.12	19	215	-	14	517	--	9
719	112	31	635	274	25	712	7.65	12	702	0.10	20	212	-	14	626	--	9
216	110	32	626	275	26	632	7.65	12	708	0.10	20	213	-	14	636	--	9
623	109	33	702	277	27	608	7.60	13	623	0.09	21	302	-	14	637	--	9
1540	95	34	642	278	28	622	7.60	13	626	0.08	22	636	-	14	642	--	9
621	91	35	637	278	28	633	7.60	13	629	0.08	22	637	-	14	635	--	9
622	85	36	712	279	29	512	7.55	14	216	0.07	23	635	-	14	629	--	9
624	84	37	636	280	30	624	7.55	14	622	0.05	24	624	-	14	632	--	9
206	80	38	720	281	31	626	7.45	15	624	0.05	24	633	-	14	633	--	9

Fort Stewart Hot Water Generators
Water Analysis Data - Sorted by Bldg Number
Filename: WATRANAL.WQ1

Bldg	°F	Cond	pH	P04	S04	Fe
PW		241	7.85	0.04	1	0.01
HTHW		185	9.05	2.65	20	0.09
BLDG	°F	COND	PH	P04	S04	FE
206	80	250	8.10	0.13	2	0.27
207	124	236	7.80	0.22	2	0.09
208	113	238	8.15	0.19	1	0.03
212	131	227	8.10	0.21	1	0.02
213	120	229	7.75	0.13	1	0.01
215	137	227	7.80	0.13	1	0.04
216	110	227	7.85	0.07	1	0.01
218	124	236	7.80	0.12	1	0.01
302	137	237	7.65	0.14	1	0.02
439	139	246	7.75	0.12	7	0.02
440	114	243	7.95	0.17	9	0.02
501	134	243	7.85	0.18	12	0.03
503	122	243	8.00	0.17	13	0.03
504	158	239	8.05	0.14	10	0.01
512	145	242	7.55	0.16	11	0.01
514	126	244	7.85	0.18	9	0.02
515	123	236	7.70	0.18	1	0.02
516	145	242	7.70	0.29	5	0.01
517	175	244	7.70	0.28	8	0.01
518	183	234	7.70	0.36	9	0.01
608	127	240	7.60	0.31	11	0.01
610	115	230	7.75	0.18	7	0.12
620	112	240	7.75	0.17	3	0.01
621	91	244	7.85	0.16	3	0.02
622	85	244	7.60	0.05	2	0.02
623	109	238	7.65	0.09	5	0.01
624	84	237	7.55	0.05	1	0.01
626	145	275	7.45	0.08	7	0.01
629	160	263	7.85	0.08	5	0.01
630	117	272	7.90	0.22	6	0.02
631	142	267	7.75	0.15	6	0.02
632	160	268	7.65	0.19	6	0.01
633	128	272	7.60	0.13	1	0.01
635	140	274	8.25	0.16	1	0.01
636	138	280	7.75	0.19	1	0.01
637	158	278	7.75	0.23	1	0.01
642	154	278	7.70	0.29	10	0.01
701	152	272	7.75	0.12	7	0.01
702	143	277	7.85	0.10	9	0.01
708	131	265	7.70	0.10	6	0.01
712	135	279	7.65	0.22	9	0.01
713	133	271	7.70	0.27	8	0.03
714	137	267	7.70	0.27	7	0.01
715	135	263	7.80	0.36	5	0.01
717	131	263	7.75	0.26	4	0.01

718	124	260	7.65	0.33	2	0.01
719	112	265	7.85	0.21	2	0.01
720	130	281	8.25	0.29	7	0.03
726	158	254	8.05	0.33	7	0.06
810	131	248	7.90	0.27	2	0.01
1540	95	248	7.95	0.27	2	0.09
1720	148	248	7.75	0.22	5	0.02
2125	120	245	7.85	0.30	1	0.02

	°F	COND	PH	P04	S04	FE
MIN	80.0	227.0	7.5	0.05	1.0	0.01
AVG	130.6	252.2	7.8	0.19	5.0	0.03
MAX	183.0	281.0	8.3	0.36	13.0	0.27
P-SD	21.3	16.5	0.17	0.08	3.5	0.04
P-VAR	454	273	0.03	0.01	12	0.002
AVG ± SD	151.9	235.7	8.0	0.27	8.5	0.07



Telephone Call Confirmation

268-1152

Project Number 694-1331-002

Local _____ L.D. _____ Placed Rec'd _____ Date 9-18-95

Conversed with Gale Fillingner or Premier Water and Energy Tech.

Regarding Fort Stewart HTW Analysis

Gale is familiar with the HTW treatment at Fort Stewart. He thinks they could detect differences in phosphate, conductivity and ph if the heat exchangers were leaking. We should also take 3-5 samples of potable water from different areas of the Fort, and ~~two~~ samples of the HTW. Samples from barracks should be taken in the afternoon. Cost of analysis is about \$25 each and it will take 2-3 days to do 100+ samples and prepare a report. They will provide the sample bottles (~1 pint each) with labels we can mark on. He would like about 1 week notice prior to the site visit to make sure they have enough sample bottles on-hand. Their facility is located near Sherrod Vans off Greenland Road.

Distribution:



Telephone Call Confirmation

Project Number 694-1331-002

Local L.D. Placed Rec'd Date 9-14-95

Conversed with Tom Brandvold or Premier Water & Energy Tech.
268-1152

Regarding Fort Stewart Water Analysis

Premier currently treats and tests the condenser water for the CEP at Fort Stewart. Tom thinks they could detect HTW in the domestic hot water by lab analysis. Gale Fillinger has the account for Fort Stewart.

Tom will meet with Gale and try to figure out the best method to accomplish our task and they will call me back next week.

Distribution:

A.7 SUBMITTAL REVIEW COMMENTS AND REVIEW ACTIONS

INTERIM

PROJECT REVIEW COMMENTS			Date: 12 APR 96	Page 1 of 1
TO: MR. CHET SCRATZMEIER CHIEF, PROJ/PROJ MGMT & OPS DIVISION		FROM: (Section) DPW, EP&S DIVISION (Reviewer) POWELL		
Project: LIMITED ENERGY STUDY, HIGH TEMPERATURE AND CHILLED WATER DISTRIBUTION SYSTEMS Location: FORT STEWART AND HUNTER AAF, GA		Year: FY-96	Line Item No. DACA01-94-D-0038 #694-1331-002	
Type of Action (Check Appropriate Boxes) <input type="checkbox"/> Preliminary <input type="checkbox"/> Final <input checked="" type="checkbox"/> INTERIM <input type="checkbox"/> Paving & Grading <input type="checkbox"/> Architectural <input type="checkbox"/> Structural <input checked="" type="checkbox"/> Mechanical <input type="checkbox"/> Electrical <input type="checkbox"/> Sanitary				
Item No.	Drawing No. or Paragraph No	COMMENTS	REVIEW ACTION	
1.	GENERAL	RECOMMEND THAT THE PRE-FINAL REPORT CONTAIN A DISCUSSION AND RECOMMENDATIONS ON WATER TREATMENT AND CATHODIC PROTECTION, SACRIFICIAL ANODE, OR OTHER CORROSION AND SCALE PREVENTION/PROTECTION PRACTICES THAT COULD BE IMPLEMENTED OR THAT NEED CHANGING AT FT. STEWART AND HUNTER AAF TO INCREASE THE LIFE OF THE DISTR. SYSTEMS.	CONCUR. DISCUSSION OF CURRENT PRACTICES AND CATHODIC PROTECTION WERE ADDED TO SECTION 4.3.	
2.	VOLUME 1 PARA. 5.2 / 1 C.E.P.	THE RECOMMENDATION SHOULD ADDRESS ANY NEGATIVE EFFECTS OR REDUCTION IN PLANT CAPABILITY BY REDUCING THE SYSTEM PRESSURE AS RECOMMENDED.	CONCUR. DISCUSSION WAS ADDED TO THE ECO-12 RECOMMENDATIONS.	
3.	VOLUME 1 PARA. 5.2 C.E.P.	PREVIOUS STUDIES HAVE MENTIONED DEAERATOR PROBLEMS THAT COULD CAUSE CORROSION TO ACCELERATE IN THE HTHW DISTRIBUTION SYSTEM. THIS SHOULD BE INVESTIGATED TO DETERMINE IF THE PROBLEMS HAVE BEEN CORRECTED, AND IF NOT, RECOMMENDATIONS SHOULD BE ADDED TO THE PRE-FINAL REPORT.	NO ACTION REQUIRED. THE DEAERATOR PROBLEMS HAVE BEEN CORRECTED.	
4.	VOLUME 1 PARA. 5.2 VALVE PITS	TREES AND SHRUBS HAVE BEEN OBSERVED GROWING IN VALVE PITS IN THE PAST. REMOVAL OF THIS DESTRUCTIVE GROWTH AT AN EARLY STAGE, TO PREVENT DAMAGE TO THE PITS AND PIPING SHOULD BE INCLUDED IN THE FINAL O&M RECOMMENDATIONS.	CONCUR. COMMENT AND LOCATION OF VALVE PIT WILL BE ADDED TO THE O&M RECOMMEND.	
5.	VOLUME 3 SURVEY FORMS	RECOMMEND THAT A COPY OF THESE FIELD NOTES BE GIVEN TO THE MECHANICAL SHOPS. A LOT OF LEG WORK HAS BEEN DONE IN THIS INVESTIGATION, AND THE MECHANICAL ROOMS WITH THE LARGEST LEAKS ARE IDENTIFIED AND CAN BE REPAIRED.	CONCUR. A SUMMARY OF THE VALVE PIT SURVEY AND MECH. EQUIPMENT ROOM SURVEY WILL BE ADDED TO VOLUME 3.	

AFZP FORM 193

Response to Review Comments**Date:** May 28, 1996**Reviewer:** Chet Scratzmeier (by Powell)
Fort Stewart DPW, EP&S Division**Response by:** William T. Todd, PE**Subject:** Interim Submittal
Limited Energy Study, HTW Distribution System, Fort Stewart
DACA01-94-D-0038, RSH #694-1331-002

Number	Dwg/Pg/Par.	Response	Review Action Comments
1	General	Concur	A discussion of cathodic protection and current water treatment practices will be added as Section 4.3.
2	Vol. 1, Par 5.2	Concur	A discussion of operation at reduced pressures will be added to the ECO-12 Recommendations in Section 4.4.
3	Vol. 1, Par 5.2	Concur	No action required. The problems with the deaerator have been corrected.
4	Vol. 1, Par 5.2	Concur	An O&M recommendation with the valve pit number and location will be added to Section 5.2.
5	Vol. 3, Forms	Concur	A summary of findings for the valve pit survey and the mechanical equipment room survey will be added to Appendix Sections B.1 and B.2, respectively.

CC: C. Warren
File

M:\STEWART\RTC-I-CS.DOC

MEMORANDUM THRU EN-D/DESIGN BRANCH

FOR EN-PM

SUBJECT: HTW/CHW DISTR STUDY, FY-96, LI 6029000, FORT STEWART, GA.,

1.		Enclosed are these sections A/E specific instructions with manday estimate.	
2.		a. Man-day estimate (mandatory for all change orders) is: <input type="checkbox"/> Professional <input type="checkbox"/> Sub-professional <input type="checkbox"/> Clerical b. Number of sheets of new drawings:	
3.		The A/E's specifications have been reviewed and <input type="checkbox"/> are satisfactory subject to enclosed comments <input type="checkbox"/> A/E should visit the District office for special instruction prior to preparation of specifications.	
4.		Revised A/E Instructions are enclosed.	
5.	X	The A/E's <input type="checkbox"/> Concept submittal <input type="checkbox"/> % preliminary Corrected <input type="checkbox"/> Final submittal [XX] Study <input type="checkbox"/> Cost Estimate <input type="checkbox"/> FP Eng Credentials	<input type="checkbox"/> is approved for continuation of design subject to enclosed comments. <input type="checkbox"/> shall be revised in accordance with enclosed comments & RESUBMITTED prior to preceding with design. SECTION CHIEF: _____ [XX] is satisfactory. CONCUR. NO ACTION REQUIRED. <input type="checkbox"/> shall be revised in accordance with enclosed comments.
6.		The design of the project thus far <input type="checkbox"/> is <input type="checkbox"/> is not satisfactory for A/E payment.	
7.		The enclosed annotated review comments have been reviewed and <input type="checkbox"/> the annotation added by the A/E is satisfactory <input type="checkbox"/> the annotations are satisfactory except as indicated by the enclosed additional comments.	
8.		The comments prepared by _____ are appropriate for mailing to the A/E.	
9.		The comments prepared by _____ are appropriate except where indicated. Additional comments or clarifications are enclosed.	
10.		The enclosed meeting notification is acknowledged. <input type="checkbox"/> No one from this section will attend. <input type="checkbox"/> The following team member will attend _____	
11.		This project's Arms Room design <input type="checkbox"/> is satisfactory <input type="checkbox"/> does not have an Arms Rm or Vault.	
12.	X	EXCELLENT SUBMITTAL CONCUR. NO ACTION REQUIRED.	

Prepared by: WALT HOHNE

INTERIM

MOBILE DISTRICT PROJECT REVIEW COMMENTS:		DATE: April 10, 1996	Page 1 of 1
TO: U. S. Army Corps of Engineers Savannah District Savannah, GA.		FROM: Robert S. Woodruff, CESAM-EN-DM Phone: (334) 694-6074 FAX: (334) 690-2424	
PROJECT/FY: Limited Energy Study High Temperature and Chilled Water Distribution Systems			
LOCATION: Fort Stewart and Hunter AAF, GA.			
TYPE REVIEW: Interim Submittal			
NO.	Page/Par	COMMENT	Response to Comment
1.	P. 1-1	The conclusions of the previous report which eliminated the High Temperature water system at Hunter AAF and both chilled water systems from this study should be restated here. As presented the reader is left wondering what happened to that part of the study because Appendix A.10 does not exist in this report.	CONCUR. APPENDIX A.10 WILL BE INC. IN THE PRE-FINAL SUBMITTAL.
2.	P. 1-2	The evaluation of E.C.O. 8 (Repair underground HTW system leaks) is dependent on the completion of the underground piping leak survey. The corroborating evidence that 40 % of the system leaks are in the underground piping is dependent on the completion of the underground piping leak survey. The Scope of Work (Para. 6.1) requires that all ECO's be evaluated in the interim report. Because of the importance of this survey and the resulting work related to it the interim report can not be considered complete without it. The A/E should resubmit the interim report when this work is completed.	CONCUR. COPY WAS PROVIDED AT THE REVIEW MEETING. RESUBMITTAL IS NOT REQUIRED. ECO 8 WILL BE INCLUDED IN PRE-FINAL RPT.
3.	P. 4-11 Para. 5	This paragraph states that 40% of the high temperature water system leak losses are in the underground portion of the piping. If 40% of the losses were caused by one or two leaks wouldn't they be worth repairing?	CONCUR. THIS WAS ADDRESSED BY ECO 8. WILL CLARIFY TEXT IN PREFINAL REPORT.
4.	P. 4-36 Para. 4	Is there any basis for concluding that half of the underground piping insulation is deteriorated?	CONCUR. Basis for THIS VALUE WILL BE ADDED TO TEXT.

Response to Review Comments**Date:** May 28, 1996**Reviewer:** Robert S. Woodruff, CESAM-EN-DM
U. S. Army COE, Savannah District**Response by:** William T. Todd, PE**Subject:** Interim Submittal
Limited Energy Study, HTW Distribution System, Fort Stewart
DACA01-94-D-0038, RSH #694-1331-002

Number	Dwg/Pg/Par.	Response	Review Action Comments
1	Pg 1-1	Concur	Appendix A.10 will be included in the Pre-final Submittal.
2	Pg 1-2	Concur	Resubmittal is not required. A copy of the ECO-8 evaluation and recommendations was provided at the review meeting and will be included in the Pre-final submittal.
3	Pg 4-11, Par 5	Concur	The analysis for ECO-8 indicates there are many small leaks. The text in the Pre-final submittal will be modified to clearly indicate the number and quantity of leaks.
4	Pg 4-36, Par 4	Concur	The assumption was based on our field observations of the valve pits and conduit vents. This will be added to the text.

CC: C. Warren
File

M:\STEWART\RTC-I-RW.DOC

INTERIM

CECPW-EM

11 April 1996

MEMORANDUM FOR Commander, U.S. Army Forces Command,
ATTN: AFPI-ENO (Mr. Naresh Kapur)
Fort McPherson, GA 30330-6000

SUBJECT: Review of Interim Report on Fort Stewart's High Temperature and Chilled Water Distribution System

1. Reference 1 April 1996 phone call from Naresh Kapur, FORSCOM, to Dennis Vevang, CECPW-EM, requesting review of Fort Stewart's interim report.

NO ACTION
REQUIRED.

2. On 2 April received the three volumes of the interim report "LIMITED ENERGY STUDY HIGH TEMPERATURE AND CHILLED WATER DISTRIBUTION SYSTEMS FOR STEWART AND HUNTER AAF, GEORGIA" prepared by Reynolds, Smith and Hills, Inc. of Jacksonville, Florida.

NO ACTION
REQUIRED.

3. SCOPE OF WORK:

a. The scope of work (Appendix A, Volume II of the report) states that the Architect-Engineer (A-E) shall perform field investigations of the high temperature water (HTW) distribution systems and the chilled water (CHW) distribution systems and identify and document projects. One particular alternative project is the complete replacement of the existing distribution lines with a shallow trench distribution system.

NO ACTION
REQUIRED.

b. For the Fort Stewart HTW field investigation, the A-E is to identify the location of energy leaks, describe and estimate the cost of the Energy Conservation Opportunities (ECOs) to close these leaks, and to perform a Life Cycle Cost Analysis (LCCA) to see if these ECOs qualify for funding under either the Federal Energy Management Program (FEMP) or the Energy Conservation Investment Program (ECIP). For the Hunter Army Airfield (HAAF) field investigation, the A-E shall gather data on the Central Energy Plant (CEP) and the pinwheel barracks energy plant and interview the personnel involved with the plants. The A-E will recommend on this investigation whether or not further study of the HAAF HTW distribution systems should be programmed for the future.

c. For both the Fort Stewart CHW and the HAAF CHW, the A-E shall gather data on the Central Energy Plant (CEP) and the pinwheel barracks energy plant and interview the personnel involved with the plants. The A-E will recommend on this investigation whether or not further study of the Fort Stewart and HAAF CHW distribution systems should be programmed for the future.

d. At the interim submittal review stage, Fort Stewart and Forces Command (FORSCOM) personnel are to give guidance to the A-E on how best to package the ECO's for funding purposes.

INTERIM

4. FACILITY DESCRIPTION:

a. Fort Stewart has a central energy plant (CEP) and satellite energy plant (SEP). The CEP has three natural gas/fuel oil-fired package boilers and one stoker-fired wood boiler and these boilers produce high pressure steam. The CEP uses the steam in three cascade heaters to produce high temperature hot water and to feed by underground steam line the two cascade heaters in the SEP about one mile away. The SEP has no boilers.

NO ACTION
REQUIRED.

b. The CEP HTW distribution system has about seven miles of underground lines and serves about 130 buildings. The SEP serves five buildings with about one mile of underground distribution lines.

c. A large amount of wood is burned in the CEP. As a result, the energy costs are very low. Wood contributes about 86 percent of the yearly energy consumed.

5. Make-up water use was an important parameter in the estimation of the leak losses. Since a HTW is a closed system, the water loss from leaks would be the make-up water minus blowdown and sootblowing uses. The A-E analyzed three years of data and used the last year (1995) as the base to determine the leaks found during the surveys.

6. The A-E came up with 12 ECOs to analyze for project cost; savings-to-investment ratio (SIR); simple payback; utility energy savings for electricity and heating fuels; quantity of water savings; and dollar savings for energy, water, and operations and maintenance. The ECOs are:
Number 1: Replacement of the existing HTW distribution lines with a new shallow trench distribution system.

Number 2: Reduce blowdown of the cascade heaters and the wood-fired boiler.

Number 3: Reduce soot blowing, install an exit gas temperature indicator on the wood-fired boiler.

Number 4: Repair HTW and steam leaks in the CEP and SEP.

Number 5: Repair HTW leaks in the mechanical equipment rooms.

Number 6: Repair building side DHW and HVAC hot water leaks.

Number 7: Repair HTW leaks in valve pits, drain pits and valve boxes.

Number 8: Repair underground HTW distribution system leaks.

Number 9: Reduce or eliminate HTW discharge during SEP start-up.

Option A. Improve start-up procedure for the SEP.

Option B. Install a new condensate/HTW return pump in the SEP.

Number 10: Use an alternative heating method to reduce SEP operating cost.

Option A. Distribute HTW from the CEP to the SEP instead of steam.

Option B. Shut down the SEP and use individual oil-fired boilers in the buildings served by the SEP

Number 11: Purchase leak locator equipment or contract leak locator service when a major HTW leak occurs.

Number 12: Reduce boiler and HTW system operating pressure.

Option A. Operate at 100 psig.

Option B. Operate at 60 psig

Option C. Operate at 30 psig

Option D. Operate at 15 psig.

INTERIM

7. RESULTS:

The following are CECPW's comments about the various ECOs:

a. Number 1: Replacement of the existing HTW distribution lines with a new shallow trench distribution system. The replacement of the existing distribution system with a new shallow trench system is not economical (the simple payback is nearly 100 years). This would be expected since the current system is in relatively good shape. However, if the existing buried distribution system deteriorates to the point that the entire distribution system has to be replaced, the shallow trench system would probably be the system to use.

CONCUR. WILL
RECOMMEND
EVALUATION OF
ABOVE GROUND
SYSTEM WHEN
EXISTING PIPIN
IS NEAR THE
END OF ITS
USEFUL LIFE

1. When designing the distribution system, the preference is for aboveground piping, followed by shallow concrete trench, and finally direct buried systems. The US Army Corps of Engineers has developed a new (October 1994) policy for heat distribution systems (HDS). This policy was developed because of many reports of poor performance of existing steam and high temperature hot water distribution systems. This policy is for Army heat distribution systems with a carrier pipe temperature 95 degrees C and above (See Policy below).

2. The Site Classifications are A, B, C, and D. These classifications are based on underground water conditions. Class A sites have severe underground water conditions. Any piping placed underground in Class A site will have water over the top of the piping. Site B has had underground water conditions; Class C moderate and Class D mild.

3. Technical Manual TM 5-810-17, HEATING AND COOLING DISTRIBUTION SYSTEMS, May 1994, provides criteria and guidance for the design and construction of heating and cooling distribution systems. This manual says that in most circumstances, experience has shown that aboveground systems are the most life cycle cost effective. Experience has also shown that the M & R costs of shallow concrete trench systems are lower than for direct buried systems, and they must be included in the life cycle cost analysis.

b. Number 7: Repair HTW leaks in valve pits, drain pits and valve boxes. This is a very important repair because if the pit or manhole fills with water large energy losses can result. During the survey, several pits had water up to the piping. There is a draft USACERL Technical Report on "BOILING MANHOLE HEAT LOSS CALCULATIONS" prepared by Charles Marsh and Terrill Laughton. The overall objective of this project is to develop a set of correlations that can be used in the field to estimate the heat loss from a boiling manhole for an entire year. The heat loss estimation is then used to assess the economic impact on the operations cost of the heat distribution system. Four variables are needed to calculate the heat loss of a boiling manhole: the steam pressure, average steam velocity, the total length, and the average diameter of the steam piping in the manhole. The calculated energy loss in a flooded manhole with 19 feet of piping with an average diameter of 6.5 inches for a high pressure steam distribution system is \$170,000 per year at average Army energy cost rates. There are also calculations for high temperature hot water distribution systems.

CONCUR. WATER
LEVEL IN PIT
IS FROM GROUND
WATER LEAKIN
IN AND SUMP
PUMPS THAT
DO NOT WORK.
PROBLEM IS
ADDRESSED IN
THE OEM
RECOMMENDATION

c. Number 8: Repair underground HTW distribution system leaks. This is not covered in the interim report. A survey of selected sections of the distribution was scheduled for February 1996. A print out and explanation of Renewables and Energy Efficiency Planning (REEP) is attached. One of ECOs is Underground Heat Distribution Systems Repairs and is rated about the fourth or fifth best savings-to-investment ratio. Page 448 of the CERL report shows how the costs were calculated for underground heat distribution system leak repairs.

CONCUR.
ECO-B ANALYSIS
PROVIDED AT
REVIEW MEETING
AND WILL BE
INCLUDED IN
PREFINAL RPT.

INTERIM

8. In summary, it is a good report. I agree with the methodology. The assumptions seem reasonable. Much of what I wrote above is for added information and shows some of the work that is going on at CERL. CECPW-EM point of contact is Dennis Vevang; COM (703) 806-6071; DSN 656-6071; FAX -5220; INTERNET dennis.i.vevang@cpw01.usace.army.mil.

NO ACTION
REQUIRED.

Encl.

Dennis Vevang
Mechanical Engineer

CF: Commander, US Army Corps of Engineers
Savannah District, ATTN: Mr. Rob Callahan
100 West Oglethorpe Avenue,
P.O. Box 889
Savannah, Georgia 31402-0889

Response to Review Comments**Date:** May 28, 1996**Reviewer:** Dennis Vevang, CECPW-EM
Construction Engineering Research Laboratories**Response by:** William T. Todd, PE**Subject:** Interim Submittal
Limited Energy Study, HTW Distribution System, Fort Stewart
DACA01-94-D-0038, RSH #694-1331-002

Number	Dwg/Pg/Par.	Response	Review Action Comments
1 - 6	N. A.	N. A.	No action required.
7.a.	Section 4.4 ECO-1	Concur	Will add text to ECO-1 recommendations that states an above ground piping system should be evaluated when the existing system is near the end of its useful life.
7.b.	Section 4.4 ECO-7	Concur	No action required. Water found in the valve pits was primarily due to ground water leaking around the conduits and inoperable sump pumps. Water in the valve pits was usually not in contact with the HTW piping. The sump pump problem is addressed in the O&M Recommendations, Section 5.2.
7.c.	Section 4.4 ECO-8	Concur	No action required. A copy of the ECO-8 evaluation and recommendations was provided at the review meeting and will be included in the Pre-final Submittal.
8	N. A.	N. A.	No action required.

CC: C. Warren
File

M:\STEWART\RTC-I-DV.DOC

FAX FOR
 Rob Callahan
 FAX 912 - 652 - 5442
 T-11 5246

NARESH KAPUR, PE
 404-669-5327

INTERIM

FORSKOM REVIEW COMMENTS ON INTERIM EEAP SUBMITTAL. "LTD ENERGY
 STUDY HIGH TEMP AND CHILLED WATER DISTRIBUTION SYSTEMS, FT
 STEWART/HAAF, GA"

A VOLUME I

1. General. This submittal is well organized. Please refer to Aug 28 submittal of RECORDS ANALYSIS AND SITE SURVEY PLAN. The important observation data and recommendations should be incorporated in this submittal. An addendum is ok. If any aspect of the study is to be discontinued, it should be documented and agreed to by all interested parties. CONCUR. WILL BE INCLUDED IN PREFINAL REPORT AS APPENDIX A.10
2. General. In sec 5, for tables 5.1-2, 5.1-4 and 5.1-5, add a column for total cost saving. Also correct total of all projects cost column in table 5.1-5. CONCUR. WILL CORRECT AND CHANGE TABLE
3. General. pl discuss PROS and CONS of recommendation for reducing the operating pressure to 60, 30, or 15 psig. CONCUR. WILL ADD TO ECO-12 RECOMMENDATION
4. Vol I, pg 5-4. Elaborate 3,4,&5. For 7&8, have these been done? These are O&M items. CONCUR. WILL ELABORATE. ALL ARE O&M ITEMS.

B. VOLUME II

5. ECO #1. Consider adding ECO description up front. This can be done by repeating the descriptions from vol I. This will make the report more user friendly. Make special effort to look for non-energy savings and non recurring savings. This comment may be applicable to other ECOs also. CONCUR. WILL ADD DESCRIPTION AND COMMENT ON AGE OF T SYSTEM.
6. ECO # 2. Add a brief discussion on boiler water quality issue. CONCUR. TEXT ADDED TO ECO-2 AND SECTION 4.3.
7. ECO #8. This ECO is very important. Need to describe it in detail. What approach is being taken to come up with Life Cycle cost Analysis (LCCA). CONCUR. ECO-8 INCLUDED IN PREFINAL RPT.
8. Some appendices are missing. Are these ready now? CONCUR. ALL APPENDICES WILL BE INCLUDED IN PREFINAL RPT.

C. VOLUME III

9. Appendix B. Consider summarizing the pit valves and fittings survey form data on a spreadsheet. add an extra row for remarks as needed. 90 plus pages can be substituted by 3-4 pages of spreadsheet. Consider the same for appendix B2. CONCUR. SUMMARY OF VALVE PITS A MECH. ROOMS WILL BE IN PREFINAL RPT
10. Appendix B4. Status? CONCUR. WILL BE INCLUDED IN PREFINAL REPORT.

Response to Review Comments**Date:** May 29, 1996**Reviewer:** Naresh Kapur, AFPI-ENO
U. S. Army Forces Command**Response by:** William T. Todd, PE**Subject:** Interim Submittal
Limited Energy Study, HTW Distribution System, Fort Stewart
DACA01-94-D-0038, RSH #694-1331-002

Number	Dwg/Pg/Par.	Response	Review Action Comments
1	Vol. I, General	Concur	The 8/28/95 submittal will be included in the Pre-final Submittal as Appendix A.10.
2	Vol. I, Section 5.1	Concur	All tables will be corrected and modified for the Pre-final Submittal.
3	Vol. I, General	Concur	A discussion about operating at reduced pressures will be added to the ECO-12 recommendations in Section 4.4.
4	Vol. I, Pg 5-4	Concur	Will elaborate on items 3, 4, and 5. All of these are O&M recommendations.
5	Vol. II, ECO-1	Concur	A description of ECO-1 and a comment on the age and condition of the existing piping system will be added.
6	Vol. II, ECO-2	Concur	A discussion on boiler water quality and treatment will be added as Section 4.3 and included in Section 4.4, ECO-2.
7	Vol. II, ECO-8	Concur	Calculations, analysis and recommendations for ECO-8 will be included in the Pre-final Submittal.
8	Vol. II, General	Concur	All appendices will be included in the Pre-final Submittal.
9	Vol. III App. B.1 & B.2	Concur	A summary list of findings for valve pits and mechanical rooms will be added for Sections B.1 and B.2, respectively.
10	Vol. III App. B.4	Concur	The forms for Section B.4 will be included in the Pre-final Submittal.

CC: C. Warren
File

M:\STEWART\RTC-I-NK.DOC

MOBILE DISTRICT PROJECT REVIEW COMMENTS:		DATE: 18 July 1996	Page 1 of 1
TO: Rob Callahan, CESAS-PM-MP USAED, Savannah		FROM: Anthony W. Battaglia, CESAM-EN-DM Phone: (334) 690-2618 FAX: (334) 690-2424	
PROJECT/FY: FY95 EEAP Limited Energy Study, HTW Distribution			
LOCATION: Fort Stewart, GA			
TYPE REVIEW: Pre-final Submittal			
NO.	Page/Par	COMMENT	Response to Comment
1.	General	The statistical analysis of the makeup water data was a very good approach; it allowed some sense to be made of what could have been very confusing.	CONCUR
2.	Pg 2-2	Figure 2.2-1: On page 3-3 and on page 4-1, there are references to condensate and HTW return lines from the SEP to the CEP. Please include these lines in Fig 2.2-1.	CONCUR
3.	Pg 3-1	Par 3.2: Some additional losses that could be included are the deaerator vent and any steam traps that discharge to the atmosphere or to a floor drain.	CONCUR
4.	Pg 3-4	On the first line, it appears that the phrase, "subtracted from" should be changed to "added to".	CONCUR
5.	Pg 4-42	Analysis - Option B: Change "50 psig" to "35 psig".	CONCUR
6.	Pg 4-42	Analysis - Option C: Are the boilers at the hospital currently being operated, or are they sitting idle?	CONCUR
7.	Pg 4-43	Analysis - Option D: The discussion of the HTW-to-Steam generators should be clarified. The temperature of the HTW must be higher than the saturation temperature corresponding to the desired steam pressure, otherwise there will be no heat transfer.	CONCUR
8.	Pg 4-43	Results and Recommendations: Options C & D should include an operation and maintenance cost for the operation of the hospital boilers.	CONCUR

Response to Review Comments**Date:** August 20, 1996**Reviewer:** Anthony W. Battaglia, CESAM-EN-DM
U. S. Army Engineer District, Mobile**Response by:** William T. Todd, PE**Subject:** Pre-final Submittal
Limited Energy Study, HTW Distribution System, Fort Stewart
DACA01-94-D-0038, RSH #694-1331-002

Number	Dwg/Pg/Par.	Response	Review Action Comments
2	Volume I Pg 2-2	Concur	The terms "HTW return" and "condensate return" are used interchangeably in the text. To avoid confusion "condensate return" will be changed to "HTW return" on page 3-3. Figure 2.2-1 will be revised to show the HTW return pipe.
3	Volume I Pg 3-1	Concur	This sentence will be modified to: "The known system losses include soot blowing, boiler blowdown, cascade heater blowdown, the deaerator vent and other miscellaneous leaks within the CEP."
4	Volume I Pg 3-4	Concur	The SEP tests quantified the leak rate from the SEP without blowdown so the blowdown should not be subtracted from the results. This sentence will be changed to: "The amount of water used for blowdown and other miscellaneous leaks must be added to the estimated loss rate from the above procedure to determine the total HTW losses from the SEP."
5	Volume I Pg 4-42	Concur	Will change "50 psig" to "35 psig" in the second sentence of Analysis - Option B.

6	Volume I Pg 4-42	Concur	To clarify this point the text will be modified to: "The existing heating and cooling plant at the hospital is only utilized when the CEP is not operational."
7	Volume I Pg 4-43	Concur	In order provide a sufficient temperature difference to produce steam at 15 psig, the steam generators require a minimum HTW system pressure of 25 to 30 psig. Therefore, Option D will be removed from this ECO.
8	Volume I Pg 4-43	Concur	Will add operation and maintenance costs for Option C.

CC: C. Warren
File

A.8 LIST OF ABBREVIATIONS AND ACRONYMS

ABBREVIATIONS

ABMA	American Boiler Manufacturer's Association
ABS	Absorption
Btu	British thermal units
BFP	Boiler Feed Pump
BFW	Boiler Feed Water
C-1	Cascade Heater No. 1
CEP	Central Energy Plant
CHW	Chilled Water
DA	Deaerator
DHW	Domestic Hot Water
DPW	Directorate of Public Works
ECO	Energy Conservation Opportunities
EEAP	Energy Engineering Analysis Program
FEMP	Federal Energy Management Program
FSEO	Fort Stewart Energy Officer
GPD	Gallons per Day
GPM	Gallons per Minute
HHW	Heating Hot Water
HPS	High Pressure Steam
HTW	High Temperature Water
HTWR	High Temperature Water Return
HTWS	High Temperature Water Supply
kGal	1,000 Gallons
LF	Linear Feet
LPS	Low Pressure Steam
MBtu	Million British thermal units
MPS	Medium Pressure Steam
MUW	Make-up Water
O&M	Operation and Maintenance
OMA	Operation and Maintenance, Army
P&A	Puckorius & Associates
PPM	Parts per million
PRS	Pressure Reducing Station
psig	pound per square inch
RS&H	Reynolds, Smith and Hills, Inc.

SEP Satellite Energy Plant
SIR Savings to Investment Ratio
TDS Total Dissolved Solids
WM Water Meter
WS Water Softener

A.9 CORRESPONDENCE AND MEETING NOTES

CSW
S



DEPARTMENT OF THE ARMY

SAVANNAH DISTRICT, CORPS OF ENGINEERS

P.O. BOX 889

SAVANNAH, GEORGIA 31402-0889

REPLY TO
ATTENTION OF:

Military Branch

SUBJECT: Request for Proposal for Delivery Order No. 2 Under Contract No. DACA01-94-D-0038, Indefinite Delivery Contract for Architect-Engineer Services for the Army Energy Engineering Analysis Program (EEAP) for the Southeast Region, Including Alabama, Arkansas, Florida, Georgia, Louisiana, Mississippi, Puerto Rico, and South Carolina

Reynolds, Smith and Hills, Incorporated
Attention: Mr. Carlos Warren
4651 Salisbury Road
Jacksonville, Florida 32256

Gentlemen:

I refer to the conversation of February 17, 1995, between Mr. Carlos Warren of your firm and Mr. Rob Callahan of the Savannah District regarding the incorporation of work into your referenced contract. The work is described in the attached Appendix A for Delivery Order Number 2.

There will be a prenegotiation conference in building number T-1139 at Fort Stewart on February 28, 1995, beginning at 9:00 am. Your firm should be appropriately represented at the meeting and be prepared to ask any questions you need to clarify the Appendix A for this project.

Please furnish your fee proposal in detail by separate item of work as outlined on the attached "Suggested Format for Architect-Engineer Fee Proposal" to the attention of the Architect-Engineer Contract Section (CESAS-EN-EA) by March 8, 1995. The estimate shall include all project costs.


You are to mark the envelope containing your fee proposal in the lower left corner "Architect-Engineer Fee Proposal". After receipt of your fee proposal, you will be contacted by an approved District negotiator for the purpose of establishing a date for fee negotiations.

You are not to proceed with this work until the negotiations are concluded and the notice to proceed is issued. You are cautioned that your participation in the prenegotiation conference and the preparation of your fee proposal are entirely at your own risk. Further, in the event of unsatisfactory fee negotiations, the Government can assume no obligation for payment

of any expense incurred by your firm in the preparation of your fee. The award of delivery orders is subject to the approval of the Contracting Officer.

If you have any questions concerning this additional work, please contact the Project Manager, Mr. Rob Callahan, of the Reimbursable Management Team, at telephone number (912) 652-5426.

Sincerely,



Warren T. Clarke
Authorized Representative of the
Contracting Officer

Attachment

Copies Furnished (wo/enclosures):

Commander, 24th Infantry Division and Fort Stewart,
Attention: AFZP-DEV (Mr. Randy Jones), Fort Stewart,
Georgia 31314

Commander, U.S. Army Forces Command, Attention: AFPI-ENO
(Mr. Naresh Kapur), Fort McPherson, Georgia 30330

2/27/95

FORT STEWART SURVEY

A. PRE-SURVEY

- ① OBTAIN SET OF DISTRIBUTION SYSTEM MAPS FROM
FT S. GIS OPERATOR / SYSTEMS ANALYSIS BRANCH
- ② OBTAIN COPY OF ANY PREVIOUS STUDIES
- ③ COPY OF WORK ORDERS AND/OR SERVICE ORDERS
PAST 12 MONTHS
FROM RESOURCE MGT DIV / FE DIVISION
- ④ INTERVIEW PERSONNEL (?) INCLUDE HAAF
- ⑤ REVIEW MAKE-UP WATER LOGS

B. DEVELOP PLAN

C. FIELD SURVEY

- ① Develop data forms
- ② APPOINT FIELD SURVEY MANAGER

2/28/95

PRE-NEGOTIATE

- ① 14,000 gal/day HTW make-up
- ② HAAF study option.
- ③ Randy wants system evaluation. (distribution only)

28 Feb 95

MEMORANDUM FOR RECORD


SUBJECT: Prenegotiation Conference for Delivery Order No. 2 under Contract No. DACA01-94-D-0038, Indefinite Delivery Contract for Architect-Engineer Services for the Army Energy Engineering Analysis Program (EEAP) for the Southeast Region including Alabama, Arkansas, Florida, Georgia, Louisiana, Mississippi, Puerto Rico, and South Carolina

1. The undersigned called the subject meeting to order on 28 February 1995 at 0900 in the Fort Stewart DPW conference room. I stated the purpose of the meeting and circulated the sign-in sheet. Project team members in attendance are shown at encl 1.
2. Everyone had already introduced themselves, so we proceeded on into our review of the draft Appendix A, or Scope of Work, for the project. We immediately got sidetracked into discussing additions to the Scope. We bounced ideas around, performed a map review, and then broke for lunch. Following lunch, we reconvened the meeting in the Central Energy Plant (CEP) manager's office. When we finished there, we did a short field investigation of some exposed distribution system piping and a few valve pits and placed a telephone call to the Repair Branch supervisor, Gene Smith, to solicit his thoughts on where water leaks exist. We discussed survey techniques that the A-E would use for the project. We decided if the A-E had to remove any pipe insulation in order to attach flow meters that Doug would initiate a DPW work request to have it repaired so that the A-E's field crew would be relieved of this responsibility.
3. The conclusion of the team from the day's work was that I would redraft the Appendix A to incorporate more work and that the work needed to proceed in a different sequence from that which I had described in the draft Scope.
4. The final revised version of the project Appendix A is attached at encl 2. It incorporates all the changes needed to bring the Scope into line with the customer's desires.
5. The order in which the A-E will perform the work now will be:
 - a. Perform the review of records on the Fort Stewart (FS) chilled water system (CHW).
 - b. Perform the review of records on the Hunter Army Airfield (HAAF) high temperature water systems (HTW) and CHW systems for both the CEP and the pinwheel barracks energy plant.
 - c. Submit recommendations, with back-up justification, on the FS CHW distribution system and the HAAF HTW/CHW systems along with the plan for the field investigation. The field investigation plan will address both the FS HTW and CHW system surveys, if the A-E's recommendation is to perform the detailed field study of the FS CHW

system.

- d. Perform the field investigations.
- e. Submit the interim report.
- f. Submit the pre-final report.
- g. Submit the final report.

6. Doug, Carlos, and I signed our Partnering Agreement (encl 3).
I adjourned the meeting at about 1400.



Robert A. Callahan
Project Manager

CONFERENCE PARTICIPANTS

Project <i>High Temp & Chilled Water Distribution</i>	Date: <i>28 Feb 95</i>
Base: <i>System Study</i> <i>Ft. Stewart</i>	Time: <i>0900</i>
Fiscal Year <i>1995</i>	Local:
Line Item	Type: <i>Pre-negotiation</i>

Name	Position	Organization	Office Sym.	Telephone
1. <i>R. b Callahan</i>	<i>Project Manager</i>	<i>Corps of Engineers</i> <i>Savannah District</i>	<i>CESAS-PM-MR</i>	<i>(912) 652-5246</i> <i>DSN: 971-6330, ext 524</i>
2. <i>RANDY JONES</i>	<i>ENERGY Coordinator</i>	<i>DPW Energy</i>	<i>AFZP-DEV</i>	<i>412-654-912</i> <i>767-7925</i>
3. <i>DH. SWANSON</i>	<i>ENERGY ENG</i>	<i>DPW Energy</i>	<i>AFZP-DEV</i>	<i>352-5535</i> <i>912-767-8880</i>
4. <i>W.T. Todd</i>	<i>Engineer</i>	<i>RS & H</i>	<i>—</i>	<i>904-279-2291</i>
5. <i>Carlos Warren</i>	<i>Proj Mgr.</i>	<i>RS & H</i>		<i>904-279-2275</i>
6.				
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				



DEPARTMENT OF THE ARMY

SAVANNAH DISTRICT, CORPS OF ENGINEERS

P.O. BOX 689

SAVANNAH, GEORGIA 31402-0689

REPLY TO
ATTENTION OF:

CESAS-PM-MP-2

8 Mar 95

MEMORANDUM FOR

Commander, 24th Infantry Division & Ft. Stewart, ATTN: AFZP-DEV
(Mr. Swanson), Ft. Stewart, GA 31314
Commander, U.S. Army Forces Command, ATTN: AFPI-ENO (Mr. Kapur),
Ft. McPherson, GA 30330
Commander, U.S. Army Engineer Division, South Atlantic,
ATTN: CESAD-EN-TE (Mr. Baggette), 77 Forsythe Street, SW,
Atlanta, GA 30335-6801
Commander, U.S. Army Engineer District, Mobile,
ATTN: CESAM-EN-DM (Mr. Battaglia), P.O. Box 2288, Mobile,
AL 36628-0001

SUBJECT: Delivery Order No. 2 Under Contract No. DACA-01-D-0038,
Indefinite Delivery Contract for Architect-Engineer Services for
the Army Energy Engineering Analysis Program (EEAP) for the
Southeast Region Including Alabama, Arkansas, Florida, Georgia,
Louisiana, Mississippi, Puerto Rico, and South Carolina

I am enclosing the minutes of the Prenegotiation Conference for
the subject project held at Fort Stewart on 28 Feb 95. Please
advise the Project Manager, Rob Callahan, of any additions,
deletions, or corrections to these minutes.

FOR THE COMMANDER:

Encl

Warren T. Clarke
WARREN T. CLARKE, R.A.

Acting Chief, Military Programs and
Project Management Branch

CF:

Reynolds, Smith and Hills, Inc., ATTN: Mr. Carlos Warren,
4651 Salisbury Road, Jacksonville, FL 32256

CONFERENCE PARTICIPANTS

Project <u>HHW & CHW Dist. Study</u>	Date: <u>6/28/95</u>
Base:	Time: <u>1330</u>
Fiscal Year	Local: <u>Ft Stewart GA</u>
Line Item	Type:

Name	Position	Organization	Office Sym.	Telephone
1. <u>Rob Callahan</u>	<u>Project Manager</u>	<u>Corps of Engineers Savannah District</u>	<u>CEAS-PM-MR</u>	<u>Com (912) 522-5246</u>
2. <u>Naresh Kapur</u>	<u>Mech Engr</u>	<u>HA. FORSCOM DCS DIM-ENGR</u>	<u>AFPI-END</u>	<u>DSN 971-6330, ext. 524</u> <u>COM 404-669-5327</u> <u>FAX 7151</u>
3. <u>Roger Coeur</u>	<u>DPW Repairs</u>			<u>262-2138</u>
4. <u>Doug Swanson</u>	<u>DPW-Enrgy</u>	<u>DAW-ENRD</u>	<u>AF2P-DEV</u>	<u>352-5535</u>
5. <u>Bill Todd</u>	<u>Mech. Eng.</u>	<u>RS&H</u>	<u>Jax</u>	<u>904-279-2281</u>
6. <u>CARLOS WARREN</u>	<u>Pres. Mgr</u>	<u>RS&H</u>	<u>JAX</u>	<u>904-279-2275</u>
7.				
8.				
9.				
10.				
11.				
12.				
13.				
14.				
15.				
16.				
17.				
18.				
19.				
20.				

MEETING NOTES

wtt

①

6/28/95

- \$10.82 /ton for wood chips

- Chilled water pipe is asbestos with asbestos insulation and asbestos pipe jacket.

- 600 Block 1st }
700 Block 2nd } not as many leaks even though
800 Block } these are the oldest systems.

- Records review

- HTW at Ft Stewart

- CHW at " "

- HTW at Hunter

- CHW at "

- Chris Harley in charge of Boiler Plant

- Doug S. is place to start for information.

- Meter at valve pits and test potable water for sulfite or other boiler feed water chemical.

* Check on type of insulation on High Temp. Pipes

- Worst problem is 4500 block - the newest system

- This loop is shut down during the summer water sits in the pipe all summer

A.9-9

6/28/95

- EEAP Study for capacity of system and load of buildings on the system
- Cost Est.
ECO Analysis
Form 1391 later?
- Rob's schedule is about 52 weeks.
- Coordinate F. Survey w/ boiler plant operation.
- Have Doug write a memo giving us access to the base to perform the survey

CHW - 120 psi for Zone 1 & 2

80 psi for Zone 3 which is the longest run

- Zone 1: 700 & 800 Block - must keep pressure up for these areas
- Zone 2 bldg 440 - not cooled properly unless pressure is high



Architectural, Engineering, Planning and Environmental Services

Reynolds, Smith and Hills, Inc.

4651 Salisbury Road
Jacksonville, Florida 32256
904-296-2000
Fax 904-279-2491

FL. Cert Nos AAC001886 • EB0005620 • LCC000210

July 19, 1995

Department of the Army
Savannah District
Corps of Engineers
100 W. Oglethorpe Avenue
Savannah, GA 31402-0889

Attn: Warren T. Clarke
Contracting Officer Representative

Subject: Contract No. DACA01-94-D-0038
Delivery Order Number 2
Limited Energy Study of High Temperature and Chilled Water
Distribution Systems at Fort Stewart and Hunter Airfield, Georgia
AEP File No. 6941331002

Gentlemen:

Pursuant to Paragraph 5.1, Appendix A of the referenced Delivery Order, the following individuals are designated:

Project Manager	Carlos S. Warren, PhD, PE
Field Survey Manager	William T. Todd, PE

Your concurrence is respectfully requested.

Very truly yours,

Carlos S. Warren, PhD, PE
Vice President - Energy Services

/gk

cc W. Todd
Distribution

A.9-11

DISTRIBUTION

Commander
24th Infantry Division and Fort Stewart
ATTN: AFZP-DEV (Mr. Doug Swanson)
Fort Stewart, GA 31314

Commander
U. S. Army Forces Command
ATTN: AFPI-ENO (Mr. Naresh Kapur)
Fort McPherson, GA 30330

Savannah District, Corps of Engineers
ATTN: CESAS-PM-MR (Mr. Rob Callahan)
100 W. Oglethorpe Avenue
P. O. Box 889
Savannah, GA 31402-0889


Mobile District, Corps of Engineers
ATTN: CESAM-EN-DM (Mr. Tony Battaglia)
P. O. Box 2288
Mobile, AL 36628-0001

RS&H

MEMORANDUM

Date: 1 September 1995

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MR (Mr. Rob Callahan)
PO Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, PhD, 
Project Manager

Subject: Monthly Progress Report
Limited Energy Study, Hunter Army Airfield and Ft. Stewart
HTW and CHW Distribution Systems
Contract No. DACA01-94-D-0038/0002

The following progress was made on the subject contract during the month of August 1995:

1. Site visit was accomplished by the Project Manager (PM) and the Site Survey Manger (SSM) 02 - 04 August. The purpose of the site visit was to gather sufficient data and records to recommend whether or not to conduct detailed surveys and analyses of the HAAF CHW and heating distribution lines and the Ft. Stewart CHW distribution lines.
2. Additional data and drawings were also obtained on the Ft. Stewart HTW distribution system.
3. The scheduled report "Records Analysis and Site Survey Plan" was distributed on 28 August 1995.

Work planned for September 1995:

1. Begin activities to prepare for the initial site survey scheduled to begin 23 October 1995. Equipment and necessary subcontractors will be committed. If judged worthwhile, the site survey may be started ahead of schedule.

cc: Doug Swanson



Telephone Call Confirmation

Project Number 694-1331-002

Local LD. Placed Rec'd Date 9-6-95
Conversed with Rob Callahan or COE - Savannah District
Regarding Fort Stewart HTW Distribution Study

They have just hired a new energy coordinator at Fort Stewart. His name is Tim Harper and he will be replacing Doug Swanson as our point of contact for this project. His office is in the FE Division and his temporary phone number is 912-767-2446. I told Rob I would call Tim this week to get acquainted. They would also like a week or two advance notice prior to each site visit. Rob has reviewed the survey plan and is very pleased/impressed with it.

There is a design and construction contractor that would like to "look over our shoulder" during the site survey. I said that would be ok as long as they did not slow us down.

Distribution: C. Warren

September 15, 1995

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: William T. Todd, PE
Field Survey Manager

Subject: Weekly Field Survey Progress Report
Limited Energy Study
Hunter Army Airfield and Ft. Stewart
HTW and CHW Distribution Systems
Contract No. DACA01-94-D-0038/0002

The following progress was made on the subject contract during the week ending 15 September 1995:

1. Site visit was accomplished by the Field Survey Manager on 13 September. The purpose of the site visit was to:
 - A. Locate HTW system make up water, chemical feed and blow down pipes to be metered and determine if pipe insulation removal is required. The make up water pipe was located and flow estimates for the two chemical feed systems and 12 blow down systems were obtained from conversations with the plant operations staff. Some pipe insulation will have to be removed if the metering effort is required. The CEP operations staff will be notified after a decision has been made.
 - B. Obtain copies of recent HTW and potable water sample analysis reports. Copies of analysis reports for boiler water, cascade heater water (HTW), make up water, condensate, and cooling tower make up water (potable water) were obtained from the CEP records.
2. Pump and pump motor nameplate data was taken for the three HTW system zones served by the CEP. This effort was originally scheduled for the October field survey, however, time permitted it during this visit. We can now go ahead and pursue the pump curves from the manufacturer.

Additional field survey work planned for September 1995:

1. No additional field survey work is planned until the initial site survey which is scheduled to begin 23 October 1995. If judged worthwhile, the initial site survey may be started ahead of schedule. We will notify the FESO and Savannah District accordingly.

/gk
cc

Tim Harper

Transmittal Letter

RS&H

Architecture, Engineering and Planning

To: Mr. Robert Meston
Utility Services Assoc. Inc.
10013 Martin Luther King Jr. Way, S.
Seattle, WA 98178

Date: 9/20/95

Project: Fort Stewart
HTW and CHW Distribution

Project No: 694-1331-002

We Transmit:

- (☒) herewith
() under separate cover

For Your:

- () approval
(☒) review & comment
(☒) use

The Following:

Copies	Date	Description
1	---	Piping System Information
1	---	HTW Distribution System Map

Remarks: Please prepare a quote for USA to provide leak detection and locating services based on the attached information.

Copies To: C. Warren

Reynolds, Smith and Hills, Inc.
4651 Salisbury Road
Jacksonville, Florida 32256
904-296-2000 Fax 904-279-2491

FL. Cert. Nos. AAC001886 • EB0005620 • LCC000210

By: William T. Todd
William T. Todd, PE



MEMORANDUM - VIA FAX

Architectural, Engineering, Planning and Environmental Services

To: Mr. Tim Harper
From: William T. Todd
Project: Fort Stewart HTW Leak Study
A/E No.: 694-1331-002
Subject: Building Hot Water Generator Survey

Date: 9-27-95

This memo is to provide written conformation of our telephone conversation regarding the building hot water generator survey planned for next week. As we discussed, our team will be at Fort Stewart for three to five days beginning Monday morning (10-2-95). We will be taking water samples from buildings that utilize the HTW system to produce domestic hot water.


Also, as per our conversation, please have a letter of authorization prepared that will allow us access to the buildings. The survey team will consist of the following people:

William T. Todd, Field Survey Manager
Paul F. Hutchins
George W. Fallon

Please call me if you have any questions. I look forward to meeting you next week.

Copies To: Mr. R. Callahan (Via Fax)
C. Warren

FORT STEWART, ENRD, ENVIRONMENTAL BRANCH



Date: 28 SEPT 95

Number of Pages (inc. cover sheet): 2

To: Bill Todd

From: Tim Harper

Phone:

Phone: 912-767-4903

Fax:

Fax:

CC:

Remarks: ☐ Urgent ☐ For your review ☐ Reply ASAP ☐ Please comment

Bill,

I believe this will be sufficient!
Let me know if you need anything else.
Look forward to meeting w/ you next
week.

Tim Harper


AFZP-DEF (420-10a)

28 Sep 95

MEMORANDUM FOR RECORD

SUBJECT: Water samples for Fort Stewart HTW Leak Study

1. The week beginning 2 Oct 95, RS&H will be at Fort Stewart taking hot water samples. The following individuals will need to enter buildings that utilize the HTW system: William T. Todd (Field Survey Manager), Paul F. Hutchins, and George W. Fallon.
2. POC is Tim Harper, extension 4903.



TIMOTHY D. HARPER
Energy Engineer, FE Division

October 6, 1995

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: William T. Todd, PE *WTT*
Field Survey Manager

Subject: Weekly Field Survey Progress Report
Limited Energy Study
Ft. Stewart HTW Distribution System
Contract No. DACA01-94-D-0038/0002

The following progress was made on the subject contract during the week ending 6 October 1995:

1. Site survey was performed by Paul Hutchins, George Fallon and the Field Survey Manager from 2 - 4 October, 1995. The following items were accomplished during the site visit:
 - A. The HTW distribution system leaks were determined by turning off all blow down and soot blowers in the CEP for 8 hours and measuring the makeup water required to refill the cascade heaters. This test will be performed again when the satellite energy plant is operational.
 - B. Obtained HTW, domestic hot water and potable water samples for analysis. The analysis will be used to determine if the heat exchangers are leaking HTW into the domestic hot water generators in the barracks and dining facilities.

Additional field survey work planned:

1. No additional field survey work is planned until the satellite energy plant (SEP) is operational. This survey, which will include valve pits and mechanical rooms, is scheduled to begin 6 November 1995. If the SEP is not operating, the site survey may be started at a later date. We will notify the FESO and Savannah District accordingly.

/gk

cc

T. Harper (FESO)
C. Warren (PM)




MEMORANDUM

Architectural, Engineering, Planning and Environmental Services

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

Date: 26 October 1995

From: Carlos S. Warren, PhD, PE 
Project Manager

Project: Limited Energy Study - Hunter Army Airfield and Ft. Stewart
HTW and CHW Distribution System
Contract No. DACA01-94-D-0038/0002
A/E No. 694-1331-002

Subject: Monthly Progress Report

The following progress was made on the subject project during the month of October 1995:

1. Site survey was accomplished the week of 2 October 1995. The purposes of the site visit were to obtain potable water samples from the buildings with HTW generators to identify possible water leaks from the heat exchanger in the generator, and to measure the makeup water required to refill the cascade heaters. A report on the survey was submitted by the Field Survey Manager to the addressee on 6 October 1995.
2. The analysis of the water samples was received on 23 October 1995. Of the 53 buildings sampled, 22 samples showed sufficient quantities of phosphates and/or sulfates (present in the HTW) to suspect leaks.
3. Observations were made of leak detection in underground water lines using ultrasonic technology. This method will be used to survey the Ft. Stewart HTW lines. The equipment and operator have been tentatively scheduled for a survey the week of 15 January 1996.

Work planned for November 1995:

1. Survey of the valve pits and mechanical rooms containing suspected HTW heat exchanger leaks will commence when the satellite energy plant is operational.

Copies To: Tim Harper (FESO)
W. Todd ✓

A.9-22

MEMORANDUM - VIA FAX

To: Mr. Tim Harper
From: William T. Todd
Project: Fort Stewart HTW Leak Study
A/E No.: 694-1331-002
Subject: Field Survey Schedule

Date: 11-3-95

Our next field survey of the Fort Stewart HTW distribution system is scheduled to take place next week (11/06/95-11/10/8⁹~~5~~). One of the main objectives of this survey is to determine the total volume of HTW losses during full heating operation. However, as described in our most recent progress report, the Satellite Energy Plant (SEP) must be operational so we can quantify the leakage rate of the entire HTW distribution system during the heating season.

I called the operator of the Central Energy Plant today and he said the SEP was still not operating. He expected it would be running within the next couple of weeks. We will check on the status of the SEP each week and schedule the next field survey as soon as possible after the SEP is operational.

Please call me if you have any questions regarding the field survey schedule.

Copies To: Mr. R. Callahan (Via Fax)
C. Warren

27 Nov 95

MEMORANDUM FOR RECORD

SUBJECT: Fort Stewart HTW Leak Study

1. The week beginning 27 Nov 95, RS&H will be at Fort Stewart taking hot water samples. The following individuals will need to enter buildings that utilize the HTW system: William T. Todd (Field Survey Manager) and George W. Fallon.
2. POC is Tim Harper, extension 4903 or 9451.



TIMOTHY D. HARPER
Energy Engineer, FE Division




MEMORANDUM

Architectural, Engineering, Planning and Environmental Services

BT

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

Date: 29 November 1995

From: Carlos S. Warren, PhD, PE 
Project Manager

Project: Limited Energy Study - Hunter Army Airfield and Ft. Stewart
HTW and CHW Distribution System
Contract No. DACA01-94-D-0038/0002
A/E No. 694-1331-002

Subject: Monthly Progress Report

The following progress was made on the subject project during the month of November 1995:

1. Evaluated the test results of the domestic hot water samples and selected buildings to revisit and perform leak tests.
2. Began writing Introduction, Facility Description and Methodology sections of Interim Report.
3. Site survey was accomplished during the week of 27 November 1995. The following items were accomplished during this field investigation:
 - Measured make up water to the CEP during heating season.
 - Measured make up water to the SEP
 - Surveyed valve pits
 - Surveyed more mechanical equipment rooms
 - Measured miscellaneous leaks within the CEP and the SEP

Work planned for December 1995:

1. Analyze data collected during field investigations and calculate annual cost of HTW distribution system leaks.

A.9-25

Memorandum to Callahan

29 November 1995

HAAF and Ft. Stewart HTW and CHW Distribution Systems

Monthly Progress Report

Page 2

2. Continue drafting Interim Report.

Copies To: Tim Harper (FESO)
W. Todd

Transmittal Letter

RS&H

Architecture, Engineering and Planning

To: Commander
24th Infantry Division and Ft. Stewart
ATTN: AFZP-DPW-OB FAC DIV (Mr. Randy Parks)
Fort Stewart, Georgia 31314-5000

Date: 12/8/95

Project: Fort Stewart HTW Distribution
System Study

Project No: 6941331002

We Transmit:

- ☒ (X) herewith
☐ () under separate cover

For Your:

- ☐ () approval
☐ () review & comment
☒ (X) use

The Following:

Copies	Date	Description
1	---	Fuel Tank Capacity (w/o baffle) by height in inches
1	---	Fuel tank capacity (with baffle) by height in inches

Remarks: These are good estimates of the usable fuel tank capacities, one with and one without a baffle. If George measured the tanks correctly, these values should be accurate within 10 to 15 gallons. Please call me if you have any questions.

Copies To:

Reynolds, Smith and Hills, Inc.


4651 Salisbury Road
Jacksonville, Florida 32256
904-296-2000
Fax 904-279-2491

By: Bill Todd
William T. Todd, PE

Memorandum

Date: December 28, 1995

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, PhD, PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of December 1995:

1. Added water temperature data, reevaluated the test results of the domestic hot water samples and selected buildings to revisit and perform leak tests.
2. Continued working on draft of Interim Report.
3. Analyzed data collected during November field investigation. Results of the analysis include:
 - Test to measure make up water to Zones 1, 2 and 3 during heating season were inconclusive. We will retry this test during January site visit.
 - Test to measure make up water to the SEP Zone indicated this was a very tight distribution system.
 - Began calculations to quantity leaks found during survey of valve pits, mechanical equipment rooms, the CEP and the SEP.
4. Canceled ultrasonic leak detection test scheduled for January based on the low volume flow of leaks within the distribution system (less than 4 g.p.m.).
5. Investigating video thermography to locate HTW system leaks.

Monthly Progress Report
Memorandum to Callahan
28 December 1995
HAAF and Ft. Stewart HTW and CHW Distribution Systems

Work planned for January 1996:

1. A field investigation is scheduled for January 15-19. The goals are:
 - Survey remaining mechanical rooms (approximately 60) for leaks.
 - Test hot water generator/heat exchangers suspected of leaks.
 - Repeat test for make-up water to Zones 1, 2 and 3.
2. Analyze data collected during field investigations and calculate annual cost of HTW distribution system leaks.
3. Continue drafting Interim Report.

/gk

Copies to: T. Harper (FESO)
W. Todd

MEMORANDUM

February 5, 1996

TO: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

FROM: Carlos S. Warren, PhD, P.E. - Project Manager

SUBJECT: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of January 1996:

1. Performed field investigation to survey about 60 mechanical equipment rooms, test hot water generators/heat exchangers for leaks and correct errors to make-up water use data.
2. Continued working on project analysis and draft of Interim Report.
3. Scheduled the ultrasonic leak detection test for February 21-23.
4. Investigated video thermography to locate HTW system leaks. Rejected this method based on high costs.

Work planned for February 1996:

1. A field investigation is scheduled for February 21-23. The goals are:
 - Survey selected sections of the underground HTW distribution piping.
 - Use ultrasonic leak detection equipment to locate leaks.
2. Complete analysis and submit Interim Report.

/kw

cc: T. Harper (FESO)
W. Todd

MEMORANDUM

February 5, 1996

TO: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

FROM: William T. Todd, P.E.
Field Survey Manager

**SUBJECT: Weekly Field Survey Progress Report
Limited Energy Study
Hunter Army Airfield and Ft. Stewart
HTW and CHW Distribution Systems
Contract No. DACA01-94-D-0038/0002**

The following field investigation progress was made on the subject contract during the week ending 19 January 1996:

1. Site visit was accomplished on 16-18 January. The purpose of the site visit was to:
 - A. Survey remaining mechanical rooms (about 60 rooms) for HTW leaks.
 - B. Test hot water generators and heat exchangers suspected of leaking.
 - C. Correct errors and explain extreme data from boiler logs.

Additional field survey work planned:

1. The next and final field survey work is planned for February 21-23. We will be testing the underground HTW pipes using ultrasonic leak detection equipment.

/kw

cc: Tim Harper
N. Kapur (via fax)
C. Warren

I:\todd\sav\02-05.mem

Transmittal Letter

Reynolds, Smith and Hills, Inc.
Architectural, Engineering, Planning and Environmental Services

To: Attached Distribution List

Date: February 16, 1996

Project: Limited Energy Study
HTW and CHW Distribution Systems
Fort Stewart and Hunter AAF

Project No.: 6941331002

We Transmit:

☒ (X) Herewith ☐ () Via Fax ☐ () Hand Carried
☐ () Under Separate Cover Via:
☐ () In Accordance with Your Request
☐ () Regular Mail ☒ (X) Overnight Mail ☐ () Courier

For Your:

☐ () Approval
☒ (X) Review and Comment
☐ () Use
☐ () Signature

The Following:

Copies	Date	Description
As per distribution list	2-19-96	Interim Submittal -Vol. I Narrative Report
As per distribution list	2-19-96	Vol. II Appendicies
As per distribution list	2-19-96	Vol. III Field Investigation Forms

Remarks: Volume III is being supplied in 3-ring binders because these forms will not change.
Updated covers and inserts will be sent with future submittals.

/kw

Copies To:

Reynolds, Smith and Hills, Inc.
4651 Salisbury Road
Jacksonville, Florida 32256
(904) 296-2000 Fax: (904) 279-2491

FL Cert. Nos. AAC001886•EB0005620•LCC000210

By:

William T. Todd

William T. Todd, P.E.

l:todd\int.rpt

A.9-32

Limited Energy Study
HTW and CHW Distribution Systems
Fort Stewart and Hunter AAF

INTERIM REPORT

NO. COPIES

2	Commander 24th Infantry Division and Fort Stewart ATTN: AFZP-DEV (Mr. Tim Harper) Fort Stewart, GA 31314
1	Commander U. S. Army Forces Command ATTN: AFPI-ENO (Mr. Naresh Kapur) Fort McPherson, GA 30330
2	Savannah District Corps of Engineers ATTN: CESAS-PM-MR (Mr. Rob Callahan) 100 W. Oglethorpe Avenue P. O. Box 889 Savannah, GA 31402-0889
1	Mobile District, Corps of Engineers ATTN: CESAM-EN-DM (Mr. Tony Battaglia) P. O. Box 2288 Mobile, AL 36628-0001

Memorandum

Date: March 1, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: William T. Todd, PE *Bill*
Field Survey Manager

Subject: Weekly Field Survey Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and CHW
Distribution System

The following investigation progress was made on the subject project during the week ending 23 February 1996:

Site visit was accomplished on February 21. The purpose of the site visit was to use ultrasonic leak detection equipment to locate leaks in selected sections of the underground HTW distribution piping. Ultrasonic leak detectors and a microprocessor - based leak correlation equipment were used in an attempt to pinpoint leaks in the HTW piping system between valve pits. Due to very loud background noise, the test results were inconclusive.

Additional field survey work planned:

There are no additional field surveys planned for this project.


/kw

cc: T. Harper (FSEO)

Memorandum

Date: March 1, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, PhD, PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and CHW
Distribution System

The following progress was made on the subject project during the month of February 1996:

1. A field investigation was performed on February 21. The goal was to use ultrasonic leak detection equipment to locate leaks in selected sections of the underground HTW distribution piping. The results were inconclusive due to very loud background noise in the HTW piping system.
2. Completed analysis of ECOs and submitted Interim Report.

Work planned for March 1996:

1. Await government review comments on the Interim Submittal.
2. Schedule review conference and presentation of Interim Report.


/kw

cc: √ T. Harper (FSEO)
W. Todd

Memorandum

Date: April 4, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, PhD, PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and CHW
Distribution System

The following progress was made on the subject project during the month of March 1996:

No additional work was accomplished due to the Government review of the Interim Report.

Work planned for April 1996:

1. Await government review comments on the Interim Submittal.
2. Schedule review conference and presentation of Interim Report.

cc: W. Todd

FACSIMILE TRANSMITTAL HEADER SHEET

For use of this form, see AR 26-11; the proponent agency is ODISC4

COMMAND/ OFFICE	NAME/ OFFICE SYMBOL	OFFICE TELEPHONE NO. (AUTOVON/Comm.)	FAX NO. (AUTOVON/Comm.)
FROM: Savannah District	Rob Callahan CESAS-PM-MP	(912) 652-5246	(912) 652-5442
TO: R S & H	BILL TUDID CARLOS WARREN		

CLASSIFICATION	PRECEDENCE	NO. PAGES (Including this Header)	DATE-TIME	MONTH	YEAR	RELEASER'S SIGNATURE
N/A		17	15	4	96	Robert A. Callahan

REMARKS Following are the comments I've received on the
Font Stewart EFAP study. See you Wednesday.

Space Below For Communications Center Use Only

DA FORM 3918-R, JUL 90


DA FORM 3918-R, AUG 72 IS OBSOLETE

V2.00

Memorandum

Date: April 29, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, PhD, PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and CHW
Distribution System

The following progress was made on the subject project during the month of April 1996:

1. The Interim Report Review Conference was held at Ft. Stewart on 17 April 1996. Project findings and subsequent evaluation of the HTW line repair ECO was presented by RS&H. Comments were discussed and disposition of each comment was agreed to by conference participants.
2. Schedule for pre-final report submittal is 31 May 1996, 44 days after the Interim Review Conference.

Work planned for May 1996:

1. Complete and submit the pre-final report.

cc: W. Todd



Reynolds, Smith and Hills, Inc.

Architectural, Engineering, Planning and Environmental Services

Transmittal Letter

To: Attached Distribution List

Date:

May 31, 1996

Project: Limited Energy Study HTW
& CHW Distribution Sys.
Fort Stewart & Hunter AAF

Project Number: 694-1331-002

We Transmit:

☒ (X) Herewith ☐ () Via Fax
☐ () Under Separate Cover Via:
☐ () In Accordance with Your Request
☐ () Regular Mail ☒ (X) Overnight Mail ☐ () Courier

For Your:

☐ () Approval
☒ (X) Review and Comment
☐ () Use
☐ () Signature

The Following:

Copies	Date	Description
As per distribution list	5-31-96	Vol. 1 Narrative Report-Pre-Final Submittal
As per distribution list	5-31-96	Vol. II Appendices
As per distribution list	5-31-96	Vol. III Cover, Title Page and Table of Contents
As per distribution list	N/A	Vol. III Valve Pit Summary Sheets - Section 1
As per distribution list	N/A	Vol. III Mech. Room Summary Sheets - Section 2
As per distribution list	N/A	Vol. III Leak Detections Survey Forms - Section 4

Remarks:

/kw

Copies To: C. Warren
File

Reynolds, Smith and Hills, Inc.

4651 Salisbury Road

Jacksonville, Florida 32256

(904) 296-2000 Fax: (904) 279-2491

FL Cert. Nos. AAC001886•EB0005620•LCC000210

By:

William T. Todd, PE

Limited Energy Study
HTW and CHW Distribution Systems
Fort Stewart and Hunter AAF

PRE-FINAL REPORT


No. Copies

2	Commander 3rd Infantry Division and Fort Stewart Attn: AFZP-DEV (Mr. Chet Scratzmeier) Fort Stewart, GA 31314
1	Commander U. S. Army Forces Command Attn: AFPI-ENO (Mr. Naresh Kapur) Fort McPherson, GA 30330
2	Savannah District Corps of Engineers Attn: CESAS-PM-MR (Mr. Rob Callahan) 100 W. Oglethorpe Avenue P. O. Box 889 Savannah, GA 31402-0889
1	Mobile District, Corps of Engineers Attn: CESAM-EN-DM (Mr. Tony Battaglia) 109 St. Joseph Street Mobile, AL 36602

Memorandum

Date: June 5, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, Ph.D., PE
Project Manager 

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of May 1996:

- The Prefinal Report was completed and submitted on 31 May.

Work planned for June 1996:

- None planned; awaiting comments on the Prefinal Report.


CC: W. Todd

F:\FTSMAY_RPT.DOC

Memorandum

Date: July 5, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, Ph.D., PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of June 1996:

- No work was done on the project, as it is in the review process.

Work planned for July 1996:

- None planned; awaiting comments on the Prefinal Report.


CC: W. Todd
A. Battaglia, Mobile COE

F:\FTSWUN_RPT.DOC

Memorandum

Date: August 5, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, Ph.D., PE 
Project Manager

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of July 1996:

- No work was done on the project, as it is in the review process.

Work planned for August 1996:

- None planned; awaiting comments on the Prefinal Report.

CC: W. Todd
A. Battaglia, Mobile COE

F:\FTSWUL_RPT.DOC

FACSIMILE TRANSMITTAL HEADER SHEET

For use of this form, see AF 25-11; the procuring agency is ODISC4

COMMAND/ OFFICE	NAME/ OFFICE SYMBOL	OFFICE TELEPHONE NO. (AUTOVON/Comm.)	FAX NO. (AUTOVON/Comm.)
FROM: Savannah District	Rob Callahan CESAS-PM-MP	(912) 652-5246	(912) 652-5442
TO: RS & H	BILL TODD		

CLASSIFICATION	PRECEDENCE	NO. PAGES (Including this Header)	DATE-TIME	MONTH	YEAR	RELEASER'S SIGNATURE
N/A		2	11	8	96	Robert A. Callahan

REMARKS Bill, following are the only comments I will be sending to you regarding the Ft. Stewart EEAP study. Please incorporate them into your final submittal. As a reminder, I'd like for you to re-read the Specific Instructions before you go final to

Space Below For Communications Center Use Only

DA FORM 3918-R, JUL 90

DA FORM 3918-R, AUG 72 IS OBSOLETE

12.00


insure compliance with all provisions, Thanks for your good work. Fred Cavada at Ft. Stewart is pleased with your work.

RAC

Memorandum

Date: September 4, 1996

To: Savannah District, Corps of Engineers
ATTN: CESAS-PM-MP (Mr. Rob Callahan)
P. O. Box 889
Savannah, GA 31402-0889

From: Carlos S. Warren, Ph.D., PE
Project Manager 

Subject: Monthly Progress Report
Contract No. DACA01-94-0038/0002
Limited Energy Study - Hunter Army Airfield and Ft. Stewart HTW and
CHW Distribution System

The following progress was made on the subject project during the month of August 1996:

- Comments on the Prefinal Report were received. The comments and responses were incorporated into the Final Report.

Work planned for September 1996:

- Completion of the Final Report.
- Submission of Final Report pages on September 6.

CC: W. Todd
A. Battaglia, Mobile COE
F:\FTSAUG_RPT.DOC



Reynolds, Smith and Hills, Inc.

Architectural, Engineering, Planning and Environmental Services

Transmittal Letter

To: Attached Distribution List

Date:

September 6, 1996

Project: Limited Energy Study HTW
& CHW Distribution Sys.
Fort Stewart & Hunter AAF

Project Number: 694-1331-002

We Transmit:

For Your:

☒ (X) Herewith ☐ () Via Fax

☐ () Approval

☐ () Under Separate Cover Via:

☒ (X) Review and Comment

☐ () In Accordance with Your Request

☐ () Use

☐ () Regular Mail ☒ (X) Overnight Mail ☐ () Courier

☐ () Signature

The Following:

Copies	Date	Description
As per distribution list	9-6-96	Vol. 1-Insert and replacement pages
As per distribution list	9-6-96	Vol. II-Insert and replacement pages
As per distribution list	9-6-96	Vol. III-Insert and replacement pages
As per distribution list	9-6-96	Vol. ES-Executive Summary

Remarks:

/kw

Copies To: C. Warren
File

Reynolds, Smith and Hills, Inc.

4651 Salisbury Road

Jacksonville, Florida 32256

(904) 296-2000 Fax: (904) 279-2491

FL Cert. Nos. AAC001886•EB0005620•LCC000210

By:

William T. Todd, PE

A.9-46


Limited Energy Study
HTW and CHW Distribution Systems
Fort Stewart and Hunter AAF

FINAL REPORT

No. Copies

4	Commander 3rd Infantry Division and Fort Stewart Attn: AFZP-DEV (Mr. Fred Cavedo) Fort Stewart, GA 31314
1	Commander U. S. Army Forces Command Attn: AFPI-ENO (Mr. Naresh Kapur) Fort McPherson, GA 30330
2	Savannah District Corps of Engineers Attn: CESAS-PM-MR (Mr. Rob Callahan) 100 W. Oglethorpe Avenue P. O. Box 889 Savannah, GA 31402-0889
1	Mobile District, Corps of Engineers Attn: CESAM-EN-DM (Mr. Tony Battaglia) 109 St. Joseph Street Mobile, AL 36602
1 (ES only)	Commander U. S. Army Engineer Division, South Atlantic Attn: CESAD-EN-TE (Mr. Baggette) 77 Forsyth Street, SW Atlanta, GA 30335-6801
1 (ES only)	Commander U. S. Army Corps of Engineers Attn: CEMP-ET (Mr. Gentil) 20 Massachusetts Avenue, NW Washington, DC 20314-1000
1 (ES only)	Commander U. S. Army Logistics Evaluation Agency Attn: LOEA-PL (Mr. Keath) New Cumberland Army Depot New Cumberland, PA 17070-5007

A.10 RECORDS ANALYSIS AND SITE SURVEY PLAN



Limited Energy Study
High Temperature and Chilled
Water Distribution Systems
Fort Stewart and Hunter AAF

Records Analysis and Site Survey Plan

August 28, 1995
Contract # DACA01-94-D-0038
Project # 694-1331-002

RS&H

Reynolds, Smith and Hills, Inc.
Architectural, Engineering, Planning and Environmental Services

A.10-1

**Limited Energy Study
High Temperature and Chilled Water
Distribution Systems**


Fort Stewart and Hunter Army Airfield

**Records Analysis and
Site Survey Plan**

Savannah District
Corps of Engineers

Contract No. DACA01-94-D-0038
Delivery Order #0002

Reynolds, Smith and Hills, Inc.
Jacksonville, Florida



Carlos S. Warren, PhD, PE
Project Manager



William T. Todd, PE
Field Survey Manager

August 28, 1995

6941331002

A.10-2

**RECORDS ANALYSIS AND
SITE SURVEY PLAN
FORT STEWART AND HUNTER ARMY AIRFIELD
HTW AND CHW DISTRIBUTION SYSTEMS**

TABLE OF CONTENTS

<u>SECTION</u>	<u>TITLE</u>	<u>PAGE</u>
1	1.0 Recommendations for the HTW and CHW Systems at Hunter AAF	1
	1.1 High Temperature Water and Steam Systems	1
	1.2 Chilled Water Distribution Systems	2
2	2.0 Recommendations for the CHW Systems at Fort Stewart	3
3	3.0 Fort Stewart HTW Distribution System	4
4	4.0 Field Investigation Plan	5
	4.1 Central Energy Plant	5
	4.2 Satellite Energy Plant	8
	4.3 Building Hot Water Generators	9
	4.4 Valve Pits, Drain Pits and Valve Boxes	10
	4.5 Underground HTW Distribution System Piping	12
5	5.0 Schedule of Events	13
6	6.0 Supporting Data and Calculations	14

**RECORDS ANALYSIS AND SITE SURVEY PLAN
FORT STEWART AND HUNTER ARMY AIRFIELD
HTW AND CHW DISTRIBUTION SYSTEMS**

1.0 RECOMMENDATIONS FOR THE HTW AND CHW SYSTEMS AT HUNTER AAF

1.1 HIGH TEMPERATURE WATER AND STEAM SYSTEMS

Estimated HTW System Losses

Makeup water volume data for the HTW and steam distribution systems for July 1994 through June 1995 were obtained from the Central Energy Plant (CEP) and Pinwheel Barracks Plant (PBP) operating logs. The total makeup water flow rate for this period was 333,857 gallons, or approximately 916 gallons per day (gpd). The PBP steam distribution system losses represent 77 percent (706 gpd) of the total and the CEP HTW system losses make up the remaining 23 percent (210 gpd). Assuming the blowdown is about equal to the chemical feed system input, the makeup water flow rate should be roughly equal to the amount of leaks from the distribution system. Based on an estimated total system volume of 1,900 gallons for the CEP HTW system, the estimated HTW leakage rate is approximately 11 percent of the total HTW system volume per day. The PBP distributes 50 psi steam. The losses from the PBP system are higher than the CEP system losses as would be expected for a steam distribution system.

The total estimated cost of losses from the CEP and PBP HTW distribution systems is approximately \$2,120 per year. This value includes the cost for fuel oil used by the boilers (443 MBtu/Year & \$1,925/Year); distribution system pumps (314 kWh/Year & \$15/Year); and the cost of raw water produced at Hunter AAF (\$180/Year). The cost for chemical treatment of the HTW system leaks is assumed to be negligible. The boiler energy use and cost assumes an average boiler efficiency of 75 percent.

Recommendations

The estimated 11 percent losses for the CEP distribution system are high for a closed loop system. However, the total costs of losses from the CEP HTW system and the PBP steam system are less than one percent of the total operating costs of these systems. Therefore, we recommend no further studies be undertaken for the HTW distribution systems from the CEP and the PBP.

1.2 CHILLED WATER DISTRIBUTION SYSTEMS

Estimated CHW System Losses

The chilled water makeup is not metered at either the CEP or the PBP. The Hunter AAF DPW staff said that their chilled water chemical treatment contractor has indicated a leakage problem with both the CEP and the PBP chilled water distribution systems. Conversations with the chemical treatment contractor revealed an estimate of thousands of gallons per week being lost from each of these two distribution systems and that there has been a leakage problem for over eight years. The contractor samples the CHW system water and adds chemicals each month. The chemicals have vanished between monthly samples. The actual CHW system losses cannot be accurately determined since there is no trace of the chemicals left.

The total chilled water system capacities were estimated to be about 4,700 gallons for the PBP and 4,200 gallons for the CEP. Assuming a conservative estimate of the equivalent of one system volume is lost each month, the CHW losses would amount to over 2,000 gallons per week. This represents a leakage rate of three percent of the total system volume per day. The actual losses could be much higher.

Recommendations

There is obviously a problem with these systems, however it can not be quantified without some type of metering effort. Installing new permanent water meters on the CHW system makeup water lines at the PBP and the CEP would cost approximately \$500 and \$200, respectively. The cost to have RS&H temporarily meter these systems would be much more than the \$700 the Army would pay to have a mechanical contractor install the two new permanent meters.

We recommend that permanent flow meters be installed on the chilled water makeup lines at the CEP and the PBP. These meters should be read and the data tabulated on a monthly basis. The new information could be analyzed after three to four months of data have been observed and recorded. Recommendations for further action could be made at that time.

2.0 RECOMMENDATIONS FOR THE CHW SYSTEM AT FORT STEWART

Estimated CHW System Losses

Makeup water volume data for July 1994 through June 1995 for the chilled water distribution system were obtained from the CEP operating logs. The total makeup water flow rate for this period was 1,106,710 gallons, or approximately 3000 gallons per day. This makeup water flow rate should be roughly equal to the amount of chilled water leaks in the distribution system. The total volume of water in the CHW distribution system was estimated to be about 600,000 gallons. Based on the total estimated volume of chilled water, the estimated chilled water leakage is approximately 0.5 percent of the total chilled water system volume per day.

The total estimated cost of the chilled water system losses is about \$1,250 per year. This value includes the cost for energy used by the chillers, condenser pumps and cooling tower fans (11,310 kWh/Year & \$566/Year); distribution system pumps (1,310 kWh/Year & \$66/Year); and the cost of raw water produced at Fort Stewart (\$615/Year). There is no chemical treatment used for the chilled water distribution system. The chiller energy use and cost assumes all of the chilled water is produced by electric centrifugal chillers, a worst case scenario since electricity is the most expensive fuel utilized at Fort Stewart.

Recommendations

The amount of the CHW distribution system losses is less than one percent of the total CHW system volume per day. Therefore, we recommend no further studies be undertaken for the Fort Stewart CHW distribution system.

3.0 FORT STEWART HTW DISTRIBUTION SYSTEM

Estimated HTW System Losses

Makeup water volume data for July 1994 through June 1995 for the HTW distribution system were obtained from the Central Energy Plant (CEP) operating logs. The total metered makeup water flow for this period was 4,029,636 gallons, or approximately 11,048 gallons per day. Boiler blowdown and flow rates for the three unmetered chemical feed systems were estimated based on conversations with CEP operators. The total estimated losses for the HTW system are approximately 5,809,700 gallons per year. This estimate assumes the total makeup water less the boiler blowdown is roughly equal to the amount of leaks from the HTW distribution system. Based on an estimated total HTW system volume of 218,000 gallons, the estimated HTW leakage represents approximately five percent of the total HTW system volume per day. Typical closed loop distribution systems have a makeup requirement of one-fourth to one-half of one percent of the total system volume in a given 24 hour period.

The total estimated cost of losses from the HTW distribution system is \$29,290 per year. This value includes the cost for wood chips, fuel oil and natural gas used by the boilers (22,100 MBtu/Year & \$25,640/Year); distribution system pumps (8,400 kWh/Year & \$420/Year); and the cost of raw water produced at Fort Stewart (\$3,230/Year). The cost for chemical treatment of the HTW system leaks is assumed to be negligible compared to these other values. The calculated boiler energy use and cost assumes an average boiler efficiency of 68 percent.

4.0 FIELD INVESTIGATION PLAN

The field investigation will be accomplished in three phases. The objective of the first phase is to determine as accurately as possible how much is leaking from the HTW system. This will be accomplished by first surveying the Central Energy Plant and Satellite Energy Plants, and metering and estimating the mass flows into and out of the HTW system. The second step of the first phase is to estimate the amount of HTW leaking within the hot water generators in the buildings served by the HTW system.

Valve pits, drain pits and valve boxes will be inspected during the second phase of the field survey effort. This survey will indicate the location of leaking valves and fittings and also isolate sections of the underground distribution piping where leaks may be occurring. We will also attempt to quantify the amount of HTW leaking from the various valves and fittings.

The final phase of the field investigation will attempt to pinpoint and quantify the leaks within the underground HTW distribution system piping. The detailed field investigation plans and schedule of events are presented in the following pages.

4.1 CENTRAL ENERGY PLANT (CEP)

1. Measure the flow of makeup water to the HTW system.

The amount of makeup water added to the HTW system is a direct indication of how much HTW is leaking out of the system.

The flows will be measured using a non-intrusive, clamp-on, transient-time ultrasonic flow meter. If any pipe insulation must be removed for these measurements, we will request that the Fort Stewart DPW perform the removal and reinstallation.

We will make sure the makeup water flow measurements include the water softeners, two chemical feed systems and the phosphate tank. It appears that the metered flow only includes the water that goes through the water softeners.

There is a 3 inch raw water line that should include all of these systems except perhaps the phosphate tank. The 3 inch line splits with a 2.5 inch line going to the water softeners and two 3/4 inch lines going to the chemical feed systems. The 2.5 inch makeup water line from the

water softeners and the 3/4 inch makeup water line from the sulphur tank feed into the deaerator. The 3/4 inch makeup water line from the ph control tank feeds into all three cascade heaters.

There is a 1/2 inch line (rated at 5 g.p.m. on the record drawings) from the phosphate tank that feeds into the 4 inch feed water line to the wood fired boiler.

2. Measure or estimate the continuous and intermittent blowdown from all boilers and cascade heaters.

The amount of blowdown water must be subtracted from the amount of makeup water to determine the actual HTW distribution system losses.

The flows will be measured using a non-intrusive, clamp-on, transient-time ultrasonic flow meter. If any pipe insulation must be removed for these measurements, we will request that the Fort Stewart DPW perform the removal and reinstallation.

There is a 4 inch line from the intermittent blowdown tank (for the wood fired boiler) rated at 165 g.p.m. on the record drawings.

Each of the three cascade heaters has a 1.5 inch blowdown line that feeds into a 3 inch header. The 3 inch blowdown header goes to a blowdown tank that may or may not be the same tank mentioned above. The record drawings indicate a blowdown tank located outside the south corner of the CEP. It is not clear from the drawings but this line may be part of the condensate return system.

3. Estimate the total flow of HTW through the supply distribution system.

The total HTW flow value will be used to determine what percentage of the total flow is lost by leaks in the distribution system.

Read and record the pressures shown on the pressure gages before and after the supply pumps for all three HTW distribution zones. Measure and record the voltage and current for each HTW pump motor. Record the data from the nameplates on the pumps and pump motors.

4. Obtain copies of the boiler water, boiler feed water and HTW supply water analysis reports.

These reports will be used to verify the boiler blowdown estimates and also to compare with the samples taken from the various domestic hot water systems in the buildings served by the HTW system. The comparison will help determine if any of the heat exchangers in the hot water generators have failed. Refer to section on survey of mechanical equipment rooms for additional information.

We will also comment on the chemical makeup of the HTW system water and whether it is appropriate to prevent corrosion or pitting of the HTW distribution system piping.

Personnel Assignments

1 - Engineer

1 - Metering Subcontractor

4.2 SATELLITE ENERGY PLANT (SEP)

1. Measure or estimate the flow of makeup water to the SEP HTW distribution system.

The amount of makeup water added to the SEP HTW system will provide a direct indication of how much HTW is leaking out of this part of the system.

There is no direct fresh or treated makeup water feed to the SEP HTW distribution system. The water level in the two SEP cascade heaters is manually checked three times per day (once each shift). When the water level in the cascade heaters drops below a certain value, the CEP operators use the HTW system return pipes to "back fill" the SEP cascade heaters. We will determine how often these systems need to be filled and approximately how much water is "added".

2. Measure or estimate the blowdown from the two cascade heaters.

The amount of blowdown water must be subtracted from the amount of makeup water to determine the actual HTW distribution system losses.

Each of the three cascade heaters in the CEP has a 1.5 inch blowdown line. Assuming the two cascade heaters in the SEP also have blowdown lines, we will determine the frequency and duration of use for these blowdown lines.

3. Estimate the total flow of HTW through the SEP supply distribution system.

The total HTW flow from the SEP will be used to determine what percentage of the total HTW flow is lost by leaks in this distribution system.

Read and record the pressures shown on the pressure gages before and after the supply pump. Measure and record the voltage and current for the HTW pump motor. Record the data from the nameplates on the pumps and pump motors.

Personnel Assignments

1 - Engineer

1 - Metering Subcontractor

4.3 BUILDING HOT WATER GENERATORS

1. Obtain a sample of the domestic hot water from the building for testing.

These samples will be analyzed by a laboratory and the analysis will be compared to the analysis of the HTW and the Fort Stewart potable water supply. If chemicals that are usually only present in the HTW are found in the domestic hot water, then the heat exchanger has probably failed and is leaking. Hot water temperatures will also be measured to indicate a leaking heat exchanger or failed controls/valves.

The domestic hot water source will be allowed to flow for a sufficient time prior to sampling to ensure the sample is not diluted with potable cold water. The samples will be taken during a time that the building hot water system is not being heavily used (9:00 AM to 3:00 PM).

2. Survey Hot Water Generators.

Those hot water generators that have leaking HTW heat exchangers will be surveyed to determine the leakage rate and volume. The hot water generators will be isolated by cut-off valves and tank overflows measured.

Personnel Assignments

Crew No. 1:

1 - Engineer

1 - Technician

Crew No. 2:

1 - Engineer

1 - Technician

4.4 VALVE PITS, DRAIN PITS AND VALVE BOXES

Valve Pits

There are approximately 60 valve pits located along the HTW supply and return lines.

1. Check for HTW leaks around the valve stems, flanges and fittings for all of the valves and fittings in the valve pit. Estimate the volume of flow from each leak found.

Valves and fittings typically found in the valve pits are listed below.

- a. Check globe valves on all HTW mains and take offs.
 - b. Check drain valves on all mains. There are two globe valves for each HTW main valve.
 - c. Check valves and fittings on all line vents. There are two globe valves and an air bottle on each vent line.
2. Check for steam flowing from the conduit vents on HTW lines where they enter and exit the pit.
 3. If there is standing water in the bottom of the pit, make a note indicating that the pump is not working.

Drain Pits

The drain pits are located at low points along the main HTW supply and return lines.

1. Check for HTW leaks around the valve stems, flanges and fittings for all of the valves and fittings in the drain pits. Estimate the volume of flow from each leak found.

Typically, there is one globe valve on each HTW supply and return line.

2. Check for steam flowing from the conduit vents on HTW lines where they enter and exit the pit.
3. If there is standing water in the bottom of the pit, make a note indicating that the pump is not working.

Valve Boxes

The valve boxes are located at high points along the main HTW supply and return lines.

1. Check for HTW leaks around the valve stems, flanges and fittings for all of the valves and fittings in the valve boxes. Estimate the volume of flow from each leak found.

There are typically two HTW risers in each valve box and two globe valves and one air bottle on each riser.

Personnel Assignments

Crew No. 1:

1 - Engineer
1 - Technician

Crew No. 2:

1 - Engineer
1 - Technician

4.5 UNDERGROUND HTW DISTRIBUTION SYSTEM PIPING

Information obtained during the survey of the valve pits will be used to isolate sections of the HTW distribution system that is suspected of having leaks. Once these sections of piping have been identified, an infrared thermometer will be used to locate "hot spots" at ground level along the HTW distribution piping. The hot spots will indicate areas of the piping where the pipe insulation has become saturated and is no longer effective. There are two possible causes of the hot spots. Either the outer conduit has failed and the insulation has become soaked with groundwater, or a leak in the pipe has caused the insulation to become saturated with HTW.

The sections of HTW piping suspected of having leaks will be systematically surveyed with a electronic gas and liquid leak detector in an effort to determine as accurately as possible the location of all distribution system leaks. The leaking HTW will more than likely flash to steam as it escapes from the pipe. The ultrasonic range of the leak detector will be used to locate these gaseous type "steam" leaks. The sonic range can be used to detect liquid leaks if for some reason the HTW leaks remain in the liquid form.

Personnel Assignments

Crew No. 1:

1 - Engineer
1 - Technician

Crew No. 2:

1 - Engineer
1 - Technician

5.0 SCHEDULE OF EVENTS

<u>Week Ending</u>	<u>Tasks to be Accomplished</u>
Aug 04, 1995	<ul style="list-style-type: none">- Obtain data, drawings and maintenance records for the HTW and CHW systems at Fort Stewart and Hunter AAF.- Conduct interviews with DPW Personnel at Fort Stewart and Hunter AAF.- Preliminary survey of CEP, valve pits and mechanical equipment rooms at Fort Stewart.
Sep 15, 1995	<ul style="list-style-type: none">- Locate HTW makeup water, chemical feed and blowdown pipes to be metered and determine if pipe insulation removal is required.- Obtain copies of recent HTW sample analysis reports from the CEP and potable water analysis reports from the water plant.- Progress report to FESO and Savannah COE.
Oct 27, 1995	<ul style="list-style-type: none">- Survey the CEP. Meter HTW makeup water, chemical feed water and blowdown water. Record pump and motor data.- Survey the SEP. Meter HTW makeup water and blowdown water. Record pump and motor data.- Water samples taken in buildings.- Progress report to FESO and Savannah COE.
Nov 10, 1995	<ul style="list-style-type: none">- Survey valve pits, drain pits and valve boxes.- Progress report to FESO and Savannah COE.
Dec 15, 1995	<ul style="list-style-type: none">- Survey HTW supply and return distribution lines.- Survey leaking hot water generators.- Progress report to FESO and Savannah COE.

6.0 SUPPORTING DATA AND CALCULATIONS



SUBJECT HUNTER AAF
HTW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 1 OF 2
DATE 8-16-95
DATE _____

HTW System Losses

Make up water data for the Pinwheel Barracks and the central energy plant were tabulated from boiler logs for 7/94 through 6/95. Assuming the makeup water is equal to the distribution system losses less the amount of boiler blowdown, the

Make up Water	916 gal/day (avg)
Chemical Feed	+ 30 gal/day estimate
Blowdown	- 30 gal/day estimate
<hr/>	
System Losses =	916 gal/day (avg)
	0.6 gal/min (avg)

Energy Loss :

$$257,332 \text{ gal/yr} \times 8.345 \frac{\text{lb}}{\text{gal}} \times 1 \frac{\text{Btu}}{16^\circ\text{F}} \times (155-70)^\circ\text{F} = 182.5 \frac{\text{MBtu}}{\text{YR}} \quad (\text{PB})$$

$$76,525 \text{ " } \times \text{ " } \times \text{ " } \times (305-70)^\circ\text{F} = 150.1 \frac{\text{MBtu}}{\text{YR}} \quad (\text{CEP})$$

$$\text{Total Energy Loss} = 182.5 + 150.1 = \underline{332.6 \text{ MBtu/YR}}$$

$$\text{Cost : } \$0.6124/\text{gallon} \times \frac{1 \text{ gallon}}{0.141 \text{ MBtu}} = \$4.34/\text{MBtu}$$

$$332.6 \frac{\text{MBtu}}{\text{YR}} \times \frac{1}{0.75} \text{ eff} \times \$4.34/\text{MBtu} = \underline{\$1,925/\text{Year}}$$

Pumping Cost

$$\text{Pump BHP} = \frac{\text{GPM} \times \text{Head}}{3960 \times \text{eff}} = \frac{0.6 \times 200 \text{ ft}^*}{3960 \times 0.70} = 0.04 \text{ BHP}$$

A-10-18 * From record drawings



SUBJECT HUNTER AAF
HTW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 2 OF 2
DATE 8-17-95
DATE _____

Pumping Cost - continued

$$0.04 \text{ RHP} \times 0.746 \frac{\text{kw}}{\text{HP}} \div 0.9 \text{ motor eff} \times 8760 \frac{\text{hr}}{\text{yr}} = \underline{314 \frac{\text{kwh}}{\text{yr}}}$$

$$\text{Cost} = 314 \frac{\text{kwh}}{\text{yr}} \times \$0.048 / \text{kwh} = \underline{\$15 / \text{year}}$$

Water Cost

$$886 \frac{\text{gal}}{\text{day}} \times 365 \frac{\text{day}}{\text{yr}} \times \$0.56 / 1000 \text{ gal} = \underline{\$181 / \text{year}}$$

Total Cost

Heating Fuel + Pumping cost + Water cost = Total

$$\text{Total Cost} = \$1925 + \$15 + \$180 \approx \underline{\$2,120 / \text{year}}$$

Percent Losses (CEP only)

$$\frac{210 \text{ gal/day makeup}}{1900 \text{ gallons volume}} \times 100 = \underline{\underline{11 \%}}$$

Hunter AAF - Central Energy Plant & Pinwheel Barracks
 Boiler Makeup Water
 Filename: HAAF-HTW.WQ1

Mo	Yr	PB (2) Makeup Gal(1)	Makeup Gal/Day	CEP (3) Makeup Gal(1)	Makeup Gal/Day	Total Makeup Gal(1)	Makeup Gal/Day
7	94	18660	602	4010	129	22670	731
8	94	17320	559	3640	117	20960	676
9	94	15030	501	3320	111	18350	612
10	94	15460	499	7478	241	22938	740
11	94	18870	629	10950	365	29820	994
12	94	17950	579	10310	333	28260	912
1	95	23840	769	6900	223	30740	992
2	95	23499	839	5730	205	29229	1044
3	95	26440	853	5750	185	32190	1038
4	95	23750	792	6280	209	30030	1001
5	95	28873	931	6222	201	35095	1132
6	95	27640	921	5935	198	33575	1119
AVG		21444	706	6377	210	27821	916
TOTALS		257332		76525		333857	

- (1) Source is Hunter AAF Operating Logs.
 (2) PB - Pinwheel Barracks Energy Plant.
 (3) CEP - Central Energy Plant.

Estimate Distribution System Losses:

	916	gpd, avg make-up water
-	30	gpd, avg blowdown water *
	886	gpd, avg dist sys losses

* Boiler blowdown estimate:

	300	gpm, estimate 150 gpm for 3 inch pipe x 2 pipes
x	0.033	min/blowdown, 2 seconds per blowdown
	10	gal/blowdown
x	3	blowdowns/day, assumed 3 blowdowns per day
	30	gal/day

Hunter AAF - Central Energy Plant
 Estimate of HTW System Losses
 Filename: H-HTW-CP.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Feet	Pipe Vol. (CF)	Pipe Vol. (Gal)
CWS	All (Plant)	6	150	29.5	220
CWR	All (Plant)	6	200	39.3	294
CWS	All (main)	6	26	5.1	38
CWR	All (main)	6	26	5.1	38
CWS	All (main)	4	255	22.3	166
CWR	All (main)	4	255	22.3	166
CWS	All (main)	2	368	8.0	60
CWR	All (main)	2	368	8.0	60
CWS	1-S Bldg.	1	154	0.8	6
CWR	1-S Bldg.	1	154	0.8	6
CWS	2-S Bldg.	1	98	0.5	4
CWR	2-S Bldg.	1	98	0.5	4

TOTALS		2152		1062
--------	--	------	--	------

Expansion Tanks, etc	500
Two Story Building Piping (estimate)	200
One Story Building Piping (estimate)	125

Estimated System Volume	1887	Gallons
-------------------------	------	---------

1.0% of total volume lost per day =	19	Gal/Day
-------------------------------------	----	---------

19 gal/day x 30 day/mo =	566	Gal/Mo.
--------------------------	-----	---------

19 gpd / 1440 min/day =	0.01	Gal/Min
-------------------------	------	---------

100.0% of total volume lost per day =	1887	Gal/Day
---------------------------------------	------	---------

1887 gal/day x 30 day/mo =	56610	Gal/Mo.
----------------------------	-------	---------

1887 gpd / 1440 min/day =	1.31	Gal/Min
---------------------------	------	---------

Hunter Army Air Field
Fuel Oil Consumption
Filename: HAAF-OIL.WQ1

Month	CEP	PBP	Total
Jul	3730	21157	24887
Aug	3880	17978	21858
Sep	3460	17244	20704
Oct	5454	8611	14065
Nov	6421	13004	19425
Dec	10040	28962	39002
Jan	8470	43829	52299
Feb	8455	44122	52577
Mar	6630	44965	51595
Apr	5379	29115	34494
May	4580	21693	26273
Jun	3850	23250	27100
Gal/Yr	70349	313930	384279
Mbtu/Y	9919	44264	54183
\$/Yr	43082	192251	235332



Telephone Call Confirmation

912-352-5519

Project Number 694 1331 002

Local (L.D.) (Placed) Rec'd 8-17-95 Date 8-17-95

Conversed with Troy Noonan or Hunter AAF Boiler Plants

Regarding Blowdown estimate for CEP and PB boilers

They have no set schedule for boiler blowdown. The operator that samples the water will manually blowdown the boiler as needed to adjust the chemical makeup of the water.

The blowdown pipe is approximately 3 inches in diameter. The duration of each blowdown is 2 seconds.

Distribution:



SUBJECT HUNTER AAF
CHW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 1 OF _____
DATE 8-22-95
DATE _____

According to the chemical treatment contractor, at least one complete volume must be leaking out each month.

CEP Volume \approx 4150 gal.

PBP Volume \approx 4670 gal.

Total = 8,820 gal.

8,820 gal / 30 days \approx 294 gal/day

Percent losses $\approx \frac{294 \frac{\text{gal}}{\text{day}} \text{ makeup est.}}{8,820 \text{ gal Volume est.}} \times 100 = \underline{3\% \text{ minimum}}$



SUBJECT HUNTER AAF
CHW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 2 OF _____
DATE 8-21-95
DATE _____

SYSTEM INFORMATION :

PBP; From record drawings, Chiller cap = 600 tons

1060 gpm, 90 ft head, 80% eff.

Pump motor design = 40 hp

$$\text{Pump BHP} = \frac{1060 \times 90}{3960 \times 0.8} = 30 \text{ BHP}$$

Make up water pipe dia. = 1", meter cost \approx \$200

CEP; from record drawings, Chiller cap. = 200 tons

342 gpm, 45 ft head, 70% eff.

Pump motor design = 20 hp

$$\text{Pump BHP} = \frac{342 \times 45}{3960 \times 0.78} = 5 \text{ BHP}$$

Make up water pipe dia. = 1 1/2", meter cost \approx \$500

Hunter AAF - Central Energy Plant
 Estimate of Chilled Water Losses
 Filename: H-CHW-CP.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Feet	Pipe Vol. (CF)	Pipe Vol. (Gal)
CWS	All (Plant)	8	145	50.6	379
CWR	All (Plant)	8	90	31.4	235
CWS	All (main)	8	285	99.5	744
CWR	All (main)	8	285	99.5	744
CWS	All (main)	6	338	66.4	496
CWR	All (main)	6	338	66.4	496
CWS	1-S Bldg.	4	154	13.4	101
CWR	1-S Bldg.	4	154	13.4	101
CWS	2-S Bldg.	3	98	4.8	36
CWR	2-S Bldg.	3	98	4.8	36

TOTALS	1985	3368
--------	------	------

Expansion Tank	132
Two Story Building Piping (estimate)	400
One Story Building Piping (estimate)	250

Estimated System Volume	4150	Gallons
-------------------------	------	---------

1.0% of total volume lost per day =	42	Gal/Day
-------------------------------------	----	---------

42 gal/day x 30 day/mo =	1245	Gal/Mo.
--------------------------	------	---------

42 gpd / 1440 min/day =	0.03	Gal/Min
-------------------------	------	---------

100.0% of total volume lost per day =	4150	Gal/Day
---------------------------------------	------	---------

4150 gal/day x 30 day/mo =	124500	Gal/Mo.
----------------------------	--------	---------

4150 gpd / 1440 min/day =	2.88	Gal/Min
---------------------------	------	---------

Hunter AAF - Pinwheel Barracks Chiller Plant
 Estimate of Chilled Water Losses
 Filename: H-CHW-PB.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Feet	Pipe Vol. (CF)	Pipe Vol. (Gal)
CWS	All (Plant)	8	67	23.4	175
CWR	All (Plant)	8	85	29.7	222
CWS	All (main)	8	218	76.1	569
CWR	All (main)	8	218	76.1	569
CWS	1275	6	308	60.5	452
CWR	1275	6	308	60.5	452
CWS	1276	4	274	23.9	179
CWR	1276	4	274	23.9	179
CWS	1277	6	304	59.7	447
CWR	1277	6	304	59.7	447

TOTALS		2360		3691
--------	--	------	--	------

Expansion Tank	80
Building 1275 Piping (estimate)	300
Building 1276 Piping (estimate)	300
Building 1277 Piping (estimate)	300

Estimated System Volume	4671	Gallons
-------------------------	------	---------

1.0% of volume lost per day =	47	Gal/Day
-------------------------------	----	---------

47 gal/day x 30 day/mo =	1401	Gal/Mo.
--------------------------	------	---------

47 gpd / 1440 min/day =	0.03	Gal/Min
-------------------------	------	---------

100.0% of volume lost per day =	4671	Gal/Day
---------------------------------	------	---------

4671 gal/day x 30 day/mo =	140130	Gal/Mo.
----------------------------	--------	---------

4671 gpd / 1440 min/day =	3.24	Gal/Min
---------------------------	------	---------

A.10-27



Telephone Call Confirmation

800-343-0538

Project Number 694 1331 002

Local LD. Atlanta Placed Rec'd 8-17-95 Date

Conversed with Frank Lloyd or Technical Specialties Corp.

Regarding Hunter AAF Chilled Water Systems at CEP & PB

Frank estimates "thousands of gallons per week" are lost from each chilled water system. They add chemicals to the systems and when a sample is taken the following month there is no trace of the chemicals. They can estimate the volume lost by taking samples more often and tracking the chemical depletion. Frank estimates the cost of installing a new permanent water meter is between \$200 (for a 1" pipe) and \$600 (for a 3" pipe). He called the water leaks in the CEP and PB a "serious loss".

In addition to the costs of leaks, the loss of chemicals creates a corrosion problem. These systems have been leaking for over 8 years. The volume in a system is estimated at 7-9 gallons/ton. Cost for chemical treatment is \$4-\$6 per ton (for systems > 1000 tons).


Distribution:

A.10-28

153 | Plumbing Appliances

153 100 | Water Appliances

		CREW	DAILY OUTPUT	MAN-HOURS	UNIT	1995 BARE COSTS				TOTAL INCL O&P
						MAT.	LABOR	EQUIP.	TOTAL	
130	3060	1 Plum	6	1.333	Ea.	2,125	39		2,164	2,375
	3080		4	2		2,050	58.50		2,108.50	2,350
	3100		3	2.667		2,500	78		2,578	2,875
	3120	Q-1	4	4		3,450	106		3,556	3,950
	3140		3	5.333		4,775	141		4,916	5,475
	3160		3	5.333		5,700	141		5,841	6,500
	3180		2.50	6.400		6,550	169		6,719	7,450
	3200		2	8		8,750	211		8,961	9,950
	3220		1.50	10.667		10,100	281		10,381	11,500
	3240		1	16		15,100	420		15,520	17,200
	3260	Q-2	1.50	16		22,400	440		22,840	25,300
160	0010									
	1000									
	1020									
	1100	Q-1	3.60	4.444	Ea.	5,825	117		5,942	6,600
	1140		2.50	6.400		6,275	169		6,444	7,150
	1180	Q-2	2.60	9.231		8,525	252		8,777	9,750
	1220		2.10	11.429		12,900	315		13,215	14,700
	1260		2	12		21,000	330		21,330	23,600
	1300		1.70	14.118		21,900	385		22,285	24,600
	2000									
	2020									
	2060	1 Plum	16	.500	Ea.	66.50	14.65		81.15	96
	2080		14	.571		115	16.75		131.75	153
	2100		12	.667		157	19.55		176.55	202
	2300									
	2340	1 Plum	8	1	Ea.	420	29.50		449.50	505
	2360		6	1.333		615	39		654	735
	2600									
	2640	Q-1	3	5.333	Ea.	2,900	141		3,041	3,425
	2660		1.50	10.667		4,525	281		4,806	5,400
	2680		1	16		6,500	420		6,920	7,825
	2700		.80	20		12,800	530		13,330	14,900
	7000									
	7260									
	7300	1 Plum	7	1.143	Ea.	790	33.50		823.50	920
	7320	Q-1	3.60	4.444		1,125	117		1,242	1,425
	7340		2.50	6.400		1,950	169		2,119	2,400
	7360	Q-2	2.60	9.231		3,250	252		3,502	3,950
	7380		2.10	11.429		6,925	315		7,240	8,100
	7400		1.70	14.118		9,475	385		9,860	11,000



155 | Heating

155 100 | Boilers

		CREW	DAILY OUTPUT	MAN-HOURS	UNIT	1995 BARE COSTS				TOTAL INCL O&P
						MAT.	LABOR	EQUIP.	TOTAL	
101	0010									
	0020									
105	0010									
	0020									



SUBJECT FORT STEWART
CHILLED WATER SYSTEM
DESIGNER W.T.T.
CHECKER _____

AEP NO _____
SHEET 1 OF 3
DATE 8-16-95
DATE _____

Chilled water makeup:

from operator logs for 7/94 - 6/95 the total amount of make up water for the chilled water distribution system = 1,106,710 gal/yr.

Average make up \approx 3000 gal/day

Average makeup = 2.1 gal/min

This amount should be approximately equal to the amount of leaks in the distribution system, and is much less than 1% of the total chilled water supplied to the distribution system.

Energy Loss:

$$1106710 \frac{\text{gal}}{\text{yr}} \times \frac{8.345 \text{ lb}}{\text{gal}} \times 1 \frac{\text{Btu}}{\text{lb}^\circ\text{F}} \times (70-49)^\circ\text{F} = 193.9 \frac{\text{MBtu}}{\text{yr}}$$

Assuming all electric chillers (worst case):

$$193.9 \frac{\text{MBtu}}{\text{yr}} \times 0.70 \frac{\text{kW}}{\text{ton}} \times \frac{1 \text{ ton}}{12000 \text{ Btu}} = \underline{11,310 \text{ kWh/yr}}$$

$$\text{Cost} = 11,310 \text{ kWh/yr} \times \$0.0500/\text{kWh} = \underline{\$566/\text{yr}}$$

Pumping Cost:

$$\text{Pump BHP} = \frac{\text{GPM} \times \text{Head}}{3960 \times \text{eff}} = \frac{2.1 \times 250^*}{3960 \times 0.72} = 0.18 \text{ BHP}$$

$$0.18 \text{ BHP} \times 0.746 \frac{\text{kW}}{\text{HP}} \div 0.9 \text{ motor eff.} \times 8760 \frac{\text{hr}}{\text{yr}} = \underline{1310 \text{ kWh/yr}}$$

A.10-30 * from record drawings



SUBJECT FORT STEWART
CHILLED WATER SYSTEM
DESIGNER WJT
CHECKER _____

AEP NO _____
SHEET 2 OF 3
DATE _____
DATE _____

$$\text{Pumping Cost} = 1310 \text{ kWh/yr} \times \$0.0500/\text{kWh} = \underline{\$66/\text{yr}}$$

Water Cost:

$$1,106,710 \frac{\text{gal}}{\text{yr}} \times \frac{\$0.5562}{1000 \text{ gal}} = \underline{\$615/\text{yr}}$$

Total Cost

$$\text{Energy Cost} + \text{Pumping Cost} + \text{Water Cost} = \text{Total}$$

$$\text{Total Cost} = \$566 + \$66 + \$615 = \underline{\$1247/\text{yr}}$$

Percent Losses

$$\frac{3023 \frac{\text{gal}}{\text{day}} \text{ Makeup}}{601184 \text{ Gal. Volume}} \times 100 = \underline{\underline{0.5\%}}$$



SUBJECT FORT STEWART
CHILLED WATER SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 3 OF 3
DATE 8-16-95
DATE _____

Energy Required to Produce Chilled Water:

- Chiller : Assume 1994-95 model centrifugal chiller.

$$\text{Energy demand} = \underline{0.60 \text{ kw/ton}}$$

- Condenser Pumps :

Assume : 3 gpm /ton (standard)
Pump head = 60 ft , eff. = 0.72

$$\frac{3 \frac{\text{gpm}}{\text{ton}} \times 60 \text{ ft}}{3960 \times 0.72} = 0.06 \text{ BHP/ton}$$

$$0.06 \frac{\text{BHP}}{\text{ton}} \times 0.746 \frac{\text{kw}}{\text{BHP}} \div 0.9 \text{ motor eff.} = \underline{0.05 \text{ kw/ton}}$$

- Cooling Tower Fans :

Assume : 100 hp for 1500 ton chiller (BAC catalog)
85% motor loading , 90% motor eff.

$$\frac{100 \text{ hp} \times 0.85}{1500 \text{ tons}} \times 0.746 \frac{\text{kw}}{\text{BHP}} \div 0.9 = \underline{0.05 \text{ kw/ton}}$$

$$\text{Total Energy Demand} = 0.60 + 0.05 + 0.05 = \underline{\underline{0.70 \text{ kw/ton}}}$$

Fort Stewart Central Energy Plant
 Chiller Makeup Water
 Filename: FS-CHW.WQ1

Month	Year	Chiller Makeup Gal (1)	Days/ Month	Makeup Gal/Day	Chiller Makeup Gal/Min
7	94	210400	31	6787	4.7
8	94	131600	31	4245	2.9
9	94	83830	30	2794	1.9
10	94	76360	31	2463	1.7
11	94	290300	30	9677	6.7
12	94	58000	31	1871	1.3
1	95	18470	31	596	0.4
2	95	10310	28	368	0.3
3	95	25500	31	823	0.6
4	95	90810	30	3027	2.1
5	95	69570	31	2244	1.6
6	95	41560	30	1385	1.0
AVERAGES		92226		3023	2.1

TOTAL 1106710 gal/yr

(1) Source is Fort Stewart Operating Logs.

Estimate of Distribution System Losses:

2.1 gpm, avg make-up water

Fort Stewart - Central Energy Plant
 Estimate of CHW System Losses
 Filename: F-CHW-CP.WQ1

Pipe Service	Bldg. Served	Pipe Dia. (in)	Linear Feet	Pipe Vol. (CF)	Pipe Vol. (Gal)
ZONE 1					
CWS	All (main)	18	1350	2385.6	17847
CWR	All (main)	18	1350	2385.6	17847
CWS	All (main)	16	2000	2792.5	20891
CWR	All (main)	16	2000	2792.5	20891
CWS	All (main)	14	200	213.8	1599
CWR	All (main)	14	200	213.8	1599
CWS	All (main)	12	1850	1453.0	10870
CWR	All (main)	12	1850	1453.0	10870
CWS	All (main)	10	750	409.1	3060
CWR	All (main)	10	750	409.1	3060
CWS	All (main)	8	750	261.8	1959
CWR	All (main)	8	750	261.8	1959
CWS	All (main)	5	800	109.1	816
CWR	All (main)	5	800	109.1	816
CWS	All (main)	10	350	190.9	1428
CWR	All (main)	10	350	190.9	1428
CWS	All (main)	8	800	279.3	2089
CWR	All (main)	8	800	279.3	2089
CWS	All (main)	6	400	78.5	588
CWR	All (main)	6	400	78.5	588
Branch Piping (assume 5% of mains)					6115
60 Buildings Piping (estimate)					12000
SUBTOTAL ZONE 1			16100		140409
ZONE 2					
CWS	All (main)	14	3700	3955.4	29590
CWR	All (main)	14	3700	3955.4	29590
CWS	All (main)	10	1250	681.8	5100
CWR	All (main)	10	1250	681.8	5100
CWS	All (main)	8	500	174.5	1306
CWR	All (main)	8	500	174.5	1306
Branch Piping (assume 5% of mains)					3600
22 Buildings Piping (estimate)					4400
SUBTOTAL ZONE 2					79992

A.10-34

ZONE 3

CWS	All (main)	24	4750	14922.6	111638
CWR	All (main)	24	4750	14922.6	111638
CWS	All (main)	18	3500	6185.0	46271
CWR	All (main)	18	3500	6185.0	46271
CWS	All (main)	12	900	706.9	5288
CWR	All (main)	12	900	706.9	5288
CWS	All (main)	16	550	767.9	5745
CWR	All (main)	16	550	767.9	5745
CWS	All (main)	14	550	588.0	4399
CWR	All (main)	14	550	588.0	4399
CWS	All (main)	10	1000	545.4	4080
CWR	All (main)	10	1000	545.4	4080
Branch Piping (assume 5% of mains)					17742
16 Buildings Piping (estimate)					3200
SUBTOTAL ZONE 3			22500		375784
Plant, Expansion Tanks, etc					5000
Total Estimated System Volume					601184 Gallons

1.0% of total volume lost per day = 6012 Gal/Day

6012 gal/day x 30 day/mo = 180355 Gal/Mo.

6012 gpd / 1440 min/day = 4.17 Gal/Min

100.0% of total volume lost per day = 601184 Gal/Day

601184 gal/day x 30 day/mo = 18035532 Gal/Mo.

601184 gpd / 1440 min/day = 417 Gal/Min

Repair History & Cost for the CHW Distribution System
Fort Stewart, GA
Filename: FSREPAIR.WQ1

Chilled Water System		
Date	Labor Hrs	Cost
10-17-94	3.4	\$92
10-19-94	11.0	\$304
10-19-94	5.0	\$135
12-09-94	2.9	\$79
12-09-94	2.8	\$76
3 MONTH	25.1	\$686
	x 4	x 4
	-----	-----
TOTALS	100.4	\$2,742



SUBJECT FORT STEWART
HTW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 1 OF _____
DATE 8-17-95
DATE _____

Estimate of HTW System Losses

The metered flow of makeup water for the HTW system was obtained from operating logs for 7/94 through 6/95. Flows for the three chemical treatment system were estimated based on conversations with CEP personnel. The total makeup water less the estimated boiler blowdown is the total system losses.

$$\text{HTW System Losses} = 15917 \text{ gal/day}$$

$$15917 \times 365 = 5,809,705 \text{ gal/year}$$

$$15917 \div 24 \div 60 = 11 \text{ gal/min}$$

Energy Losses

$$5809705 \frac{\text{gal}}{\text{yr}} \times 8.345 \frac{\text{lb}}{\text{gal}} \times 1 \frac{\text{Btu}}{\text{lb}^\circ\text{F}} \times (380 - 70)^\circ\text{F} = 15029 \frac{\text{MBtu}}{\text{yr}}$$

$$\text{Fuel use} = 15029 \frac{\text{MBtu}}{\text{yr}} \div 0.68 \text{ boiler eff.} = \underline{22,100 \frac{\text{MBtu}}{\text{yr}}}$$

$$\text{Fuel cost} = 22,100 \frac{\text{MBtu}}{\text{yr}} \times \$1.16/\text{MBtu} = \underline{\$25,640/\text{yr}}$$

Pumping Cost

$$\text{Pump BHP} = \frac{\text{GPM} \times \text{Head}}{3960 \times \text{eff}} = \frac{11 \times 300^*}{3960 \times 0.72^*} = 1.16 \text{ BHP}$$

* Data from record drawings 'A.10-37



SUBJECT FORT STEWART
HTW DIST. SYSTEM
DESIGNER WTT
CHECKER _____

AEP NO _____
SHEET 2 OF _____
DATE 8-18-95
DATE _____

Pumping cost - continued.

$$1.16 \text{ BHP} \times 0.746 \frac{\text{kw}}{\text{HP}} \div 0.90 \text{ motor eff} \times 8760 \frac{\text{hr}}{\text{yr}} = \underline{8404 \frac{\text{kwh}}{\text{yr}}}$$

$$\text{Cost} = 8400 \text{ kwh/yr} \times \$0.0500/\text{kwh} = \underline{\$420/\text{yr}}$$

Water Cost

$$5809705 \frac{\text{gal}}{\text{yr}} \times \frac{\$0.5562}{1000 \text{ gal}} = \underline{\$3,230/\text{year}}$$

Total Cost

$$\text{Total} = \text{Energy Cost} + \text{Pumping Cost} + \text{Water Cost}$$

$$\text{Total Cost} = \$25,640 + \$420 + \$3,230 = \underline{\$29,290/\text{yr}}$$

Fort Stewart Central Energy Plant
Boiler Makeup Water
Filename: FS-HTW1.WQ1

Month	Year	WS Makeup Gal(1)	Days/ Month	Makeup Gal/Day	S Makeup Gal/Day	M Makeup Gal/Day	P Makeup Gal/Day	Total Makeup Gal/Day
7	94	535250	31	17266	72	72	7200	24610
8	94	407100	31	13132	72	72	7200	20476
9	94	246220	30	8207	72	72	7200	15551
10	94	136384	31	4399	72	72	7200	11743
11	94	442980	30	14766	72	72	7200	22110
12	94	419160	31	13521	72	72	7200	20865
1	95	403424	31	13014	72	72	7200	20358
2	95	383366	28	13692	72	72	7200	21036
3	95	360940	31	11643	72	72	7200	18987
4	95	264078	30	8803	72	72	7200	16147
5	95	206480	31	6661	72	72	7200	14005
6	95	224254	30	7475	72	72	7200	14819
AVERAGES		335803		11048	72	72	7200	18392
TOTALS		4029636	gal/yr					

- (1) Source is Fort Stewart Boiler Operating Logs.
 WS - Water softener makeup water from meter readings.
 S - Sulfite (oxygen control) chemical feed makeup water estimate.
 M - Morpholine (PH control) chemical feed makeup water estimate.
 P - Phosphate (calcium control) chemical feed makeup water estimate.

Estimate Distribution System Losses:

18392	gpd, avg make-up water
- 2475	gpd, avg blowdown water *
<hr/>	
15917	gpd, avg dist system losses

* Boiler blowdown estimate:

	165	gpm
x	5	min/shift
	<hr/>	
	825	gal/shift
x	3	shift/day
	<hr/>	
	2475	gal/day

Fort Stewart Central Energy Plant
Energy Consumption
Filename: FS-ENRGY.WQ1

Month	Yr	Wood Tons (1)	Wood MBtu (2)	Wood Cost (2)	#2 Oil Gals (1)	#2 Oil MBtu (3)	#2 Oil Cost (3)	Used Oil Gals (4)	Used Oil MBtu (5)	Used Oil Cost (5)	N.Gas CuFt (1)	N.Gas MBtu (6)	N.Gas Cost (6)	Total MBtu	Total Cost
7	94	6052	74137	65483	75497	10645	46808	0	0	0	5572730	5701	18563	90483	130854
8	94	8169	100070	88389	13822	1949	8570	12956	1749	0	874295	894	2878	104662	99836
9	94	4969	60870	53765	40667	5734	25214	17703	2390	0	352500	361	1056	69355	80034
10	94	3947	48351	42707	42608	6008	26417	18775	2535	0	598230	611	1790	57504	70913
11	94	5000	61250	54100	15884	2240	9848	24298	3280	0	1082030	1107	3488	67877	67436
12	94	6631	81232	71749	22257	3138	13799	9470	1278	0	1366090	1398	4363	87046	89912
1	95	6100	74726	66003	39741	5603	24639	8891	1200	0	1027820	1049	3199	82579	93841
2	95	5024	61544	54360	110411	15568	68455	13181	1779	0	1159730	1186	3368	80078	126182
3	95	5723	70107	61923	19404	2736	12030	11576	1563	0	518890	530	1463	74935	75417
4	95	1869	22895	20223	550	78	341	0	0	0	12995190	13268	37455	36241	58019
5	95	5322	65195	57584	6525	920	4046	11324	1529	0	550120	563	1724	68207	63354
6	95	4768	58408	51590	11466	1617	7109	5476	739	0	2081740	2128	6435	62892	65134
AVERAGES		5298	64899	57323	33236	4686	20606	11138	1504	0	2348280	2400	7148	73488	85078
TOTALS		63574	778785	687874	398832	56235	247276	133650	18043	0	28179365	28796	85782	881859	1020931
AVG COST			\$0.88 /MBtu			\$4.40 /MBtu			\$0.00 /MBtu			\$2.98 /MBtu		\$1.16 /MBtu	

- (1) Source is Fort Stewart Operating Logs.
- (2) Assumes heating value of 6125 btu/lb; cost is \$10.82/ton.
- (3) Assumes heating value of 141000 btu/gal; cost is \$0.62/gal.
- (4) Source is monthly Oil Reports prepared at the CEP.
- (5) Assumes heating value of 18000 btu/lb, 7.5 lb/gal; no cost.
- (6) Uses heating value and cost from utility bills.


Fort Stewart Central Energy Plant
 Energy Production
 Filename: FS-ENRGY.WQ1

Month	Yr	Steam Prod k lb (1)	Steam Prod MBtu (2)	Fuel Input MBtu	Avg Eff (3)
7	94	60989	73187	90483	81%
8	94	62837	75404	104662	72%
9	94	44574	53489	69355	77%
10	94	43662	52394	57504	91%
11	94	38255	45906	67877	68%
12	94	49619	59543	87046	68%
1	95	55003	66004	82579	80%
2	95	50776	60931	80078	76%
3	95	45611	54733	74935	73%
4	95	34688	41626	36241	115%
5	95	37774	45329	68207	66%
6	95	40653	48784	62892	78%
AVERAGE		47037	56444	73488	79%
TOTALS		564441	677329	881859	

- (1) Source is Fort Stewart Operating Logs.
 (2) Total heat content of steam @ 200 psi is 1200 Btu/lb.
 (3) Calculated based on input and output data provided.

Available Energy In Wood

Source: Marks Mech Eng Hndbk, Pg 7-11



Heating Value of Wood Fuel
Filename: WOOD-HV.WQ1

Moisture Content, %	Heating Value, Btu/lb
0	8750
10	7875 *
20	7000
30	6125 *
40	5250 *
50	4375
60	3500 *
70	2625 *
80	1750

Source: Marks' Handbook for Mechanical Engineers
* These values were extrapolated.

Repair History & Cost for the HTW Distribution System
Fort Stewart, GA
Filename: FSREPAIR.WQ1

High Temperature System		
Date	Labor Hrs	Cost
04-08-94	5.0	\$125
04-11-94	4.0	\$100
04-11-94	14.0	\$321
04-11-94	3.6	\$90
04-13-94	4.6	\$135
10-27-94	14.2	\$501
11-04-94	1.9	\$51
11-17-94	6.0	\$2,703
03-01-95	7.0	\$175
TOTALS	60.3	\$4,202



Telephone Call Confirmation

912-767-8931

Project Number 694 1331 002

Local LD. Placed Rec'd 8-14-95 Date

Conversed with Randy Parks or Ft. Stewart CEP

Regarding HTW Makeup water & chemical treatment at CEP

The mixing tank for feedwater to the wood-fired boiler is used to add Morpholine and phosphate on a continuous basis.

The chemical feed systems for the other boilers are used to add sulphite and morpholine. They estimate the flow from these systems to be about 3 gal/hr each.

The existing makeup water meter does not include any of these chemical feed systems.

The HTW is tested for sulphite and pH. They try to keep the pH between 8.3 and 8.5 (9.3-9.9 is recommended). They try to keep the sulfite between 30 and 40 ppm.

Distribution:

A.10-45

Gas and Liquid Leak Detector

The XLT-16 is revolutionary in that it has both a sonic range to sense liquid leaks and an ultrasonic range to sense gaseous leaks. Both systems are within a very compact control box. Water companies and liquid leak detection professionals can make use of the ultrasonic range when they add air to a water system to cause a distinct "sputtering" at the leak location. Additional uses for the ultrasonic range are: to sense bearing wear, valve flow and seatings, corona discharge, leaking steam traps, and general mechanical trouble shooting. Do not use for detecting leaks of flameable gases.

Features

- Compact control box which can be worn: on the belt; around the neck or over the shoulder with the attachable strap.
- Both sonic and ultrasonic frequency ranges can be sensed for leaks.
- Minimum number of controls for a user-friendly control panel.
- Listening is loudness limited to lessen sudden blasts of uncomfortable sound.
- The "Big Foot" and Hydrophonic Cylinder Probes have three position switches for: (1) mute, (2) momentary on, or (3) locked on.
- The "Big Foot" probe is compact for access in tight areas.
- The carrying case holds all items of the basic set plus the two accessory transducers and a set of spare batteries (not included).

SPECIFICATIONS

Frequency		Batteries:	2 ea. 9 volt (NEDA 1604)
Sonic Range	Tuneable 100 Hz - 5 KHz	Battery Life:	20 hours - intermittent use with standard carbon zinc batteries
	Flat Band 100 Hz - 15 KHz		150 ohms
Ultrasonic Range	38 KHz - 42 KHz	Headset Impedance:	Weight:
			(In carrying case with both accessory transducers)
Listening Frequency for Both Ranges:	Tuneable 100 Hz - 5 KHz		(Carrying case)
	Flat Band 100 Hz - 15 KHz		7-1/4 x 19 x 15 inches
Gain:	65 dB	Size:	(18.4 x 48.2 x 38.1 cm.)
Type of Filter:	Tuneable and Flat Band		

Each Kit Includes:

Complete with carrying case, cushioned headphones, "Big Foot" probe, hydrophonic cylinder probe, three 16" sound rods, four inch sound rod, T-handle, coil cord, cassette recorded training tape, instruction book



ORDERING INFORMATION

Catalog No.	Model	Description	Price
FI096510	XLT-16	Leak Detector Kit	\$1125.00
FI096511	202352	Ultrasonic Probe	\$ 95.00
FI096512	202357	Little Foot Probe	\$ 225.00
FI096513	202374	25' Extension Cable For Ultrasonic Probe	\$ 35.00



DEDICATED UNIFLOW

**Better Performance, Reliability and Economy
than Magmeters, Vortex, Venturis, Turbines
and Orifice Plates in Most Applications.**

System 990N Uniflow Dedicated NEMA 4X Field Programmable Flow Computer

Large Digit LCD
Flow, Total, Analog
Barchart and Status
Display for each
Channel.
Dual Channel
Graphics Display
Optionally Available.

NEMA 4X Case,
suitable for
essentially all field
environments.
Intrinsically safe
models available.

Transducers mount
in either Direct or
Reflect Mode with
PinStop location
accuracy. Tracks
mount in just
minutes (shown
in Reflect Mode).

All printed circuit
modules, including
power supply,
plug-in for simple
function upgrade or
maintenance.

Weatherproof,
submersible, NEMA 4
Transducers are
intrinsically safe
(shown in
Direct Mode).

Stainless Steel
Track Mounting
Straps.

Use the 995T Hand-Held CDU to tell Uniflow the pipe size you want to work on, and what you want it to measure, display, record or control. It takes only minutes to setup a site and install transducers, and only seconds to recall a previously saved site. Used only for Site Setup and Installation, only one 995T Hand-Held CDU is needed to service many individual 990N NEMA 4 Systems.

The 996P Portable Thermal Printer features quiet, high-contrast printing. An RS-232C serial connector is provided for interconnection to a Flow Display Computer. A rechargeable battery allows printing up to 1,500 character lines, before recharging. This printer is provided in a convenient soft carry case.

A New Standard in Flowmeter Accuracy and Rangeability...

Made Possible by UNIFLOW's

MultiPulse™ and TransX™ Technology.

How UNIFLOW WORKS

Uniflow is a Clamp-On Flowmeter which detects liquid flow rate by its effect on the Transit-Time of Ultrasonic Pulses, alternatively injected through the pipe wall in the upstream and downstream directions by Controlotron's patented ultrastable metallic transducers. Each transmission is not a single pulse, as in prior types of ultrasonic flowmeters, but rather as many as 100 pulses, resulting in the extraordinary sensitivity and calibration stability of Uniflow's MultiPulse™ System.

Uniflow also benefits from its patented TransX™ Transmission System. This is a method by which Uniflow measures the sonic properties of the application's pipe, and automatically optimizes its ultrasonic beam transmission. This gives Uniflow its Universality, the ability to operate on most pipes and most liquids, and its extraordinary immunity to such conditions as liquid aeration and non-homogeneity.

How DOES UNIFLOW PERFORM?

EXTRAORDINARY PERFORMANCE

Uniflow's Digital MultiPulse™ System uses no analog circuits, not even phase locked loops. This produces the greatest precision, sensitivity and stability ever achieved in an ultrasonic flowmeter. Flow response is extremely linear over its full ± 40 fps range (including zero flow), and is virtually drift free.

Uniflow's SMARTSLEW™ real time data analysis results in extremely low data scatter, even at high slew rate settings. When set for its fastest flow response rate, Uniflow is ideal for flow control or detection of flow transients which would be missed by slower flowmeters. Slower response can be selected, if desired, to avoid reporting flow pulsations which are not of interest.

Uniflow intrinsic calibration accuracy is usually within 1% to 2% in most applications and within 1/4% to 1% if flow calibrated.* Intrinsic repeatability will generally be within 1/2% for most pipe sizes.

SYSTEM 990 UNIFLOW SPECIFICATIONS

APPLICABILITY

LIQUIDS: Any sonically conductive homogeneous liquid of low to moderate aeration (up to 30% maximum).

LIQUID (PIPE) TEMPERATURE: -40°F to $+250^{\circ}\text{F}$ (-40°C to $+120^{\circ}\text{C}$) Standard
 -80°F to $+450^{\circ}\text{F}$ (-60°C to $+230^{\circ}\text{C}$) Optional

PIPE SIZES: 0.25" to 8" OD (6.35mm to 203.2mm) Specify Group 2 Flow Computer
0.5" to 24" OD (12.7mm to 609.6mm) Specify Group 3 Flow Computer
0.5" to 48" OD (12.7mm to 1219.2mm) Specify Group 4 Flow Computer
0.5" to 216" OD (12.7mm to 5486.4mm) Specify Group 5 Flow Computer
0.5" to 360" OD (12.7mm to 9144mm) Specify Group 6 Flow Computer

PIPE MATERIAL: Any sonically conductive pipe material: Metal, Glass, Plastic, etc.

PIPE WALL THICKNESS: 0.01" to 3.00" (0.25mm to 76.2mm)

LINER MATERIAL: Any sonically conductive material, Glass, Plastic, Cement, etc., intimately bonded to the pipe interior.

LINER THICKNESS: Up to 1" (25.4mm), dependent on material.

FLOW VELOCITY RANGE: ± 40 fps ($\pm 12.2\text{m/sec}$), minimum

991 CLAMP-ON TRANSDUCERS

PIPE SIZE RATINGS:

- Group 0: 0.25" to 2" (6.35mm to 50.8mm) pipe OD
- Group 1: 0.5" to 4" (12.7mm to 101.6mm) pipe OD
- Group 2: 1.25" to 8" (31.75mm to 203.2mm) pipe OD
- Group 3: 6" to 24" (152.4mm to 609.6mm) pipe OD
- Group 4: 20" to 48" (508.0mm to 1219.2mm) pipe OD
- Group 5: 36" to 360" (914.4mm to 9144.0mm) pipe OD

RATING: Intrinsically safe. Radiation Resistant and Submersible available.

CONSTRUCTION: Aluminum, stainless steel and special alloy or plastic.

CONNECTORS: Condulet for NEMA 4, BNC for Portable.

992 MOUNTING TRACKS

- Available in Direct and Reflect Mounting for all transducer sizes in standard pipe diameter ranges.
- PinStop transducer spacing standard for all models.

994 FLOW COMPUTER

- **POWER:** 100/120 or 220/240 VAC, 1 ϕ , 40 VA
9 to 36 VDC, 20W, portable systems available with internal battery
- **TEMPERATURE:** -5°F to $+115^{\circ}\text{F}$ (-20°C to $+45^{\circ}\text{C}$)
(except for Graphics Models)
- **SIZE:** 10.5" W, 9" D, 13" H (266.7mm W, 228.6mm D, 330.2mm H)
- **WEIGHT:** 12.8 pounds (5.8 kilograms), (without Battery)
- **RATING:** Intrinsically safe. NEMA 4X with cover closed.
- **MODULES:** Plug-In, Interchangeable W/O special tools
- **RANGES:** Group 2: Transducer Sizes 0, 1 and 2
Group 3: Transducer Sizes 1, 2 and 3
Group 4: Transducer Sizes 1, 2, 3 and 4
Groups 5 & 6: Transducer Sizes 1, 2, 3, 4 and 5


994 PERFORMANCE (Standard Conditions)*

- **SENSITIVITY:** 0.001 fps (0.3mm/sec) at any flow rate including zero.
- **LINEARITY:** 0.003 fps (0.9mm/sec) under standard conditions.
- **DATA UPDATE RATE:** 10 Hz
- **SLEW RATE:** 0.1 to 40 ft/sec/sec (0.03 to 12.2m/sec/sec), (settable)
- **FLOW PROFILE COMPENSATION:** Reynold's Number 0 to 10^7
- **ZERO DRIFT STABILITY:** 0.02 fps (6mm/sec) for transducer sizes 0 to 2
0.01 fps (3mm/sec) for transducer sizes 3 to 5

995 HAND HELD CONTROL/DISPLAY TERMINAL


- 4 row, 80 character LCD
- 30 Keys, Numeric or Function identified

* Submit Application Form for estimate of performance under specific application conditions. For statement of accuracy, site survey is required.




VALVE PIT



A.10-49



5 TYPICAL CONDUIT VENT DETAILS
M-12 NOT TO SCALE




6 TYPICAL LINE VENT RISER
M-12 & AIR BOTTLE DETAILS
NOT TO SCALE




4 TYPICAL DRAIN PIT
 M-12 NOT TO SCALE

A.10-51




SECTION A-A

VALVE BOX



DETAIL WATER GENERATOR PIPING A M-10 M-9

NOT TO SCALE




NOTE:

USE FLANGED CONNECTIONS
WATER CONNECTIONS TO H.I

SECTION



A.10-54 SCALE: $\frac{1}{2}" = 1'-0"$



SECTION



A.10-55

SCALE: $\frac{1}{2}$ " = 1'-0"

